

PAKISTAN RAILWAYS



COMPOSITE SCHEDULE OF RATES (LAHORE DIVISION)

2016

PAKISTAN RAILWAYS HEADQUARTER OFFICE
LAHORE – PAKISTAN

PREFACE

After independence in 1947, the first Schedule of Rates for the Civil Engineering Department was issued by the then Railway Administration in 1954, under the title “Revised Schedule of Rates (RSR) 1954”. This document continued to be used up to year 1967.

During the years 1964 to 1967, the Standing Rates Committee constituted by the then Government of West Pakistan compiled and issued, a set of specifications including “Specifications for Materials of Construction” and “Specifications for Execution of Works”, along with “Composite Schedule of Rates” (based on these specifications), for adoption by all engineering departments in the province including Railways, which was under the Provincial Government at that time and was also a member of this Committee. The then Railway Administration adopted the above mentioned Specifications and the Composite Schedule of Rates in 1967.

Although Pakistan Railways became a Federal Government Department after 1971, but it continued to use the above mentioned publications up to 1990 when it issued its own “Pakistan Railways Composite Schedule of Rates-1990”, which was up-dated in 2003. This Schedule of Rates however continued to be based on the above referred Specifications, adopted by Railway Administration in 1967.

The Railway Administration decided in year 2010 to revise/update the above referred specification books, because in the first instance these documents had been prepared in 1964-1967, to meet the requirements of all the engineering departments of the province of West Pakistan including Buildings, Highways, Irrigation, WAPDA, Public Health and Agricultural Engineering, in addition to Railways and secondly these specifications had become more than four decades old.

The Railway Administration also decided at that stage to revise/update the Composite Schedule of Rates 2003, based on the above referred revised/updated specifications and also to prepare the Analysis of above mentioned revised/updated Composite Schedule of Rates, using appropriate computer software. Both the above stated assignments were awarded to ILF Pakistan (Private) Limited Lahore, a local consultancy firm.

Composite Schedule of Rates-2003 has now been revised / updated as ‘Composite Schedule of Rates-2016’ along with the preparation of the ‘Analysis of Composite Schedule of Rates-2016’, making maximum use of the appropriate computer software. The procedure adopted by the consultants for the development of requisite software and its utilization for the desired revision/updating of the Composite Schedule of Rates has been briefly described in it’s in the next section.

While compiling the revised/updated Composite Schedule of Rates-2016 and the Analysis of Composite Schedule of Rates-2016, the items of work included in each chapter of the Schedule of Rates-2003, were rearranged under appropriate sub-heads, to facilitate their referencing. The Table of Contents has also been expanded for this purpose.

The above mentioned revised/updated Composite Schedule of Rates and the Analysis of these Rates are being published, as under, separately for each railway division;

i) Pakistan Railways Composite Schedule of Rates-2016

ii) Analysis of Pakistan Railways Composite Schedule of Rates-2016 (in 2 volumes)

The existing specification books have also been revised/updated as “Specifications for Railway Infrastructure Works’ Volume-1 Structural Works-2016 and “Specifications for Railway Infrastructure Works’ Volume-II Roads and Road Works, Water Supply and Sewerage Works-2016. Since all the items of works included in different chapters of the Composite Schedule of Rates-2016 carry reference to relevant sections/sub-sections of the above referred Specification of Works, these books shall be issued separately as supplementary books for Composite Schedule of Rates-2016.

The Composite Schedule of Rates -2016 and Analysis of Composite Schedule of Rates -2016 has been issued with the approval of the Additional General Manager/Infrastructure. These shall come into effect from the date of their issue and thereafter their use shall be obligatory for the execution of all civil engineering works on Pakistan Railways.

In case the operation of a non-schedule item is considered unavoidable by any Chief Engineer/Project Director/ Managing Director/ Divisional Superintendent for the execution of a particular civil engineering work under his control, he will submit the detailed particulars of such item(s) along with the rate analysis and necessary justification, for the approval of Additional General Manager/Infrastructure, through Chief Engineer/Open Line. The sanction if and when accorded shall be notified by Chief Engineer/Open Line in the form a correction slip to the afore-said documents.

I, on behalf of the Railway Administration wish to express my thanks to all those who have contributed to the compilation of the above mentioned documents, particularly ILF Pakistan (Private) Limited, Lahore, the Consultants for this assignment.

Any suggestions to improve these publications would be welcome.

Lahore: January, 2016

(Farrukh Taimur Khan Ghilzai)
Chief Engineer (Open Line)
Pakistan Railways Headquarters Office,
Lahore.

INTRODUCTION

1.1 BRIEF BACKGROUND

Schedule of Rates is prepared by various engineering departments to provide a realistic reference base for the preparation of cost estimates and evaluation of bids/tenders/ variation orders/claims/bill of quantities etc for their various projects. It also provides a legal frame work for the execution of engineering works on contractual basis. Pakistan Railways Composite Schedule of Rates (CSR) in its present form was first compiled in year 1990 and revised in year 2003. It is being revised / updated now by using appropriate computer software.

1.2 RATES FOR CONSTRUCTION LABOUR/MATERIALS AND PLANT/MACHINERY

The rates of construction labour, construction materials and rental of plant/machinery adopted for the revision/updating of Pakistan Railways Composite Schedule of Rates-2003 have been based on the data collected from the sources described in the following sub-paragraphs.

1.2.1 Cost Data Issued by Pakistan Institute of Cost and Contracts (PICC) Lahore

Pakistan Institute of Cost and Contracts (PICC) Lahore was established in 2009, as a subsidiary of Pakistan Engineering Council (PEC) to function independently for the preparation and updating of web based cost of all construction inputs and to deal with the matters related to engineering contracts.

Through an amendment in Pakistan Engineering Council Act, 1975, PEC was also mandated, among other functions, to prepare, maintain and update the construction cost data for all construction related inputs. PICC accordingly prepared the Construction Cost Data for all the districts of Pakistan including AJ&K, which was being regularly updated and posted on its website very month. This website was unfortunately closed suddenly in September 2013, but is expected to be re-activated soon.

Accordingly, the above referred last published PICC Cost Data for the month of August 2013 was mostly used for the revision/updating of the CSR-2003. This Cost Data was however, updated in August 2015 through fresh market survey, wherever considered necessary. .

The cooperation extended by PICC/PEC in the above context is gratefully acknowledged.

1.2.2 Cost Data Issued by Finance Department Government of Punjab Lahore

The next preference was accorded to the cost data issued quarterly by Finance Department, Government of Punjab on their web-site This data comprises the estimat-

ed/projected rates of construction labour and construction materials for the prevalent quarter. As these rates are confined only to the districts of Punjab, they did not provide a uniform reference base across the country, and were generally used only in the cases where PICC cost data was not available.

The use of this data is also gratefully acknowledged.

1.2.3 Cost Data Published by Statistics Division Government of Pakistan, Islamabad

Similar cost data in respect of few selected categories of construction labour and construction materials for certain selected cities of Pakistan is also compiled by Statistics Division, Government of Pakistan and issued every month on their website- This data being of very limited nature in respect of construction industry was generally not used.

1.2.4 Cost Data collected through Market Surveys & other Sources

The cost data not available on the above referred web sites was mostly collected through market surveys and from other available sources.

1.3 DATA FILES OF RATES OF CONSTRUCTION LABOUR/MATERIAL & RENTAL OF PLANT/MACHINERY

Data files were prepared in Microsoft Excel software for each railway division, entering under allocated code numbers, the rates of applicable categories of construction labour, construction materials and rental of plant/machinery, based on the data collected under Para 1.2 above, for the civil district in which the office of relevant Divisional Superintendent was located.

1.4 SOFTWARE DEVELOPED IN MICROSOFT EXCEL FOR PREPARATION OF SCHEDULE OF RATES AND ITS ANALYSIS

A software was developed in Microsoft Excel, which picked up the rates of construction labor, construction materials and rental for plant/machinery from the corresponding data files of the respective railway divisions, referred to in para 1.3 above, while the quantities of these inputs had already been calculated for each item of work and their values entered in the relevant Microsoft Excel files of analysis of rates of the respective chapter of Composite Schedule of Rates (CSR)-2016 for the relevant division.

Following the procedure adopted during the preparation of Pakistan Railways Composite Schedule of Rates 1990, the labour cost calculated in the relevant Microsoft Excel file of analysis of rates was increased by 10% on account of "sundries" to cover charges on small T&P items used by the relevant labour. Another 10% was then added each on calculated costs of construction labour, construction materials and rental charges of plant/machinery, to cover contractor's profit and his overheads.

The above mentioned Microsoft Excel file for analysis of rates provided the output in the form of calculated unit rates (labour and composite) for the respective items of work and entered it in relevant file of Composite Schedule of Rates (CSR)-2016 through the linkages provided amongst the above mentioned three Microsoft Excel files.

These linkages ensure automatic revision of relevant rates in the Composite Schedule of Rates of a division, whenever a change is affected in any data file containing rates of construction labour or construction materials or rental of plant and machinery on that division.

The subject soft ware can also ensure that any change in the above mentioned data file shall be affected only by an authorized person.

1.5 ALLOCATION OF CODE NUMBERS TO ENTRIES IN DATA FILES

1.5.1 Code Numbers for Construction Man-power/Labour for Structural Works

Separate code numbers have been allocated to each category of man-power/labour of the contractor from X100-00-00 onward. The digit X represents the letter allocated to a particular division as stated below:

P for Peshawar Division

R for Rawalpindi Division

L for Lahore/Mughalpura Division

M for Multan Division

S for Sukkur Division

K for Karachi Division, and

Q for Quetta Division

These code numbers include only the manpower directly charged to the items of work. The man-power cost of the senior supervisors, administration & other non- productive work of support staff of a contractor is covered under his over-head charges.

1.5.2 Code Numbers for Construction Materials for Structural Works

Separate code numbers have been allocated to different construction materials from X200-00-00 onwards. The digit X represents the digit allocated to a particular division as described under para 1.5.1 above

1.5.3 Approved Sources of Important Construction Materials for Different Divisions

The rates of the construction materials like crushed stone and sand etc. included in the data files of the relevant divisions are inclusive of the charges for their transportation from their respective sources to the site of work, unless stated otherwise in the Composite Schedule of Rates -2016 and its Analysis.

The most appropriate source(s) of such materials have been considered for each division from the point of view of quality and economy. These sources will be approved and notified separately by Chief Engineer/Open Line for every division.

1.5.4 Code Numbers for Rental of Plant & Machinery for Structural Works

Small T & P items shall be charged under overheads of the contractors and only major T&P items have been allocated code number from 300-00-00 onwards.

The hiring charges of plant/machinery have been taken as same for each railway division, and as such its code number does not carry the digit x, representing the name of the respective railway division.

1.6 CONVERSION FACTORS

The basic document i.e. the Analysis of the Composite Schedule of Rates-2016 has been prepared in Microsoft Excel software in FPS units while its resultant output in the form of labour and composite rates has been entered in the corresponding book "Pakistan Railways Composite Schedule of Rates (CSR)-2016" in FPS as well as in SI (metric) units. The conversion factors used for this purpose are tabulated below:

To convert		Into		Multiply by
Length				
Inch	(in)	Millimetre	(mm)	25.400
Millimetre	(mm)	Inch	(in)	0.039
Inch	(in)	Centimetre	(cm)	2.540
Centimetre	(cm)	Inch	(in)	0.394
Foot	(ft)	Metre	(m)	0.305
Metre	(m)	Foot	(ft)	3.281
Mile	(mi)	Kilometre	(km)	1.609
Kilometre	(km)	Mile	(mi)	0.621
Area				
Square inch	(in ²)	Square centimetre	(cm ²)	6.452
Square centimetre	(cm ²)	Square inch	(in ²)	0.155
Square foot	(ft ²)	Square metre	(m ²)	0.093
Square metre	(m ²)	Square foot	(ft ²)	10.765
Square yard	(yd ²)	Square metre	(m ²)	0.836
Square metre	(m ²)	Square yard	(yd ²)	1.196

To convert	Into	Multiply by
Square metre (m ²)	Hectare (ha)	0,0001
Hectare	Square metre	10,000
Hectare (ha)	Acre (acr)	2.475
Acre (acr)	Hectare (ha)	0.404
Volume/Capacity		
Cubic inch (in ³)	Cubic centimetre (cm ³)	16.387
Cubic centimetre (cm ³)	Cubic inch (in ³)	0.061
Cubic feet (ft ³)	Cubic metre (m ³)	0.028
Cubic metre (m ³)	Cubic feet (cft)	35.320
Cubic yard (yd ³)	Cubic metre (m ³)	0.765
Cubic metre (m ³)	Cubic yard (yd ³)	1.307
Gallon (imperial) (gal)	Litre (lit)	4.546
Litre (l)	Gallon (imperial) (gal)	0.220
Mass/Weight		
Ounce (oz)	Gram (gm)	28.328
Gram (gm)	Ounce (oz)	0.035
Pound (lb)	Kilogram (kg)	0.454
Kilogram (kg)	Pound (lb)	2.204
Tonne (t)	Kilogram (kg)	1000
Kilogram (kg)	Tonne (mt)	0.001
Long ton (T)	Tonne (mt)	1.016
Tonne (mt)	Long ton (T)	0.984
Maund (Md)	Kilogram (kg)	37.324
Force/Stress/ Pressure		
Kilogram (force) (kgf)	Newton (N)	9.806
Pound (force) (lbf)	Newton (N)	4.448
Mega Pascal (MPa)	Newton/mm ² (N/mm ²)	1.000
Mega Pascal (MPa)	Pounds/inch ² (PSI)	145.038
Kilogram/cm ² (kg/cm ²)	Newton/mm ² (N/mm ²)	0.0981

1.7 MATERIALS REQUIRED FOR COMMON CONSTRUCTION ACTIVITIES

The estimated quantities of building materials required for common construction activities are generally taken as under:

1.7.1 Brick masonry (100 cft)

- a. No. of Bricks (9"x4 1/2"x3") = 1350 No.
- b. cement sand mortar (dry) = 30 cft.

1.7.2 Brick flooring, bricks laid flat (100 sft.)

- a. No. of Bricks (9"x4 1/2"x3") = 350 No.
- b. cement sand mortar (dry) = 08 cft.

1.7.3 Brick flooring, bricks laid on edge (100 sft.)

- a. No. of Bricks (9"x4 1/2"x3") = 500 No.
- b. cement sand mortar (dry) = 12 cft.

1.7.4 Stone masonry, random rubble-coursed (100 cft.)

- a. Stone = 125 cft.
- b. cement sand mortar (dry) = 42 cft.

1.7.5 Stone masonry, ashlar block/ashlar fine (100 cft.)

- a. Stone = 200 cft.
- b. cement sand mortar (dry) = 24 cft.

1.7.6 Cement Sand Plaster 1/2" (12 mm) thick (100 sft.)

- a. cement sand mortar (dry) = 06 cft.

1.7.7 Cement sand pointing for brickwork (100 sft.)

- a. cement sand mortar (dry) = 02 cft.

1.7.8 Cement concrete 1:2:4 (100 cft.)

- a. Cement = 22 cft (17.6 bags).
- b. Sand = 44 cft.
- c. Coarse Aggregate = 88 cft.

1.7.9 Bitumen 10/20 grade for coating on DPC or Roof (100 sft.)

a. One coat = 19 lbs.

b. Two coats = 34 lbs.

1.8 DATA FILES FOR RATES OF CONSTRUCTION LABOUR, MATERIALS & RENTAL OF PLANT/MACHINERY

The rates of construction labour, construction materials and rental of plant/machinery used in the compilation of the Composite Schedule of Rates-2016 for each railway division have been included in the two volumes of "Analysis of Composite Schedule of Rates-2016" for the respective railway divisions

1.9 SPECIFICATIONS FOR THE EXECUTION OF ITEMS OF WORKS INCLUDED IN THE COMPOSITE SCHEDULE OF RATES

The existing specification books have also been revised/updated as "Specifications for Railway Infrastructure Works' Volume-1 Structural Works-2016 and "Specifications for Railway Infrastructure Works' Volume-II Roads and Road Works, Water Supply and Sewerage Works-2016.

All the items of works included in different chapters of this Composite Schedule of Rates-2016 carry reference to relevant sections/sub-sections of the above referred books of "Specification for Railway Infrastructure Works". These books are as such also being issued separately as complementary books of Composite Schedule of Rates-2016.

TABLE OF CONTENTS		PAGE
PREFACE		i
INTRODUCTION		iii
1.	DISMANTLING WORKS	1
1.1	Dismantling of Stone Work	1
1.2	Dismantling of Brick Work	2
1.3	Dismantling of Concrete	2
1.4	Dismantling of Roofing / Ceiling	3
1.5	Dismantling of Flooring	4
1.6	Dismantling of Wood Work	5
1.7	Dismantling of Iron Work	6
1.8	Dismantling of Pipe Work	6
1.9	Dismantling of Miscellaneous Items	7
2.	CARRIAGE OF MATERIALS	8
2.1	Carriage of Building Materials (General)	9
2.2	Carriage of Bricks/Brick Tiles	10
2.3	Carriage of Cement Bags	11
2.4	Carriage of Bitumen, Tar & Lubricants	12
2.5	Hiring of Truck/Tractor Trolley	13
3.	LOADING, UNLOADING & STACKING	14
3.1	Loading/Unloading – Construction Materials	14
3.2	Loading/Unloading – POL Items	15
3.3	Loading/Unloading – Rail Track Materials	15
3.4	Loading/Unloading – Earth	17
3.5	Removing & Stacking of Materials	17
4.	EARTHWORKS	19
4.1	Site Clearance	19
4.2	Excavation-General	20
4.3	Excavation for Foundations/Trenches	22
4.4	Filling earth under floors / behind retaining Structures	25
4.5	Embankment with Excavated/Barrow Material	26
4.6	Dressing of Earthwork	27

	4.7	Re-handling & Carriage of Earth	28
	4.8	Miscellaneous Items	29
5.	CONCRETE		32
	5.1	Dry Rammed Brick/Stone Ballast	32
	5.2	Cement Concrete in Foundations	32
	5.3	Damp Proof Course (DPC)	33
	5.4	Plain Cement Concrete	35
	5.5	Shuttering for Plain Cement Concrete (vertical)	35
	5.6	Fabrication of Steel Reinforcement	36
	5.7	Reinforced/Pre-stressed Cement Concrete	37
	5.8	Other Precast Cement Concrete Works	39
	5.9	Admixtures	40
	5.10	Contraction/Expansion Joints	40
	5.11	Miscellaneous Items	41
6.	BRICK MASONRY		43
	6.1	Brick Work in Cement Sand Mortar	43
	6.2	Cement Concrete Block Masonry	45
	6.3	Brick Work for Cavity Walls	47
	6.4	Brick Work other than for Buildings	47
	6.5	Reinforced / Perforated Brick Work	49
	6.6	Other Special Brick Works	51
	6.7	Termite Proofing	52
	6.8	Miscellaneous Items	52
7.	STONE MASONRY		53
	7.1	Stone Masonry Works	53
	7.2	Dressing of Stones	55
	7.3	Miscellaneous Items	55
8.	ROOFING		57
	8.1	RCC Slab Roofing & Roof Insulation	57
	8.2	Pre-cast (Pre stressed Concrete Girders) /Slab Roofing	59
	8.3	Jack Arch Roofing	61
	8.4	Plain/Corrugated G.I Sheet Roofing	61
	8.5	Corrugated Asbestos Cement Sheet Roofing	62
	8.6	Fiber Glass (Corrugated and Plain) Roofing	63

	8.7	Roof Drainage Items	63
	8.8	Miscellaneous Items	65
9.	FLOORING		67
	9.1	Brick/Brick Tile Flooring/Paving	67
	9.2	Cement Concrete Tile Flooring / Skirting	68
	9.3	Cement Concrete Flooring	68
	9.4	Mosaic / Terrazo Flooring / Skirting	70
	9.5	Ceramic / Porcelin Tile Flooring / Skirting	72
	9.6	Marble & Granite Stone Flooring / Skirting and Marble slabs	74
	9.7	Wooden Flooring / Skirting	77
	9.8	Rubber / Venyle Tile Flooring	78
	9.9	Paver / interlocking Tile Flooring	78
	9.10	Miscellaneous Items	79
10.	SURFACE RENDERING		80
	10.1	Mud Plaster & Gobri Leeping	80
	10.2	Gypsum Plaster	80
	10.3	Cement Sand Plaster	80
	10.4	Cement sand Pointing	82
	10.5	Colour/Cement/ White Washing	83
	10.6	Distempering	84
	10.7	Extra for Work above 20 ft height	84
	10.8	Miscellaneous Items	85
11.	WOOD WORK		86
	11.1	Wood Work (General)	86
	11.2	Paneled & Glazed Doors & Windows	87
	11.3	Framed, Ledged, Braced, Battened Doors & Windows	89
	11.4	Wire Gauzed Doors & Windows	89
	11.5	Hallow & Solid Flush Doors	91
	11.6	Wooden / Steel Chowkats for Doors & Windows	92
	11.7	Wooden Almirahs/Wardrobes/Showcase/ Cabinets	92
	11.8	Wooden Planking/Shelves	93
	11.9	Fixing Glass Panes to Doors & Windows	94
	11.10	Doors & Windows Fixtures	94
	11.11	Wooden Partitions	96

	11.12	Wooden / Gypsum Borar / Thermopore False Ceiling	96
	11.13	Wooden Panelling	97
	11.14	Miscellaneous Items	98
12.	PAINTING & VARNISHING		99
	12.1	Cleaning & Scraping of Painted Surfaces	99
	12.2	Painting Old Surfaces	99
	12.3	Painting New Surfaces	101
	12.4	Painting with Emulsion Paint	103
	12.5	Polishing	104
	12.6	Varnishing	104
	12.7	Painting/Varnishing above 20 ft height	104
	12.8	Painting with Coal tar/ Bitumen Solignum & Creosote	104
	12.9	Miscellaneous Items	105
13.	STRUCTURAL STEEL/ALUMINIUM WORKS		106
	13.1	Fabrication of Small Steel Works	106
	13.2	Fabrication of Heavy Steel Works, i.e. Trusses, Girder & Tanks etc.	106
	13.3	Revitting Work	106
	13.4	Erection of Small/Heavy Steel Works	107
	13.5	Providing & Fixing Steel Doors & Windows	107
	13.6	Providing & Fixing Steel Railings	109
	13.7	Providing & Fixing Steel Grill for Windows	110
	13.8	Providing & Fixing Steel Gates	110
	13.9	Providing & Fixing Aluminum Doors & Windows	111
	13.10	Providing & Fixing Barbed Wire Fencing / Razor Wire Fencing	112
	13.11	Miscellaneous Items	113
14	PILE FOUNDATION		114
	14.1	Providing Cast-in-Situ RCC Piles	114
	14.2	Fabrication of Steel	116
	14.3	Testing of Piles	116
	14.4	Miscellaneous Items	116
15.	WELL FOUNDATION		117
	15.1	Excavation of Well in Dry	117
	15.2	Dry Sinking of Wells	118
	15.3	Wet Sinking of Wells	120

	15.4	Providing & Laying RCC Curbs	122
	15.5	Providing False Brick Masonry on Wells & its Dismantling	122
16.	PROTECTION & DIVERSION WORKS		123
	16.1	Cutting Pilchi, Farash & Sarkanda, making bundles and launching them in position	123
	16.2	Supplying jute bags, filling them with sand/earth and laying them in position.	124
	16.3	Supplying boulders, Munj or Patha Trungers & G.I. Wire nets	125
	16.4	Supplying and Dumping at site Boulders/Brick Bats etc. without Boats	126
	16.5	Supplying and Dumping Boulders/Brick Bats with Boats	127
	16.6	Providing and Laying Pilchi Revetment	127
	16.7	Providing and laying Stone Pitching	128
	16.8	Miscellaneous Items	129
17	ROAD AND ROAD STRUCTURES		130
	17.1	Sub-Base Course	130
	17.2	Base Course	131
	17.3	Bitumen Work & Surfacing	132
	17.4	Dry Brick Pavement/Soling	134
	17.5	Road Edging	134
	17.6	Supply & Fixing Cats Eye	134
18.	INSTALLATION OF TUBE WELLS		135
	18.1	Percussion Drilling for Tube Well	135
	18.2	Direct Rotary/Reverse Rotary Drilling in Common Soil	137
	18.3	Direct Rotary/Reverse Rotary Drilling in Shingle & Gravel	137
	18.4	Collection & Preservation of Coring and Water Samples from Bore Holes	138
	18.5	Providing & Installing Brass Strainers	138
	18.6	Providing & Installing M.S Bail Plug	139
	18.7	Providing & Installing M.S Blind Pipe	140
	18.8	Shrouding of Tube Well Bore with Gravel	141
	18.9	Testing/Developing of Tube Well	141
	18.10	Supplying & Erecting DWT Pumps	141
19.	WATER SUPPLY		142
	19.1	Providing & Laying Cast Iron Pipes	142
	19.2	Providing & Fixing Cast Iron Specials/Fixtures	143
	19.3	Providing & Laying Galvanized Iron (GI) Pipes	144

	19.4	Providing and Laying Unplasticised Polyvinyle Chloride (UPVC) Pressure Pipes	146
	19.5	Providing and Laying Polypropylene Random Copolymer (PPRC) Pipes & Fittings	147
	19.6	Providing & Fixings Hand Pumps & Pressure Pipes	147
	19.7	Supply and Installation of Water Pumps	148
	19.8	Supply and installation of water storage tanks (polyethylene) Blue.	149
20.	PLUMBING AND SANITARY INSTALLATIONS		150
	20.1	Providing & Fixing Water Closets, Urinals & other Sanitary Ware.	150
	20.2	Providing & Fixing Sinks, Wash Hand Basin, Bath Tubs	155
	20.3	Providing & Fixing Various Valves, Cocks & Traps	156
	20.4	Providing & Laying Soil Waste & Vent Pipes	158
	20.5	Providing & Fixings C.I Manhole Covers	160
	20.6	Providing & Laying RCC Pipe in Trenches	160
	20.7	Providing & Laying G.I Pipe & Fittings	160
	20.8	Miscellaneous Items	161
21.	SEWERAGE & RCC PIPE SEWERS		163
	21.1	Providing & Laying Reinforced Concrete Pipes (RCC) in Trenches	163
	21.2	Providing & Laying Non-Reinforced Concrete Pipes in Trenches	166
	21.3	Lowering of Sub Soil Water Table & Laying of Pipe Sewers in Trenches	167
	21.4	Construction of Gully Grating Chamber with Gully Trap	168
	21.5	Providing Manhole Chambers & Manhole Covers	168
	21.6	De-silting of Disposal Works, Collecting Tanks & Wells	169
22.	SUI GAS WORKS		170
	22.1	Supplying & Laying High Pressure Sui Gas Pipeline	170
	22.2	Supplying & Laying Low Pressure Sui Gas Pipeline	171
	22.3	Supplying & Fixing in Position Sui Gas Appliances & their Fittings	171
	22.4	Supplying & Fixing in Position Valves/Cocks etc.	173
23.	MISCELLANEOUS WORKS		174
	23.1	Miscellaneous Works	174
	BIBLIOGRAPHY		177

CHAPTER 1**DISMANTLING WORKS**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 2-Dismantling Works of "Specification for Railway Infrastructure Works, Volume I, (2016)".
- (2) Rates for all "Dismantling Works" include the lowering/removal of surplus debris, unused released material and by-products and stacking them within 100 ft (30 m).
- (3) The rates for dismantling roofs or upper storey floors, include the dismantling of all materials, except roof supports such as beams and trusses.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
1.1 Dismantling of Stone Work				2.3 & 2.4	
1.1.1 Dismantling dry stone masonry.	100 cft (m ³)	494 174			
1.1.2 Dismantling stone masonry in mud mortar.	100 cft (m ³)	726 256			
1.1.3 Dismantling stone masonry in lime or cement mortar.	100 cft (m ³)	1742 615			Add extra 13%, 32% and 51% on labour rates only for heights from 14.1 to 26 ft, 26.1 to 38 ft, 38.1 to 50 ft and above, and for 2nd, 3rd and subsequent floors of 12 ft height respectively on item 1.1.3
1.1.4 Dismantling pitching stone:-					
(a) Dry stone or spawl pitching	100 cft (m ³)	871 308			
(b) Stone or spawl pitching (mud grouted)	100 cft (m ³)	1104 390			
1.1.5 Dismantling stone pitching or spawl and apron in silted condition.	100 cft (m ³)	1452 513			
1.1.6 Dismantling stone pitching, cement or lime grouted.	100 cft (m ³)	2323 821			
1.1.7 Dismantling stone in crates:-					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) In wooden crates	100 cft (m ³)	1162 410			
(b) In wire crates	100 cft (m ³)	1452 513			
1.1.8 Dismantling Dhajji walling.	100 cft (m ³)	581 205			
1.2 Dismantling of Brick Work				2.3 & 2.4	
1.2.1 Dismantling brick work in mud mortar.	100 cft (m ³)	1016 359			Add extra 13%, 32% and 51% on labour rates only for heights from 14.1 to 26 ft, 26.1 to 38 ft, 38.1 to 50 ft and above, and for 2nd, 3rd and subsequent floors of 12 ft height respectively on items 1.2.1 to 1.2.3.
1.2.2 Dismantling brick work in lime or cement mortar.	100 cft (m ³)	2468 872			
1.2.3 Dismantling cement block masonry in cement mortar.	100 cft (m ³)	2178 769			
1.3 Dismantling of Concrete				2.3 & 2.4	
1.3.1 Dismantling lime concrete.	100 cft (m ³)	1597 564			Add extra 13%, 32% and 51% on labour rates only for heights from 14.1 to 26 ft, 26.1 to 38 ft, 38.1 to 50 ft and above, and for 2nd, 3rd and subsequent floors of 12 ft height respectively on items 1.3.1, 1.3.2 & 1.3.3.
1.3.2 Dismantling Plain Cement Concrete:-					
(a) Cement concrete with brick or stone aggregate (1:5:10)	100 cft (m ³)	1742 615			
(b) Cement concrete plain 1:4:8	100 cft (m ³)	3194 1128			
(c) Cement concrete plain 1:3:6	100 cft (m ³)	5227 1846			
(d) Cement concrete plain 1:2:4	100 cft (m ³)	6389 2257			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(e) Cement concrete with iron filling	100 cft (m ³)	6970 2462			
(f) Cement concrete with rail grillage, separating rails from concrete and clearing the same.	100 cft (m ³)	6970 2462			
1.3.3 Dismantling reinforced cement concrete and separating reinforcement from concrete.	100 cft (m ³)	8131 2872			
1.4 Dismantling of Roofing/Ceiling				2.3 & 2.4	
1.4.1 Dismantling tile roofing upto 14ft height.	100 sft	726			(i) Add extra 13%, 32% and 51% on labour rates only for heights from 14.1 to 26 ft, 26.1 to 38 ft, 38.1 to 50 ft and above, and for 2nd, 3rd and subsequent floors of 12 ft height respectively on items 1.4.1, 1.4.2, 1.4.4
1.4.2 Dismantling asbestos sheets and ridge coping up to 14 ft height.	100 sft (m ²)	532 57.3			
1.4.3 Dismantling wooden roofs & ceilings:-					
(a) Dismantling wooden roof of wooden planks and battens, upto any height.	100 sft (m ²)	426 45.9			
(b) Extra for dismantling wooden ceiling above 26' height and in difficult position, including lifting with care and using special scaffolding along live electric wires and with machines underneath.	100 sft (m ²)	847 91			
1.4.4 Dismantling jack arch roofing complete with mud and mud plaster, including removal of joists.	100 sft (m ²)	1162 125			
1.4.5 Dismantling reinforced brick roof complete with mud and mud plaster, including separating reinforcement up to any height.	100 sft (m ²)	1162 125			
1.4.6 Stripping slates or tiles from the truss roofing at any height.	100 sft (m ²)	726 78.2			
1.4.7 Stripping corrugated G.I. sheet from truss roofing at any height.	100 sft (m ²)	697 75.0			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
1.4.8 Stripping corrugated G.I. sheet from other than truss roofing at any height.	100 sft (m ²)	348 37.5			
1.4.9 Extra for dismantling corrugated G.I. sheet roof above 26 ft (8 m) and in difficult position including lifting with special scaffolding along live electric wires with machine underneath.	100 sft (m ²)	1113 119.8			
1.4.10 Dismantling slates or tile roofing including battens, purlins and planking at any height.	100 sft (m ²)	1162 125			
1.4.11 Dismantling precast roofs of any height consisting of;					
(a) Precast prestressed concrete girders & slabs	100 sft (m ²)	1162 125			
(b) Prestressed concrete double Tee planks	100 sft (m ²)	581 62.5			
1.4.12 Dismantling and removing north light glasses upto any height.	100 sft (m ²)	290 31.3			
1.4.13 Dismantling false ceiling of any type upto any height.					
(a) With wooden framework	100 sft (m ²)	968 104.2			
(b) With Aluminium framework	100 sft (m ²)	378 40.6			
1.5 Dismantling of Flooring				2.3 & 2.4	Add extra 13%, 32% and 51% on labour rates only for 2nd, 3rd and subsequent floors of 12 ft height respectively on items 1.5.1, 1.5.2 and 1.5.4 to 1.5.6
1.5.1 Dismantling brick flooring without concrete foundation.	100 sft (m ²)	494 53.1			
1.5.2 Dismantling planks or wooden block flooring etc.	100 sft (m ²)	726 78.2			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
1.5.3 Dismantling interlocking paver flooring including removing of sand but excluding dismantling of base concrete.	100 sft (m ²)	581 62.5			
1.5.4 Dismantling mosaic, marble and all kinds of tile flooring (except glazed tiles), excluding base concrete.	100 sft (m ²)	581 62.5			
1.5.5 Dismantling mosaic, marble and all kinds of tile skirting complete (excluding glazed tiles).	100 sft (m ²)	726 78.2			
1.5.6 Dismantling glazed tiles, flooring.	100 sft (m ²)	968 104			
1.6 Dismantling of Wood Work				2.3 & 2.4	
1.6.1 Removing wooden doors and windows:-					Add extra 13%, 32% and 51% on labour rates only for heights from 14.1 to 26 ft, 26.1 to 38ft, and 38.1 to 50ft and above and for 2nd, 3rd and subsequent floors of 12 ft height respectively on items 1.6.1 to 1.6.7
(a) Removing wooden door with chowkat	100 sft (m ²)	1337 143.9			
(b) Removing wooden window and sky lights with chowkat	100 sft (m ²)	968 104.2			
(c) Removing iron grill in openings and wall	100 sft (m ²)	968 104.2			
1.6.2 Removing ventilators and wooden sunshades etc.	each	102			
1.6.3 Dismantling wooden beams upto 12' in length	each	145			
1.6.4 Dismantling wooden beams from 12.1' to 23' length	each	290			
1.6.5 Dismantling wooden partition jaffry work etc.	100 sft (m ²)	304 32.8			
1.6.6 Dismantling wooden trusses	100 kg	661			
1.6.7 Dismantling wooden almirah work in any position and floor.	100 sft (m ²)	304 32.8			Measurements shall be for surface area of front of Almirah.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
1.7 Dismantling of Iron Work				2.3 & 2.4	
1.7.1 Dismantling iron work or trusses, sheds, water tanks, etc. including cutting of rivets, upto any height.	100 kg	903			
1.7.2 Dismantling rolled steel beams or rails etc. upto any height					
(a) Heavy work	100 kg	581			
(b) Light work	100 kg	381			
1.7.3 Dismantling water column on broad gauge (B.G) sections.	each	6098			
1.7.4 Dismantling all types of wire fencing, including rolling wire into bundles and	100 sft (m ²)	116.2 12.5			
1.7.5 Dismantling steel grating of any size in any position and any floor including stacking within 100 ft (30 m).	100 kg	929			
1.8 Dismantling of Pipe Works					
1.8.1 Disjointing R.C.C. pipes inside the trench and dismantling and removing the pipe with fittings from the trench and stacking them outside:-					(i) The rate does not include cost of excavation & refilling of trench, or the demolition of any masonry or brick work for item 1.8.1 to 1.8.3
(a) 4" to 12" diameter	Rft (m)	19.4 63.5			
(b) 13" to 24" diameter	Rft (m)	31.0 101.6			
(c) 25" to 36" diameter	Rft (m)	43.6 143			(ii) Dismantling of sockets, tees, elbows, bends, crosses, unions and plugs etc., is included in the rates for item 1.8.1 to 1.8.3
(d) Above 36" diameter	Rft (m)	62.0 203			
1.8.2 Dismantling and stacking within one chain GI, CI, AC and plastic pipes with fittings in any position and any height excluding digging and refilling of trenches:-					
(a) Upto 4" dia	Rft (m)	10.6 34.9			
(b) From 4.1" to 9" dia	Rft (m)	16.0 52.4			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(c) From 9.1" dia to 12" dia	Rft (m)	21.3 69.9			
1.8.3 Dismantling sluice valves upto 12" bore.	each per inch bore	21.5			
	each per cm bore	8.5			
1.9 Dismantling of Miscellaneous Items				2.3 & 2.4	Add extra 13%, 32% and 51% on labour rates only for heights from 14.1 to 26 ft, 26.1 to 38 ft, 38.1 to 50 ft and above, and for 2nd, 3rd and subsequent floors of 12 ft height respectively on items 1.9.3 & 1.9.5
1.9.1 Dismantling and removing road metalling.	100 cft (m ³)	1162 410			
1.9.2 Dismantling and removing road pavement etc including screening and stacking of by-products upto one chain lead.	100 cft (m ³)	1510 533			
1.9.3 Removing cement sand plaster from walls.	100 sft (m ²)	194 20.8			
1.9.4 Cleaning mortar of old bricks to be used in brick masonry.	1000 bricks	1016			
1.9.5 Removing of white/colour wash.	100 sft (m ²)	116 12.5			

CHAPTER 2

CARRIAGE OF MATERIALS

Notes:

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 3 Carriage of Materials of "Technical Specifications for Railway Infrastructure Works, Volume I, (2016)"
- (2) Carriage of material for distance less than one mile shall be normally done by cart & beyond one mile carriage shall invariably be done by truck/tractor trolleys.
- (3) For carriage of material upto 1200 ft (330 m), the relevant carriage rates per chain shall be paid. In case carriage exceeds 1200 ft (360 m), the relevant carriage rates for first 1/4 mile (1st 400 m) and subsequent 1/4 miles (400 m) shall be paid, up to one mile.
- (4) The rates for carriage of materials other than those included in this chapter may be calculated on the basis of their equivalence to 100 cft of volume or 5 tons of weight of the respective items included in this chapter.
- (5) The rates included in this chapter are applicable to carriage of material on pacca roads only. For Kacha roads an allowance of 25% extra shall be allowed for 2nd mile (2nd 1.6 km) and subsequent miles (1.6 km) rates. Rate upto 1st mile (1.6 km) is however common to both kacha and pacca roads.
- (6) For hilly areas 25% above the rates in the plain areas shall be allowed for total distance covered.
- (7) In case of articles longer than 15 ft (4.6 m) carried in trucks/tractor trolleys, the following rates shall be allowed.
 - (i) 15.1 ft to 25 ft (4.6 to 7.5 m): Rate to be paid will be 1.5 times of the rate given in this chapter.
 - (ii) Above 25 ft (7.5 m): Rate to be paid will be 2 times of the rate given in this chapter.

The length measured shall not be the actual length, but the length of the form of consignment as actually received for carriage.
- (8) The term '**mile (kilometer)**' whenever used is to mean statute mile (kilometer).
- (9) The rates for carriage of materials include their loading & unloading and their stacking as directed.
- (10) The rates for carriage by boat or steamer shall be the same as by any other mechanical means on land.
- (11) The term "**chain**" whenever used is to mean 100 linear feet (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
2.1 Carriage of Building Materials (General)				3.2 & 3.3	
2.1.1 Carriage of 100 cft (2.83 m ³) of all materials like stone aggregate, spawl, kankar, brick bats, lime (unslaked), surkhi, sand etc. or 200 cft (5.66 m ³) of timber, by truck or by any other means owned by the contractor.					
(a) 1st Chain (1st 30 m)	chain (m)	136 4.47			This rate will be paid for lead upto 1200 ft (360m) lead beyond 1200ft shall be paid as per items (d) & onward (for 1st and subsequent 1/4 mile /miles).
(b) 2nd Chain (2nd 30 m)	chain (m)	23.9 0.78			
(c) 3rd to 12th Chain (60 m -360 m)	chain (m)	14.3 0.47			
(d) 1st 1/4 mile (400 m)	1/4 mile (100 m)	376 94.0			
(e) 2nd and subsequent 1/4 mile (400 m) upto 1 mile (1.6 km)	1/4 mile (100 m)	31.7 7.93			
(f) 2nd mile (1.6 - 3.2 km)	mile (km)	110.3 68.9			
(g) 3rd mile (3.21 - 4.8 km)	mile (km)	97.8 61.1			
(h) 4th mile (4.81 - 6.4 km)	mile (km)	88.1 55.1			
(i) 5th mile (6.41 - 8.0 km)	mile (km)	80.6 50.4			
(j) 6th mile (8.01 - 9.6 km)	mile (km)	74.5 46.6			
(k) 7th mile and subsequent mile (9.61 km & beyond)	mile (km)	46.0 28.7			
2.1.2 Carriage of 1 ton of all material like, rails, fastenings, points and crossing, girders, pipe, sheets, M.S. bars, etc. by truck or any other means owned by the contractor:-					The word "Pipe" covers G.I., C.I., R.C.C., P.C.C., PPRC/PVC pipe etc.
(a) 1st Chain (1st 30 m)	chain (m)	27.3 0.89			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) 2nd Chain (2nd 30 m)	chain (m)	4.8 0.16			
(c) 3rd to 12th Chain (60 m - 360 m)	chain (m)	2.86 0.09			
(d) 1st 1/4 mile (400 m)	1/4 mile (100 m)	75.2 18.8			
(e) 2nd and subsequent 1/4 mile (400 m) upto 1 mile (1.6 km)	1/4 mile (100 m)	6.35 1.59			
(f) 2nd mile (1.61 - 3.2 km)	mile (km)	22.1 13.8			
(g) 3rd mile (3.21 - 4.8 km)	mile (km)	19.6 12.2			
(h) 4th mile (4.81 - 6.4 km)	mile (km)	17.6 11.0			
(i) 5th mile (6.41 - 8.0 km)	mile (km)	16.1 10.1			
(j) 6th mile (8.01 - 9.6 km)	mile (km)	14.9 9.3			
(k) 7th mile and subsequent mile (9.61 km & beyond)	mile (km)	9.2 5.7			
2.2 Carriage of Bricks/Brick Tiles				3.2 & 3.3	
2.2.1 Carriage of 1000 bricks, 9" x 4-1/2" x 3" (Nominal Size) or 1000 brick tiles 12" x 6" x 2":-					
(a) 1st Chain (1st 30 m)	chain (m)	85.2 2.80			
(b) 2nd Chain (2nd 30 m)	chain (m)	14.9 0.49			
(c) 3rd to 12th Chain (60 m -360 m)	chain (m)	8.95 0.29			
(d) 1st 1/4 mile (400 m)	1/4 mile (100 m)	104 25.9			
(e) 2nd and subsequent 1/4 mile (400 m) upto 1 mile (1.6 km)	1/4 mile (100 m)	11.6 0.12			
(f) 2nd mile (1.61-3.2 km)	mile (km)	42.1 26.3			
(g) 3rd mile (3.21-4.8 km)	mile (km)	38.7 24.2			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(h) 4th mile (4.81-6.4 km)	mile (km)	260 163			
(i) 5th mile (6.41-8.0 km)	mile (km)	50 31			
(j) 6th mile (8.01-9.6 km)	mile (km)	46.6 29.1			
(k) 7th mile and subsequent mile (9.61 km & beyond)	mile (km)	28.7 18.0			
2.2.2 Carriage of 1000 Nos. brick tiles, 9"x 4-1/2" x 1-1/2":					
(a) 1st Chain (1st 30 m)	chain (m)	42.6 1.40			
(b) 2nd Chain (2nd 30 m)	chain (m)	7.46 0.24			
(c) 3rd to 12 th Chain (60 m -360 m)	chain (m)	4.47 0.15			
(d) 1st 1/4 mile (400 m)	1/4 mile (100 m)	81.5 20.4			
(e) 2nd and sbsequent 1/4 mile (400 m) upto 1 mile (1.6km)	1/4 mile (100 m)	7.67 1.92			
(f) 2nd mile (1.61 - 3.2 km)	mile (km)	27.1 16.9			
(g) 3rd mile (3.21 - 4.8 km)	mile (km)	24.4 15.3			
(h) 4th mile (4.81 - 6.4 km)	mile (km)	22.4 14.0			
(i) 5th mile (6.41 - 8.0 km)	mile (km)	20.7 13.0			
(j) 6th mile (8.01 - 9.6 km)	mile (km)	19.4 12.1			
(k) 7th mile and subsequent mile (9.61 km & beyond)	mile (km)	13.3 8.3			
2.3 Carriage of Cement Bags				3.2 & 3.3	
2.3.1 Carriage of 100 nos. 50 kg cement bags:-					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) 1st Chain (1st 30 m)	chain (m)	136 4.47			
(b) 2nd Chain (2nd 30 m)	chain (m)	23.9 0.78			
(c) 3rd to 12th Chain (60 m - 360 m)	chain (m)	14.32 0.47			
(d) 1st 1/4 mile (400 m)	1/4 mile (100 m)	261 65.2			
(e) 2nd and subsequent 1/4 mile (400 m) upto 1 mile (1.6 km)	1/4 mile (100 m)	24.6 6.14			
(f) 2nd mile (1.61 - 3.2 km)	mile (km)	86.8 54.2			
(g) 3rd mile (3.21 - 4.8 km)	mile (km)	78.2 48.9			
(h) 4th mile (4.81 - 6.4 km)	mile (km)	71.6 44.7			
(i) 5th mile (6.41 - 8.0 km)	mile (km)	66.4 41.5			
(j) 6th mile (8.01 - 9.6 km)	mile (km)	62.2 38.9			
(k) 7th mile and subsequent mile (9.61 km & beyond)	mile (km)	42.6 26.6			
2.4 Carriage of Bitumen, Tar & Lubricants				3.2 & 3.3	
2.4.1 Carriage of bitumen, tar or other lubricants in drums:-					For carriage beyond 3 mile (4.8 km) proportional rate based on item 2.1.2 above be paid
(a) 1st mile (1st 1.6 km)	per ton	66.9			
(b) 2nd mile (1.6 - 3.2 km)	per ton	17.4			
(c) 3th mile and subsequent mile (3.2 km and beyond)	per ton	15.6			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
2.5 Hiring of Truck/Tractor/ Tractor Trolley				3.2 & 3.3	
2.5.1 Hire charges of:-					
(a) Truck (8 ton capacity)	per day	4000			(i) This item will be allowed with prior approval of Divisional Superintendent.
(b)Tractor (Fiat-480) and Trolley with Jack,Capacity 7 m ³	per day	6400			(ii) The rate includes pay of driver and cleaner, repairs, if any.
(c)Tractor (Fiat-480) and Trolley without Jack,Capacity 7 m ³	per day	4800			(iii) Cost of lubrication, fuel, loading & unloading shall be paid by borrower.
(d) Tractor with rotater blade	per day	4800			(iv) The day means the duration of 8 hrs.

CHAPTER 3**LOADING, UNLOADING & STACKING**

Note.-

- (1) The rate for loading into and unloading from mobile trucks, trolleys and boats, etc. will be the same as for Railway wagons.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
3.1 Loading/Unloading - Construction Materials					
3.1.1 "Loading into or unloading from railway wagons, shingle, sand, ashes, kankar, brick bats, coal and lime etc. including stacking, lead up to one chain (30 m)	100 cft (m ³)	726 256			
3.1.2 "Loading into or unloading from railway wagons, including stacking, lead up to one chain (30 m) of:					
(a) Bricks 9" x 4-1/2 x 3" or brick tiles 12" x 6" x 2"	1000 no.	454			
(b) Brick tiles 9" x 4-1/2" x 1-1/2"	1000 no.	227			
(c) Concrete solid blocks 6"x8"x12"	1000 no.	2420			
(d) Concrete hollow blocks 6"x 8"x 16"	1000 no.	2074			
3.1.3 Loading into or unloading from railway wagons, cement in 50 kg bags (from inside or outside the godown) and stacking, lead upto one chain (30 m).	100 no.	726			
3.1.4 Loading into or unloading from railway wagons, structural steel, R.S. joists, rails and rail fastenings, etc. lead upto one chain (30 m).	per ton	348			
3.1.5 Loading into or unloading, from railway wagons, 45 gallon filled drums, lead upto one chain (30 m).	Each	43.6			
3.1.6 Loading into or unloading from railway wagons, packages of all sorts, upto one cwt (50 Kg), lead upto one chain (30m)	Each	21.8			Except cement in jute or paper bags.
3.1.7 Loading into or unloading from railway wagons pitching stone or spawl, including clearing 5ft. away from rails.	100 cft (m ³)	215 75.9			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
3.2 Unloading - POL Items					
3.2.1 Unloading oil, bitumen, tar, from railway wagons					
(a) Crude oil (to be pumped from tank wagon into tank)	1000 gln (1000 lit)	348 77			
(b) Crude oil (drained by gravity)	1000 gln (1000 lit)	908 200			
(c) Crude oil materials from railway wagons, including stacking within one chain (30 m) lead.	100 cft (m ³)	116.2 41.0			
(d) Fuel oil from tank into empty tins/drums, including stacking within one chain (30 m) lead.	per ton	332			
(e) Petrol/Kerosine oil in 4 gallon tins, including stacking within one chain (30 m) lead.	100 no.	944			
(f) Tar and bitumen in drums	per ton	363			The rate includes checking and weighing the tins.
3.3 Loading/Unloading - Rail Track Materials					
3.3.1 Loading into or unloading from railway wagons sleepers other than wooden and concrete, including stacking, lead within one chain (30 m).					
(a) Broad gauge sleepers	100 no.	1815			
(b) Metre gauge and narrow gauge sleepers.	100 no.	908			
3.3.2 Loading into or unloading from railway wagons timber logs or timber for shuttering, including stacking, lead within one chain (30 m).	per ton	242			
3.3.3 Loading into or unloading from railway wagons timbers scraps or wooden plugs and stacking within one chain (30 m) lead.	per ton	363			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
3.3.4 Loading into railway wagons girders, rails, permanent way material (except wooden sleepers), iron work, M.S. bars, Pipes, etc. including lead one chain (30 m) and stacking inside wagons.	per ton	465			
3.3.5 Unloading from railway wagons girders, rails, permanent way material (except wooden sleepers), iron works, M.S. bars, pipe, etc. including one chain (30 m) lead but excluding stacking.	per ton	232			
3.3.6 Loading into railway wagons wooden broad gauge sleepers including one chain (30 m) lead and stacking.	100 no.	1452			
3.3.7 Unloading from railway wagons wooden broad gauge sleepers including one chain (30 m) lead excluding stacking.	100 no.	1162			
3.3.8 Loading into railway wagons metre gauge or narrow gauge wooden sleepers including one chain (30 m) lead and stacking inside wagons.	100 no.	774.4			
3.3.9 Unloading from railway wagons metre gauge or narrow gauge wooden sleepers, including one chain (30 m) lead but excluding stacking.	100 no.	387.2			
3.3.10 Loading into railway wagons, bridge and crossing timbers, including one chain (30 m) lead and stacking.	100 no.	2904			
3.3.11 Unloading from railway wagons bridge and crossing timbers, including one chain (30 m) lead but excluding stacking.	100 no.	1452			
3.3.12 Loading into railway wagons wooden blocks for sleepers including one chain (30 m) lead and stacking.	100 no.	545			
3.3.13 Unloading from railway wagons wooden blocks for sleepers from wagons including one chain (30 m) lead but excluding stacking.	100 no.	290			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
3.3.14 Loading into railway wagons B.G. cement concrete sleepers including one chain (30 m) lead and stacking:-					
(a) R.C.C. Twin block sleepers.	100 no.	5328			
(b) P.S.C. Sleepers.	100 no.	6453			
3.3.15 Unloading from railway wagons B.G. cement concrete sleepers including one chain (30 m) lead but excluding stacking:-					
(a) R.C.C. Twin block sleepers	100 no.	2904			
(b) P.S.C. Sleepers	100 no.	3319			
3.4 Loading and Unloading - Earth					
3.4.1 Unloading earth from railway wagons and clearing upto 5ft (1.5 m) from rail.	100 cft (m ³)	218 76.9			
3.4.2 Unloading earth from railway wagons and spreading upto 15ft (4.5 m) from rail.	100 cft (m ³)	363 128			
3.5 Removing & Stacking of Materials					
3.5.1 Removing and stacking within one chain (30 m) lead:-					
(a) Stone, spawl, brick bats, brick tiles/concrete blocks of sizes, shingle, sand, lime, surkhi, ashes, Kankar, coal etc:	100 cft (m ³)	363 128			
(b) Bricks 9" x 4-1/2" x 3" or brick tiles 12" x 6" x 2".	1000 no.	1056			
(c) Brick tiles 9" x 4-1/2" x 1-1/2"	1000 no.	528			
(d) Broad gauge wooden sleepers	100 no.	581			
(e) Meter gauge or narrow gauge wooden sleepers	100 no.	332			
(f) Rails, girders, pipes, cement, structural steel, etc.	per ton	166			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(g) Bridge and crossing timbers, etc.	100 no.	1936			
(h) Wooden Blocks for sleepers	100 no.	218			
(i) B.G. Concrete sleepers of all kinds	100 no.	2904			

CHAPTER 4**EARTHWORKS**

Notes.-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 4 Earthwork of "Technical Specifications for Railway Infrastructure Works, Volume I, (2016)"
- (2) The application of rates given in this chapter for excavation in hard soil, wet soil, slush, daldal and flowing water will be subject to the prior approval of concerned Divisional/Executive Engineer.
- (3) The application of rates given in this chapter for excavation in soft rock, medium hard rock and hard rock shall be subject to the prior approval of Chief Engineer, on the basis of geological investigation report of the relevant project site.
- (4) The following allowances for shrinkage should be provided for earth work which is not compacted, or evenly consolidated:-
 - (a) Deduction for shrinkage from the bank measurements when the earthwork is done by manual labour or tractor trolly = 10%
 - (b) Deduction for settlement from the bank measurements when the earthwork is done by heavy earth moving machinery = 5%
 - (c) No deduction for shrinkage shall be made for earth work carried out and tested for 95% or above modified AASHTO dry density.
- (5) The prescribed field and laboratory tests for the earthwork and its compaction will be arranged by the contractor at his own expenses .
- (6) The rates for earth work are inclusive of charges such as royalty and all other such charges, where ever involved.
- (7) In case of earthwork measurement, where extra lift is to be paid in terms of lead reference may be made to Annexure 1 of this chapter.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
4.1 Site Clearance				4.6.2,	
4.1.1 Clearing and grubbing of sites including removal of stumps, roots, bushes, trees less than 6" (150 mm) girth and objectionable materials upto 12" (300 mm) in depth and disposal of materials within 100 ft (30 m) lead, as per drawings and in accordance with the specifications.	100 sft m ²	254 27.3		4.6.3, 4.6.4, 4.6.5, 4.6.6	
4.1.2 Cutting of trees, removal and disposal of roots and stumps within 100 ft (30 m) lead, including filling of holes and compaction to required degree, complete in accordance with the specifications.					Uprooting stumps of trees less than 6" (150 mm) girth is included in the relevant rate for earthwork excavation.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
a) Above 6" (150 mm) and up to 12" (300 mm) girth	No.	436			
b) Above 12" (300 mm) and up to 2.0' (600 mm) girth	No.	726			
b) Above 2.0' (600 mm) girth	No.	1452			
4.1.3 Cutting and Clearing of bush stumps, shrubs, roots, logs and trees less than 6" (150 mm) girth and disposal of material within 100 ft (30 m) lead as per drawings and in accordance with the specifications.					
(a) Trees of Light Concentration	100 sft (m ²)	36.3 3.90			
(b) Trees of Thick Concentration	100 sft (m ²)	54.5 5.85			
4.1.4 Stripping and Removal of top soil to required depth and disposal of stripped material in stock pile or spreading at designated area, within 100 ft (30 m) lead, complete as per drawings and in accordance with the specifications.	100 cft (m ³)	290 102.57			
4.2 Excavation - General					
4.2.1 Earth work excavation as per designed section, grade, lines and profiles, undressed, including disposal of excavated material upto single throw of kassi, in accordance with the specifications.				4.6.6, 4.8.3, 4.8.4, 4.8.5, 4.8.6,	
(a) In ashes, sand, soft soil or silt clearance.	100 cft (m ³)	272 96.2			
(b) In ordinary soil.	100 cft (m ³)	327 115.4			
(c) In hard soil or soft Stratum.	100 cft (m ³)	436 154			
4.2.2 Excavation as per designed section, grade, lines & profiles, undressed, including disposal of excavated material upto 100 ft (30 m) lead & lift upto 5 ft (1.5 m) in accordance with the specifications					
(a) In ashes, sand, soft soil or silt clearance.	100 cft (m ³)	399 141			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) In ordinary soil.	100 cft (m ³)	472 167			
(c) In hard soil or soft Stratum.	100 cft (m ³)	581 205			
4.2.3 Borrow pit excavation, undressed, lead upto 100 ft (30 m) and lift upto 5ft (1.5 m) in accordance with the specifications					
(a) In ordinary soil.	100 cft (m ³)	508 179			
(b) In hard soil or soft murum.	100 cft (m ³)	624 221			
(c) In shingle and gravel formation	100 cft (m ³)	799 282			
4.2.4 Extra for excavation in wet soil.	100 cft (m ³)	254 89.7			
4.2.5 Extra for excavation in slush or daldal	100 cft (m ³)	363 128			
4.2.6 Extra for excavation in flowing water	100 cft (m ³)	508 179			
4.2.7 Excavation in rock dressed to designed section, grade, line and profile in accordance with the specifications including the disposal of excavated material upto 100 ft (30 m) lead & lift upto 5 ft (1.5 m).					(i) Tools and plants required shall be the liability of contractor.
(a) In soft rock, slate, shale, schist or latrite, which can be excavated with pick and crow bar.	100 cft (m ³)	835 29.5			(ii) Reduce the rate by 8% if the excavated section is not dressed or levelled to designed section
(b) In medium hard rock, requiring occasional blasting.	100 cft (m ³)	1149 406	1228 434		
(c) In hard rock requiring blasting	100 cft (m ³)	1936 68.4	2233 78.9		
4.2.8 Excavation in hard rock requiring blasting but blasting prohibited, dressed to designed section, grade, lines and profile in accordance with the specifications including disposal of excavated material upto 100 ft (30 m) lead and lift upto 5 ft (1.5 m).	100 cft (m ³)	3872 1368	4466 1578	4.8.4	(i) Tools and plants required shall be the liability of contractor.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
					(ii) Reduce the rate by 8% if the excavated section is not dressed or levelled to designed section.
4.3 Structural & Trench Excavations				4.8.4, 4.9, 4.10, 4.11, 4.12	
4.3.1 Structural excavation for foundation of buildings, bridges and other structures upto 5 ft (1.5 m) depth including dagbelling, dressing, refilling around structures with excavated earth, watering and ramming, lead upto 100 ft (30 m) complete in all respects.					
(a) In sand, ashes or loose soil.	100 cft (m ³)	678 239			
(b) In ordinary soil.	100 cft (m ³)	799 282			
(c) In hard soil or soft moorum.	100 cft (m ³)	895 316			
4.3.2 Structural excavation for foundation of buildings, bridges and other structures from 5.1 ft upto 10.0 ft (1.51 - 3.0 m) depth including dagbelling, dressing, refilling, around structure with excavated earth, watering and ramming, lead upto 100 ft (30 m) complete in all respect.					
(a) In sand, ashes or loose soil.	100 cft (m ³)	750 265			
(b) In ordinary soil.	100 cft (m ³)	871 308			
(c) In hard soil or soft moorum.	100 cft (m ³)	968 342			
4.3.3 Structural excavation for foundation of buildings, bridges and other structures upto 5 ft (1.5 m) depth including dagbelling, dressing, refilling, around structure with excavated earth, watering and ramming, lead upto 100 ft (30 m) complete in all respects.					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) In soft rock, slate, shale, schist or laterite work, with pick and crow bar.	100 cft (m ³)	1016 35.9			
(b) In medium hard rock requiring occasional blasting.	100 cft (m ³)	1270 449	1349 477		
(c) In hard rock requiring blasting,	100 cft (m ³)	2081 735	2378 840		
4.3.4 Structural excavation for foundation of buildings, bridges and other structures in hard rock (requiring blasting but blasting not permitted) upto 5 ft (1.5 m) depth including dagbelling, dressing, refilling, around structure with excavated material, including raming, lead upto 100 ft (30 m) complete in all respects	100 cft (m ³)	4162 1470	4757 1680		Tools and plants required shall be the liability of the contractor.
4.3.5 Extra for excavation requiring shoring.	100 cft (m ³)	103 36.3	124 43.9		Composite rate includes material i.e., planks etc.
4.3.6 Trench excavation in open cutting for sewers and manholes chambers to the designed section, lines, grade and profile according to drawings & specifications and disposal of excavated material within 100 ft. (30m) and dressing in specified manner including shuttering, timbering and removing surface water, in all types of soil, except shingle, gravel and rock:-					
(a) 0 ft to 5.0 ft (0 to 1.52 m) depth.	100 cft (m ³)	610 216	638 225		(i) The rate does not include back filling after laying sewer, which is payable separately under item 4.3.8 below
(b) 5.01 ft to 10.0 ft (1.52 to 3.04 m) depth.	100 cft (m ³)	1018 360	1059 374		
(c) above 10.0 ft (3.04 m) depth.	100 cft (m ³)	1308 462	1350 477		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
4.3.7 Trench excavation in open cutting for sewers and manhole chambers, etc. below sub-soil water level to the designed section, line, grade and profile according to drawings & specifications including shoring, timbering and shuttering M.S. sheets on both sides of the trenches including removal / lowering of sub-soil water, in all types of soil, except shingle, gravel and rock:-					ii)The rate does not include backfilling after laying sewers which is payable separately under item 4.3.8 below.
(a) 0 ft to 4.0 ft (0 to 1.2 m) depth below SSWL	100 cft (m ³)	986 348	1184 418		
(b) 4.01 ft to 8.0 ft (1.2 to 2.4 m) depth below SSWL	100 cft (m ³)	1233 435	1443 510		
(c) exceeding 8 ft (2.4 m) depth below SSWL	100 cft (m ³)	1849 653	2077 734		
4.3.8 Back filling of excavated earth in trenches in all types of soil including dressing, levelling, compaction, etc. and lead upto one chain.	100 cft (m ³)	460 162			
4.3.9 Trench excavation for water supply pipeline upto 5 ft (1.5 m) depth from ground level to the design section, line, grade and profiles according to drawings & specifications in all types of soils, except rock.	100 cft (m ³)	557 197			
4.3.10 Trench excavation in open cutting up to 5' -0" ft depth for storm water channels/drain and sullage drains in open areas, roads, streets and lanes, including under pinning of walls and shoring to protect existing work, shuttering and timbering the trenches, dressed to design level and dimensions, trimming, removal of surface water from trenches, back filling, disposal and dressing of surplus excavated material within 100 ft (30 m) lead, complete.					
(a) In Ordinary soil	100 cft (m ³)	583 206	590 208		
(b) In hard soil	100 cft (m ³)	682 241	691 244		
(c) In gravel and Shingle / Soft rock not requiring blasting	100 cft (m ³)	974 344	986 348		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
4.3.11 Trench excavation in open cutting 5 - 01 ft to 10 - 0 ft (1.5 to 3.0 m) depth for storm water channels/drains and sullage drains in open areas, roads, streets and lanes including under pinning of walls and shoring to protect existing work, shuttering and timbering the trenches, dressed to design level and dimensions, trimming, removal of surface water from trenches, back filling, disposal and dressing of surplus excavated material within 100 ft (30 m) lead complete.					
(a) In ordinary Soil	100 cft (m ³)	633 224	658 232		
(b) In hard Soil	100 cft (m ³)	730 258	760 268		
(c) In gravel and shingle / soft rock not requiring blasting	100 cft (m ³)	1057 373	1084 383		
4.4 Filling Earth under Floors / behind Retaining Structures				4.9, 4.10.12, 4.11.10 & 4.12.7	
4.4.1 Filling, watering and ramming earth under floors:-					
(a) With surplus earth from foundation, etc.	100 cft (m ³)	387 137			
(b) With new earth excavated from outside the structure	100 cft (m ³)	895 316			
4.4.2 Ramming earth work behind retaining walls.	100 cft (m ³)	145 51			
4.4.3 Providing & filling coarse grained granular backfill, without admixture of fine particles, clean and permeable behind the abutments/retaining walls, of approved gradation and source, compacted in layers with approved mechanical means, including all lead, lift, carriage, dressing to designed section/ profile, complete in all respect.	100 cft (m ³)	439 155	4399 1554		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
4.5 Embankment with Excavated/Barrow Material				4.6.6, 4.6.7, 4.8.7 & 4.12.5	
4.5.1 Earth work for embankment in ordinary soil with excavated material, lead upto 300 ft (90 m) including placing of earth in layers, ploughing & mixing with blade, grader, or disc horrow or other suitable equipment and compaction by mechanical means at optimum moisture content and dressing to designed section, lines, grade and profile according to drawings & specifications complete in all respects.					The "excavated material" includes all suitable material removed from excavation for railway formation, excavations from barrowpits in railway land and surplus material from structural excavations.
(a) 95% to 100% maximum modified AASHTO dry density	100 cft (m ³)	571 202	669 236		
(b) 90% maximum modified AASHTO dry density	100 cft (m ³)	543 192	636 225		
(c) 85% maximum modified AASHTO dry density.	100 cft (m ³)	515 182	604 213		
4.5.2 Compaction of earth work available at site of work, including placing of earth in layers, ploughing & mixing with blade, grader, or disc horrow or other suitable equipment and compaction by mechanical means at optimum moisture content, dressing to designed section, lines, grade and profile according to drawings & specifications complete in all respects.					The rate also includes hire charges of machinery, cost of fuel, lubricant, pay of driver and cleaner, etc., but excludes the cost of supply of earth at site of work.
(a) 95% to 100% maximum modified AASHTO dry density.	100 cft (m ³)	62.9 22.2	161 57.0		
(b) 90% maximum modified AASHTO dry density.	100 cft (m ³)	59.8 21.1	153 54.1		
(c) 85% maximum modified AASHTO dry density.	100 cft (m ³)	56.8 20.1	146 51.4		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
4.5.3 Compaction of natural ground including ploughing & mixing with blade, grader, or disc harrow or other suitable equipment and compaction by mechanical means at optimum moisture content, dressing to designed section, lines, grade and profile according to drawings & specifications complete in all respects. with power roller as per drawing and in accordance with the specifications.					
(a) 95% to 100% maximum modified AASHTO dry density.	100 sft (m ²)	31.5 3.39	80.6 8.68		
(b) 90% maximum modified AASHTO dry density.	100 sft (m ²)	29.9 3.22	76.6 8.25		
(c) 85% maximum modified AASHTO dry density.	100 sft (m ²)	26.9 2.90	71.3 7.67		
4.5.4 Mixing, moistening earth to optimum moisture content in layers for compaction, etc, complete.	100 cft (m ³)	94.4 33.3			
4.5.5 Compaction by rolling with animal/hand driven roller including all charges complete:-					
(a) Soft, or sandy soil	100 cft (m ³)	90.8 32.1			
(b) Ordinary soil	100 cft (m ³)	108.9 38.5			
(c) Hard soil	100 cft (m ³)	127 44.9			
(d) Admixture of shingle	100 cft (m ³)	145 51.3			
4.6 Dressing of Earthwork				4.12	
4.6.1 Dressing of earthwork excavated to designed section and profile etc, complete:-					
(a) Ashes, sand, silt or soft soil	100 cft (m ³)	28.1 9.92			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) In ordinary or hard soil.	100 cft (m ³)	57.1 20.2			
(c) In gravel work or soft rock not requiring blasting.	100 cft (m ³)	133.1 47.0			
4.6.2 Dressing of slopes:-					
(a) Dressing slopes of banks or ground surface.	100 sft (m ²)	127 13.7			To be paid only when exclusively dressing is done and no earthwork is carried out in embankment or cutting.
(b) Dressing of earthwork (done by machinery or otherwise and left undressed) to designed section.	100 sft (m ²)	145 15.6			(i) The surface area dressed is to be taken for measurement. (ii) The item is applicable where the dressing is done by the contractor other than the one who executed the work.
4.7 Re-handling & Carriage of Earth				4.6.26 & 4.6.27	
4.7.1 Rehandling of excavated earth, lead upto a single throw of kassi.	100 cft (m ³)	182 64.1			
4.7.2 Rehandling of excavated earth manually/ by cart, lead upto 50 ft (15 m):-					
(a) For earth work soft, ordinary and hard soil	100 cft (m ³)	254 89.7			
(b) For gravel, shingle or rock	100 cft (m ³)	363 128			
4.7.3 Extra for every 50 ft (15 m) additional lead or part thereof:-					
(a) for earth work soft, ordinary, hard and very hard	100 cft (m ³)	14.51 5.12			This rate shall be applicable upto 1000 ft (300 m) total distance, including the lead covered in the item of earthwork.
(b) for gravel, shingle or rock	100 cft (m ³)	17.4 6.15			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
4.8.5 Plantation of grass on slopes of banks or lawns with grass sods including ploughing, laying, setting and watering (Turf got from within a distance of 5 miles (8 km) and maintenance for 15 days) including cost of DACCA/CHINA Grass	100 sft (m ²)	1278 138	1617 174		
4.8.6 Extra for clay puddling.	100 cft (m ³)	363 128			
4.8.7 Removing earth from roofs lowering to ground and disposed with in one chain (30 m) lead.	100 cft (m ³)	407 144			
4.8.8 Bailing out water:-					
(a) by hand	100 cft (m ³)	218 76.9			Rate to be operated only for very small quantities.
(b) by pump	100 cft (m ³)	26.5 9.35	42.4 15.0		Rate includes cost of providing pump, POL and operation charges etc.

ANNEXURE - A to Chapter- 4
CONVERSION OF LIFT INTO LEAD

In the case of earthwork measurement where extra lead is to be paid in lieu of lift, the method will be as follows:

The lift will be measured from the centre of gravity of the excavated earth to that of placed earth. This will constitute the mean lift for the section.

When earth has to be carried over a spoil bank and dumped beyond it the mean lift would be the difference in level between the centre of gravity of the excavated earth and the top of the spoil bank omitting the dowel.

The equivalent leads for various mean lifts are given below:

Lift in feet	Conversion factor	Equivalent Horizontal lead in feet
1	1' lift 8' lead	8
2	1' lift 8' lead	16
3	1' lift 8' lead	24
4	1' lift 8' lead	32
5	1' lift 10' lead	50
6	1' lift 10' lead	60
7	1' lift 10' lead	70
8	1' lift 10' lead	80
9	1' lift 11' lead	99
10	1' lift 12' lead	120
11	1' lift 13' lead	143
12	1' lift 14' lead	168
13	1' lift 15' lead	195
14	1' lift 16' lead	224
15	1' lift 17' lead	255
16	1' lift 18' lead	288
17	1' lift 19' lead	323
18	1' lift 20' lead	360
19	1' lift 21' lead	399
20	1' lift 22' lead	440
21	1' lift 23' lead	483
22	1' lift 24' lead	528
23	1' lift 25' lead	575
24	1' lift 26' lead	624
25	1' lift 27' lead	675
26	1' lift 27' lead	702
27	1' lift 27' lead	729
28	1' lift 27' lead	756
29	1' lift 27' lead	783
30	1' lift 27' lead	810

These conversion factors also incorporate allowance for extra lead due to cross lead with a view to ensure a uniform system. The equivalent lead will be added to the horizontal lead to get the total lead to be paid for. The exact site or R.D.s between which extra lead is to be given must be recorded in the first column of detailed measurements in the measurement book.

CHAPTER 5**CONCRETE**

Notes:

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 5 "Concrete" of " Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and stacking them within 100 ft (30 m).
- (3) If concrete mixer or high frequency vibrator, etc., is supplied by the department, all charges including depreciation will be recovered from the contractor.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.1 Dry Ramming of Brick/Stone Ballast				5.2.1	
5.1.1 Providing and laying dry rammed stone ballast 1-1/2" (40 mm) to 2" (50 mm) gauge.	cft (m ³)	29.0 1025	65.3 2306		
5.1.2 Providing and laying dry rammed brick ballast 1-1/2" (40 mm) to 2" (50 mm) gauge.	cft (m ³)	29.0 1026	59.3 2094		
5.2 Cement Concrete in Foundations				5.2.1, to 5.2.3 5.2.6,5.4	
5.2.1 Providing and laying cement concrete with stone ballast 1-1/2" (40 mm) to 2" (50 mm) gauge in foundation and plinth:-					
(a) Ratio 1:3:6	cft (m ³)	53.2 1880	162 5715		
(b) Ratio 1:4:8	cft (m ³)	53.2 1880	147 5181		
(c) Ratio 1:5:10	cft (m ³)	53.2 1880	138 4862		
(d) Ratio 1:6:12	cft (m ³)	53.2 1880	130 4609		
5.2.2 Providing and laying cement concrete with brick ballast 1-1/2" to 2" gauge in foundation and plinth:-					
(a) Ratio 1:3:6	cft (m ³)	53.2 1880	157 5532		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Ratio 1:4:8	cft (m ³)	53.2 1880	141 4995		
(c) Ratio 1:5:10	cft (m ³)	53.2 1880.4	132 4671		
(d) Ratio 1:6:12	cft (m ³)	53.2 1880	125 4419		
5.2.3 Extra on item No. 5.2.1 & 5.2.2 above, for sedimentation tank or filter beds:-					
(a) in bed	cft (m ³)	18.8 662			
(b) on slope	cft (m ³)	26.6 940			
5.3 Damp Proof Course (DPC)				6.5.3	
5.3.1 Providing and laying damp proof course of cement concrete 1:2:4 nominal mix (using cement, sand and shingle/crushed stone), including bitumen coating:-					The rate includes overlaps of polythene sheet.
(a) With one coat of bitumen 10/20 grade @ 19 lbs per 100 sft and polythene sheet 500 gauge.					
(i) 1-1/2" (40 mm) thick	sft (m ²)	24.2 261	62.8 676		
(ii) 2" (50 mm) thick	sft (m ²)	24.2 261	70.1 755		
(iii) 3" (75 mm) thick	sft (m ²)	25.4 274	86.2 928		
(b) with two coats of bitumen 10/20 grade @34 lbs/100 sft and ploythene sheet 500 gauge.					
(i) 1-1/2" (40 mm) thick	sft (m ²)	24.2 261	70.0 753		
(ii) 2" (50 mm) thick	sft (m ²)	24.2 261	77.6 835		
(iii) 3" (75 mm) thick	sft (m ²)	25.4 274	93.7 1008		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.3.2 Providing and laying damp proof course horizontal or vertical with cement sand plaster and bitumen coating:-					The rate includes overlaps of polythene sheet
(A) With one coat of bitumen 10/20 grade @19 lbs/100 sft and polythene sheet 500 gauge;					
(a) Cement sand plaster ratio 1:4;					
(i) 1/2" (12 mm) thick.	sft	18.2	37.7		
	(m ²)	195	406		
(ii) 3/4" (19 mm) thick	sft	18.2	40.3		
	(m ²)	195	434		
(b) Cement sand plaster ratio 1:3;					
(i) 1/2" (12 mm) thick.	sft	18.2	38.5		
	(m ²)	195	414		
(ii) 3/4" (19 mm) thick	sft	18.2	41.2		
	(m ²)	195	444		
(c) Cement sand plaster ratio 1:2;					
(i) 1/2" (12 mm) thick	sft	18.2	39.9		
	(m ²)	195	430		
(ii) 3/4" (19 mm) thick	sft	18.2	44.0		
	(m ²)	195	474		
(B) With two coats of bitumen 10/20 grade @34 lbs/100 sft and polythene sheet 500 gauge;					
(a) Cement sand plaster ratio 1:4;					
(i) 1/2" (12 mm) thick	sft	18.2	44.7		
	(m ²)	195	481		
(ii) 3/4" (19 mm) thick	sft	18.2	47.3		
	(m ²)	195	509		
(b) Cement sand plaster ratio 1:3;					
(i) 1/2" (12 mm) thick.	sft	18.2	45.5		
	(m ²)	195	490		
(ii) 3/4" (19 mm) thick	sft	18.2	48.2		
	(m ²)	195	519		
(c) Cement sand plaster ratio 1:2;					
(i) 1/2" (12 mm) thick.	sft	18.2	47.4		
	(m ²)	195	511		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(ii) 3/4" (19 mm) thick	sft (m ²)	18.2 195	51.5 554		The rate includes overlaps.
5.3.3 Supplying and laying polythene sheet over DPC under floors and on roofs etc.					
(a) 300 gauge (.003" thick)	sft (m ²)	1.82 19.5	4.00 43.1		
(b) 500 gauge (.005" thick)	sft (m ²)	2.18 23.4	5.48 59.0		
5.3.4 Laying 2" thick sand and bitumen carpet, with bitumen 10/20 grade mixed with sand in the ratio of 4% , on top of foundation of oil tank.	sft (m ²)	15.7 169	41.2 443		
5.4 Plain Cement Concrete				5.2.1 to 5.2.3 5.2.6 & 5.4	
5.4.1 Providing cement concrete plain using coarse sand and screened graded & washed aggregate of approved quality including placing compacting, finishing, curing, complete as per specifications without shuttering on ground floor of buliding and for structrues up to 20ft height.					
(a) Nominal mix 1:2:4	cft (m ³)	60.0 2120	235 8308		
(b) Nominal Mix (1:3:6)	cft (m ³)	60.0 2120	170 6021		
(c) Nominal Mix (1:4:8)	cft (m ³)	60.0 2120	153 5421		
5.4.3 Extra for using sulphate resistant cement.	per bag		55.0		
5.5 Shuttering for Plain Cement Concrete (vertical)				5.4.9	
5.5.1 Providing vertical wooden/steel shuttering for plain cement concrete works, including its erection and removal complete.	sft (m ²)	26.6 287	44.4 478		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.6 Fabrication of Steel Reinforcement				5.3, 5.6	
5.6.1 Providing and laying mild steel reinforcement including the cost of straightening, cutting, bending, binding, wastage, and overlaps as are not shown in the drawing, placing in position on cement concrete 1:2:4 spacers or MS chairs, tying them with binding wire, complete in all respects as per drawing and in accordance with the specifications.				5.3	The rate includes wastage over laps and chairs, etc.
(a) Deformed bars (Grade 40) conforming to ASTM A-615, $f_y=40,000$ Psi/276 N/mm ² (Mpa)	per kg	7.74	102		For fabrication of steel reinforcement for pile foundations refer to chapter 14
(b) Deformed bars (Grade 60) $f_y= 60,000$ Psi/ 412 N/mm ² (Mpa)	per kg	9.68	108		
(c) Plain bars 1/4" dia (Grade -36) $f_y=36,000$ Psi/248 N/mm ² (Mpa)	per kg	7.74	94.6		
5.6.2 Providing and laying high tensile steel prestressing cable conforming to ASTM A-416 for prestressed (post tensioned) concrete including assembling by drawing the H.T. wire through metal spacer plate, inserting in helix core and taping or tying, sheathing in longitudinally welded metal corrugated sheath, positioning, anchorage with male and female set of anchorage cone, forming ducts for transverse cable stressing cables with jack at both ends as per stressing schedule, maintaining stressing record and supply the same in the approved proforma to the Engineer-in-charge, making loop at blind end, including all materials required for it, grouting the cable ducts with cement cutting projected ends & making good recesses etc., complete in all respects in accordance with the specifications.	per kg	53.5	311	5.6	The rate includes wastage in cutting and breakage in stressing etc

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.6.3 Fabrication of high tensile steel reinforcement conforming to ASTM A-416 for prestressed (pre-tensioned) concrete work, including inserting wire in moulds, providing M.S. shear bars, spacers and lift hooks, male and female anchorage, tie down, struts, stressing cables, maintaining stress record and supply the same in approved proforma to the Engineer-in-charge, cutting wires and projecting ends and making good recesses.etc. complete in all respects in accordance with the specifications.	per kg	31.22	285.5	5.6	(i) The rate includes wastage in cutting and breakage in stressing etc. (ii) Quantity of H.T.wire will form basis of payment.
5.7 Reinforced/Prestressed Cement Concrete				5.2.1 to 5.2.7 & 5.4	
5.7.1 Providing & laying reinforced cement concrete (including prestressed concrete), using coarse sand and crushed stone of approved quality / source, including mixing, transporting, placing, compacting, finishing and curing etc. complete in all respect as per specification but excluding the cost of steel reinforcement, its fabrication and placing in position etc. (a) Reinforced cement concrete in roof slabs, beams, columns, lintels, girders & other structural members cast in-situ or prestressed members cast in-situ complete in all respect as per specifications, including the cost of form work, moulds and shuttering complete in all respects, on ground floor of the buliding and for structures upto 20 ft height					(1) The rate includes rendering surface smooth and the plastering done for making up all surfaces after removing centering. If plastering for smoothing surface not done the rate be reduced by 10%. (2) fc' means 28 days compressive cylander strength of concrete. (3)The tenders condition should specified whether concrete will be supplied

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(i) Nominal mix 1:1:2	per cft (m ³)	96.8 3419	393 13891		on the basis of nominal mix or 28 days cylinder strength. (3) For reinforced cement concrete for pile foundation refer to chapter 14
(ii) Nominal mix 1:1-1/2:3	per cft (m ³)	96.8 3419	349 12329		
(iii) Nominal mix 1:2:4	per cft (m ³)	96.8 3419	319 11263		
(b) Reinforced cement concrete in rafts/spread/strip foundations base slab of columns, retaining walls floor and track supports etc. and other structural members other than those mentioned in 5.7.1 (a) complete in all respect as per specification, but excluding the cost of form work, moulds and shuttering, for ground floor of the building and for structures upto 20 ft height.					The cost of shuttering may be paid against item 5.5.1
(i) Nominal mix 1:1:2	per cft (m ³)	62.9 2222	318 11220		
(ii) Nominal mix 1:1-1/2:3	per cft (m ³)	62.9 2222	274 9694		
(iii) Nominal mix 1:2:4	per cft (m ³)	62.9 2222	245 8650		
(c) Pre-cast reinforced cement concrete and prestressed reinforced cement concrete in columns, beams, lintels, stair cases, shelves, manholes/drain covers etc. including formwork, complete in all respect as per specifications.					
(i) Nominal mix 1:1:2	per cft (m ³)	108.9 3846	394 13932		
(ii) Nominal mix 1:1-1/2:3	per cft (m ³)	108.9 3846	351 12405		
(iii) Nominal mix 1:2:4	per cft (m ³)	108.9 3846	322 11362		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.7.2 Erecting and fixing in position, precast cement concrete slabs etc. including all lead and lift complete.	per cft (m ³)	70.2 2479	83.6 2952	5.2.1 to 5.2.7 & 5.5	
5.7.3 Extra labour for laying concrete plain or reinforced at (a) 2nd and subsequent storeys in the buildings	per cft (m ³)	29.0 1026			
(b) Above 20 ft (6 m) upto 40 ft (12m) for other than buildings	per cft (m ³)	36.3 1282		5.6	
(c) For every additional 10 ft (3 m) height beyond 40 ft for other than buildings.	per cft (m ³)	18.2 641			
5.7.4 Lifting transporting and placing precast prestressed concrete beams, girders & other members, (excluding battens) etc. in position on the bridges to correct alignment and level etc. complete:-					
a) Beams up to 50 ft (15m) length	cft (m ³)	17.6 621			
(b) Beam above 50 ft (15 m) upto 75	cft (m ³)	24.8 877			
(c) Beam above 75 ft (23 m) upto 100 ft (30.5 m) length	cft (m ³)	33.8 1194			
(d) Beam above 100 ft (30.5 m) upto 150 ft (45.75 m) length	cft (m ³)	44.0 1553			
(e) Beam above 150 ft (45.75 m) length.	cft (m ³)	54.5 1926			
5.8 Other Precast Cement Concrete Works				5.2 & 5.5	
5.8.1 Providing & fixing in position precast cement concrete solid or face blocks (1:2:4), including cost of templates.	per cft (m ³)	59.3 2094	241 8500		
5.8.2 Providing & fixing in position precast cement concrete hallow blocks (1:2:4) including cost of templates.	per cft (m ³)	59.3 2094	177 6250		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.8.3 Providing and fixing in position ornamental cement concrete (1:2:4) Jali including cost of steel & its fabrication and templates complete in all respects.					
(a) 2" (50 mm) thick	per sft (m ²)	48.4 521	86.4 930		
(b) 3" (75 mm) thick	per sft (m ²)	67.8 729	119 1285		
(c) 4" (100 mm) thick	per sft (m ²)	87.1 938	152 1639		
5.8.4 Providing reinforced cement concrete spouts, including fixing in position (2-1/2' x 6" x 5") (760 mm x 150 mm x 125 mm).	each	484	659		
5.9 Admixtures				5.2.7 & 5.4	
5.9.1 Extra for adding water proofing agent as approved by the Engineer incharge in cement mortar/concrete.	per kg		74.3		
5.10 Contraction/Expansion Joints				5.4 & 5.7	
5.10.1 Providing and fixing 6" (150 mm) wide curved sheet of required shape fixed on face of the expansion joint with G.I. Screw 1.5 inch long to cover expansion joints vertically:-					
(a) Aluminum sheet 1/16 inch thick	per rft (m)	22.1 72.5	114 373		
(b) G.I. Sheet 14 SWG.	per rft (m)	12.60 41.4	62.9 206.4		
5.10.2 Providing and fixing 6" (150 mm) wide G.I. sheet 18 SWG stopper to expansion joint.	per rft (m)	7.50 24.6	52.5 172		
5.10.3 Filling expansion joints with bitumen 10/20 grade / Asphaltic mixture.	per rft (m)	6.66 21.8	18.1 59.4		
5.10.4 Providing PVC 5 mm thick water stopper in construction joints of RCC water tanks including fixing in position, complete.	sft (m ²)	6.66 71.6	52.6 567		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.10.5 Providing brass sheet 3 mm. thick water stopper in construction Joints & RCC water tanks, including over laps, fixing in position, etc complete.	sft (m ²)	9.68 104.2	828 8914		
5.10.6 Providing & laying preformed expansion joint filler, non-extruding and resilient type conforming to AASHTO M-213 specifications as shown on the drawings.	sft (m ²)	20.8 68.2	219 718		
5.10.7 Providing & filling joint filler, hot poured elastic type, conforming to AASHTO M-173, as shown on the drawings .	ft (m)	16.9 55.6	189 620		
5.11 Miscellaneous Items					
5.11.1 Nicking cement concrete surface:-	sft (m ²)	6.05 65.13			
5.11.2 Supplying and fixing broken glasses on court yard boundary walls, including 1:3:6 cement concrete coping.	sft (m ²)	35.5 382	77.9 839		
5.11.3 Making holes in old cement concrete or stone masonry walls and repairing.	per inch dia per ft depth	290.4			Payment shall be made for actual depth involved.
	per cm dia per m depth	375.1			
5.11.4 Keeping holes in cement concrete and fixing bolts in true alignment and levels including grouting with cement concrete 1:1.5:3 excluding cost of bolts.	per inch dia per ft depth	50.8	76.1		
	per cm dia per m depth	65.6	98.3		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
5.11.5 Supplying and fixing RCC mosaic bench 8-0' (2.5 m) long of approved design as per H.Q.E. sketch No. 3298 consisting of 1/2" (12 mm) mosaic topping of one part of white cement and marble powder ratio 3:1 and two parts marble chips laid over 2" (50 mm) thick precast RCC 1:2:4 slab (seat and back of bench). The rate also includes 3 Nos. precast RCC legs 3" (75 mm) thick finished with mosaic in grey cement, bolts and nuts. etc. rubbing, polishing, lead and lift complete in all respects.	each	6050	9901		
5.11.6 Providing and fixing RCC fencing on Platform complete in all respect as per HQE sketch no. H.Q.E Plan No.29537 (F-54) Type	ft	47.8	147		

CHAPTER 6**BRICK MASONRY**

Notes:

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 6 Brick Masonry of " Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and its stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.1 Brick Work in Cement Mortar				6.4.2 & 6.4.3	
6.1.1 Providing, laying and jointing pacca brick work in foundation and plinth in buildings or other than buildings using first class new bricks, raking of joints and curing as per drawings and specifications, complete in all respects in:-					
(a) Cement sand mortar 1:3	cft (m ³)	66.0 2333	229 8105		
(b) Cement sand mortar 1:4	cft (m ³)	66.0 2333	223 7882		
(c) Cement sand mortar 1:5	cft (m ³)	66.0 2333	219 7733		
(d) Cement sand mortar 1:6	cft (m ³)	66.0 2333	216 7629		
6.1.2 Providing, laying and jointing first class pacca brick work in foundation and plinth in buildings or other than buildings, using released bricks, including, raking of joints and curing as per drawings and specifications, complete in all respects in:-					
(a) Cement sand mortar 1:3	cft (m ³)	66.0 1.87	103 3647		i)The rates do not include cost of released bricks which will be supplied free of cost by Railways.
(b) Cement sand mortar 1:4	cft (m ³)	66.0 2333	96.9 3424		
(c) Cement sand mortar 1:5	cft (m ³)	66.0 2333	92.7 3275		
(d) Cement sand mortar 1:6	cft (m ³)	66.0 2333	89.8 3171		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.1.3 Providing, laying and jointing first class pacca brick work in ground floor for 9" (225 mm) to 13-1/2" (337 mm) thick walls including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects in:-					(i) Masonry of court yard wall to be considered as masonry of buildings.
(a) Cement sand mortar 1:3	cft (m ³)	72.1 2546	236 8319		
(b) Cement sand mortar 1:4	cft (m ³)	72.1 2546	229 8096		
(c) Cement sand mortar 1:5	cft (m ³)	72.1 2546	225 7947		
(d) Cement sand mortar 1:6	cft (m ³)	72.1 2546	222 7843		
6.1.4 Providing, laying and jointing first pacca brick work in ground floor for 9" (225 mm) to 13-1/2" (337 mm) thick walls with released bricks including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects. in:-					i)The rates do not include cost of released bricks which will be supplied free of cost by Railways.
(a) Cement sand mortar 1:3	cft (m ³)	72.1 2546	109 3861		
(b) Cement sand mortar 1:4	cft (m ³)	72.1 2546	103 3637		ii) The labor for cleaning of released bricks to be
(c) Cement sand mortar 1:5	cft (m ³)	72.1 2546	98.8 3489		paid under items 6.8.2 or 6.8.3 as appropriate.
(d) Cement sand mortar 1:6	cft (m ³)	72.1 2546	95.8 3384		
6.1.5 Providing, laying and jointing first class pacca brick work in ground floor for 4-1/2" thick walls. including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects in:-					
(a) Cement sand mortar 1:3	cft (m ³)	80.4 2839	244 8612		
(b) Cement sand mortar 1:4	cft (m ³)	80.4 2839	237 8388		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(c) Cement sand mortar 1:5	cft (m ³)	80.4 2839	233 8240		
(d) Cement sand mortar 1:6	cft (m ³)	80.4 2839	230 8135		
6.1.6 Add extra labour on item No.6.1.3, 6.1.5, for brick work in:-					
(a) First Floor	cft (m ³)	20.6 727			
(b) Second Floor	cft (m ³)	24.2 855			
(c) Third Floor	cft (m ³)	30.9 1090			
(d) Fourth and subsequent Floors	cft (m ³)	38.2 1350			
6.2 Cement Concrete Block Masonry				6.5.2 & 6.5.3	
6.2.1 Providing, laying and jointing block masonry using cement concrete (1:3:6) machine moulded solid blocks in foundation and plinth including scaffolding, raking of joints and curing as per drawings and specifications, complete in all respects in:-					The normal size of the solid blocks will be 6"x8"x12" (150 mm x 200mmx 300 mm) or 8"x8"x12" (200mmx 200mmx 300mm) for items 6.2.1 and 6.2.2
(a) Cement sand mortar 1:3	cft (m ³)	45.6 1610	233 8232		
(b) Cement sand mortar 1:4	cft (m ³)	45.6 1610	231 8146		
(c) Cement sand mortar 1:5	cft (m ³)	45.6 1610	229 8075		
(d) Cement sand mortar 1:6	cft (m ³)	45.6 1610	228 8044		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.2.2 Providing and laying and jointing block masonry using cement concrete (1:3:6) machine moulded solid blocks in ground floor including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects in:-					Same rate be paid for block masonry in other than buildings.
(a) Cement sand mortar 1:3	cft (m ³)	60.7 2145	248 8767		
(b) Cement sand mortar 1:4	cft (m ³)	60.7 2145	246 8681		
(c) Cement sand mortar 1:5	cft (m ³)	60.7 2145	244 8609		
(d) Cement sand mortar 1:6	cft (m ³)	60.7 2145	243 8578		
6.2.3 Providing and laying and jointing block masonry using cement concrete (1:3:6) machine moulded hallow blocks in ground floor including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects in:-					i) The normal size of the hallow blocks will be 6"x8"x16" (150 mm x 200mm x 400 mm) ii) Same rate be paid for block masonry in other than buildings.
(a) Cement sand mortar 1:3	cft (m ³)	60.7 2145	192 6774		
(b) Cement sand mortar 1:4	cft (m ³)	60.7 2145	189 6688		
(c) Cement sand mortar 1:5	cft (m ³)	60.7 2145	187 6616		
(d) Cement sand mortar 1:6	cft (m ³)	60.7 2145	187 6601		
6.2.4 Add extra labour on item No.6.2.2, 6.2.3 for block masonry work in:-					
(a) First Floor	cft (m ³)	20.6 727			
(b) Second Floor	cft (m ³)	24.2 855			
(c) Third Floor	cft (m ³)	30.9 1090			
(d) Fourth and subsequent Floors	cft (m ³)	38.2 1350			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.3 Brick Work for Cavity Walls				6.4.2, 6.4.3, 6.4.4 & 6.4.12	
6.3.1 Providing , laying and jointing first class pacca brick work in ground floor with 2" to 3" cavity having 4-1/2" thick walls on either side bonded with wall ties of approved design at required horizontal and vertical spacing including scaffolding, raking of joints and curing as per drawings and specifications, complete in all respects, in:-					i) Actual width of wall including cavity will be measured. ii) Extra labour on item no 6.3.1 for brick work in first, Second, Third and fourth floor shall be paid as per item 6.1.6
(a) Cement sand mortar 1:3	cft (m ³)	111 3910	245 8640		
(b) Cement sand mortar 1:4	cft (m ³)	111 3910	254 8987		
(c) Cement sand mortar 1:5	cft (m ³)	111 3910	249 8788		
(d) Cement sand mortar 1:6	cft (m ³)	111 3910	245 8651		
6.4 Brick Work other than for Buildings				6.4.2, 6.4.3 & 6.4.4	
6.4.1 Providing ,laying and jointing first class pacca brick work other than in buildings above foundations and plinth upto 10 ft (3 m) height including scaffolding, raking of joints and curing as per drawings and specifications, complete in all respects, in:-					Workshops, godowns, bins, house type godowns, reservoirs, filter beds, storage tanks, wells, screening chambers, collecting tanks, manholes, boundry wall etc., are to be treated as masonry other than buildings for items 6.4.1 and 6.4.2.
(a) Cement sand mortar 1:3	cft (m ³)	50.3 1778	221 7798		
(b) Cement sand mortar 1:4	cft (m ³)	50.3 1778	214 7575		
(c) Cement sand mortar 1:5	cft (m ³)	50.3 1778	210 7426		
(d) Cement sand mortar 1:6	cft (m ³)	50.3 1778	207 7322		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.4.2 Providing laying and jointing first class pacca brick work other than in buildings above foundations and plinth upto 10 ft (3 m) height using released bricks including scaffolding, raking of joints and curing as per drawings and specifications, complete in all respects, in:-					i)The rates do not include cost of released bricks which will be supplied free of cost by railway.
(a) Cement sand mortar 1:3	cft (m ³)	50.3 1778	87.5 3092		
(b) Cement sand mortar 1:4	cft (m ³)	50.3 1778	81.2 2869		ii) The labor for cleaning of released bricks to be paid under items 6.8.2 or 6.8.3 as appropriate
(c) Cement sand mortar 1:5	cft (m ³)	50.3 1778	77.0 2720		
(d) Cement sand mortar 1:6	cft (m ³)	50.3 1778	74.1 2616		
6.4.3 Extra labour for arch work in brick masonry, including labour for centring and decentring.	cft (m ³)	17.4 615		6.4.2, 6.4.3 & 6.4.4	
6.4.4 Extra for pucca brick work in steining of wells or any other circular masonry.	cft (m ³)	12.10 427	19.8 698	6.4.2, 6.4.3	
6.4.5 Extra labour for profile and flared walls.	cft (m ³)	4.16 147		6.4.2, 6.4.3	
6.4.6 Extra labour for pacca brick work in piers and abutment:-				6.4.2, 6.4.3	
(a) From 10 ft to 20 ft.	cft (m ³)	4.07 143.60			
(b) Above 20 ft height.	cft (m ³)	8.23 290.61			
6.4.7 Add extra labour on item No. 6.4.1 for every 10 ft additional height, or part thereof.	cft (m ³)	10.3 363.27			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.5 Reinforced / Perforated Brick Work				6.4.2, 6.4.3 & 6.4.11	
6.5.1 Providing, laying and jointing reinforced brick work in lintel of openings laid in 1:3 cement sand mortar including all labour, material, shuttering & lifting and placing in position etc, and filling of gap between the bricks with 1:2:4 PCC (but excluding cost of steel reinforcement and its fabrications which shall be paid separately) complete in all respects:-	cft (m ³)	142.10 5019	302 10660		
6.5.2 Providing, laying and jointing first class pacca brick walling laid in 1:3 cement sand mortar, reinforced with 1" wide 18 gauge hoop iron including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects.					
(a) 4-1/2" thick walling with hoop iron bonding 6" apart.	sft (m ²)	24.8 267.0	106 1136.9		
(b) 4-1/2" thick walling with hoop iron bonding 12" apart.	sft (m ²)	22.4 241.0	94.8 1020.2		
(c) 3" thick walling with hoop iron bonding 6" apart.	sft (m ²)	19.6 211.0	80.3 864.2		
(d) 3" thick walling with hoop iron bonding 12" apart.	sft (m ²)	19.6 211.0	70.9 762.9		
6.5.3 Providing, laying and jointing perforated pacca brick walling half brick 4-1/2" thick in ground floor in cement sand mortar including scaffolding, raking of joints and curing as per drawings and specifications complete in all respects.					
(i) Cement sand mortar 1:3	sft (m ²)	35.5 382	76.4 822		
(ii) Cement sand mortar 1:4	sft (m ²)	35.5 382	74.8 805		
(iii) Cement sand mortar 1:5	sft (m ²)	35.5 382	73.7 794		
(iv) Cement sand mortar 1:6	sft (m ²)	35.5 382	73.0 786		
6.5.4 Add extra labour on item No. 6.5.3 for pacca brick work in:-					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) First Floor	sft (m ²)	5.14 55.4			
(b) Second Floor	sft (m ²)	11.80 127.0			
(c) Third Floor	sft (m ²)	18.5 199			
(d) Fourth & subsequent Floor	sft (m ²)	38.2 412			
6.5.5 Providing, laying and jointing perforated pacca brick walling one brick (9") thick in ground floor in cement sand mortar including scaffolding, raking of joints and curing as per drawing and specifications complete in all respects, in				6.5,6.6.1 & 6.6.10	
(i) Cement sand mortar 1:3	sft (m ²)	53.3 574	135 1454		
(ii) Cement sand mortar 1:4	sft (m ²)	53.3 574	132 1420		
(iii) Cement sand mortar 1:5	sft (m ²)	53.3 574	130 1397		
(iv) Cement sand mortar 1:6	sft (m ²)	53.3 574	128 1381		
6.5.6 Add extra labour on item No. 6.6.5 for perforated pacca brick work in:-					
(a) First Floor	sft (m ²)	21 221.4			
(b) Second Floor	sft (m ²)	24 260.5			
(c) Third Floor	sft (m ²)	31 332.2			
(d) Fourth & subsequent Floor	sft (m ²)	38 411.6			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.6 Special Brick Works					
6.6.1 Providing, laying and fixing pacca Guttka bricks of first quality laid in 1:2 cement sand mortar supported with nails, including scaffolding, raking of joints and curing as per drawing and specifications complete in all respects.					
(a) Size 1-1/2"x 1-1/2"x 9" (38 x 38 x 229 mm)	sft (m ²)	36.3 390.8	143 1536.8		
(b) Size 2-1/4"x 3"x 9" (57 x 75 x 229 mm)	sft (m ²)	36.3 390.8	117 1258.3		
6.6.2 Providing, laying and jointing Fire brick masonry in fire clay mortar including scaffolding, raking of joints and curing as per drawing and specifications, complete in all respects.					
(a) Upto 20 ft (6 m) height including all charges.	cft (m ³)	69.0 2436	296 10469		
(b) Extra for every 5 ft (1.5) additional height or part thereof.	cft (m ³)	20.6 727			
6.6.3 Providing, laying and jointing pacca brick work with special brick (architectural design) including scaffolding, raking of joints and curing as per drawing and specifications, complete in all respects in:-				6.4.10, 6.4.12 to 6.4.18	
(a) Cement sand ratio 1:2	cft (m ³)	63.5 2243	268 9465		
(b) Cement sand ratio 1:3	cft (m ³)	63.5 2243	257 9093		
(c) Cement sand ratio 1:4	cft (m ³)	63.5 2243	251 8870		
6.6.4 Extra for masonry of any description for bonding old and new masonry including making recesses as required in old masonry (actual measurement of new masonry inserted into old masonry to be given).	cft (m ³)	72.60 2564.23			
6.6.5 Extra for chamfering bricks for:-				6.4.2, 6.4.3	
(a) Special architectural bricks	each	38.77			
(b) all other purposes.	each	19.38			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
6.6.6 Maroo corners.	each corner	242.0			
6.7 Termite Proofing				6.6	
6.7.1 Providing pre-construction termite proofing by using diluted spray emulsion of FMC-Biflex or approved equilent at 40-liter per 100 sft of surface area complete in all respect and as directed by the engineer incharge.	100 sft of each spray	106.48	224		
	(m ² of each spray)	1146.3	2414.7		
6.7.2 Providing termite proofing of existing buildings by drilling 3/8" dia 2-1/2' deep holes along the walls at approximately 3' c/c injecting approved anti termite chemical of FMC-Biflex or approved equilent make with pressure machine and sealing the same, as per specification complete in all respects as directed by the engineer incharge.	Per lft (m)	5.81 62.5	7.13 76.7		(i) Rate shall be reduced by 75% for first and each subsequent floor.
6.7.3 Providing termite proofing of wooden fixtures inside or out side the existing buildings such as doors, windows, almirahs, sun-shades, panellings, ceilings, railings, etc. by injecting the approved anti termite chemical with pressure machine and sealing the same, as per specification complete in all respect.	sft (m ²)	3.39 36.47	4.71 50.68		
6.8 Miscellaneous Items					
6.8.1 Dry brick pitching.	cft (m ³)	26.6 940	65.9 2327		
6.8.2 Cleaning bricks dismantled from kacha pacca masonry.	each	1.27			
6.8.3 Cleaning bricks dismantled from pacca masonry.	each	2.40			
6.8.4 Replacing kallar eaten bricks.	each	44.37	54.71		

CHAPTER 7
STONE MASONRY

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 7 Stone Masonry of "Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) The cost of supply and carriage to site of work of all materials used for stone masonry is included in the composite rates.
- (3) Rates for all finished work include the removal of surplus debris, unused material and by-products and stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
7.1 Stone Masonry Works				7.4&7.5	
7.1.1 Providing, laying and jointing random, rubble stone masonry (uncoursed), in foundation and plinth:-				7.4, 7.7.1, 7.7.2 & 7.7.6	
(a) Dry masonry	cft (m ³)	46.0 1624	99.2 3504		
(b) In mud mortar	cft (m ³)	57.5 2030	113 3989		
(c) In cement sand mortar:-					
(i) Cement sand mortar 1:3	cft (m ³)	76.2 2692	185 6544		
(ii) Cement sand mortar 1:4	cft (m ³)	76.2 2692	176 6209		
(iii) Cement sand mortar 1:6	cft (m ³)	76.2 2692	165 5826		
(iv) Cement sand mortar 1:8	cft (m ³)	76.2 2692	159 5614		
7.1.2 Providing, laying and jointing random rubble stone masonry (uncoursed) in ground floor in buildings or upto 20 ft (6 m) height in other than building:-				7.4, 7.5.1, 7.5.2, & 7.5.6	
(a) Dry masonry	cft (m ³)	46.0 1624	99.2 3504		
(b) In mud mortar	cft (m ³)	62.9 2222	118 4181		
(c) In cement sand mortar:-					
(i) Cement sand mortar 1:3	cft (m ³)	78.0 2757	187 6608		
(ii) Cement sand mortar 1:4	cft (m ³)	78.0 2757	178 6273		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(iii) Cement sand mortar 1:6	cft (m ³)	78.0 2757	167 5890		
(iv) Cement sand mortar 1:8	cft (m ³)	78.0 2757	161 5678		
7.1.3 Providing, laying and jointing coursed rubble stone masonry hammer dressed, in foundation and plinth:-				7.4, 7.5.1, 7.5.2, & 7.5.5	
(a) Dry masonry	cft (m ³)	64.1 2265	117 4146		
(b) In mud mortar	cft (m ³)	81.1 2863	137 4823		
(c) In cement sand mortar:-					
(i) Cement sand mortar 1:3	cft (m ³)	105.8 3735	216 7613		
(ii) Cement sand mortar 1:4	cft (m ³)	105.8 3735	207 7315		
(iii) Cement sand mortar 1:6	cft (m ³)	105.8 3735	197 6974		
(iv) Cement sand mortar 1:8	cft (m ³)	105.8 3735	192 6787		
7.1.4 Providing, laying and jointing coursed rubble stone masonry hammer dressed, in ground floor in buildings or upto 20 ft (6 m) height, in other than building:-				7.4, 7.7.1, 7.7.2 & 7.7.5	
(a) Dry masonry	cft (m ³)	67.8 2393	121 4274		
(b) In mud mortar	cft (m ³)	100.4 3547	151 5328		
(c) In cement sand mortar:-					
(i) Cement sand mortar 1:3	cft (m ³)	111.9 3953	222 7831		
(ii) Cement sand mortar 1:4	cft (m ³)	111.9 3953	213 7533		
(iii) Cement sand mortar 1:6	cft (m ³)	112 3953	204 7192		
(iv) Cement sand mortar 1:8	cft (m ³)	112 3953	198 7005		
7.1.5 Extra labour on items 7.1.2 and 7.1.4 above for work in:-					
(a) First Floor	cft (m ³)	24.2 855			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Second Floor	cft (m ³)	24.2 855			
(c) Third Floor	cft (m ³)	30.9 1090			
(d) Fourth & subsequent floors.	cft (m ³)	38.2 1350			
7.1.6 Extra labour on items 7.1.2 and 7.1.4 above for every 5 ft (1.5 m) additional height, or part thereof above 20 ft (6 m) in other than buildings.	cft (m ³)	27.8 983			
7.1.7 Extra labour for arch work in stone masonry, including centring and decentring, etc.	cft (m ³)	24.2 855	26.6 940	7.5, 7.7.1 & 7.7.9	
7.1.8 Extra labour for:-				7.7.1 & 7.7.8	
(a) Coping and caps, etc.	cft (m ³)	230 8120			
(b) Cornice & string course	per rft (m)	174 571.68			
7.2 Dressing of Stones				7.7.1 & 7.7.2	
7.2.1 Dressing stones:-					(i) This rate of dressing shall be paid only when undressed stone has been supplied. (ii) In case of rate for stone masonry, dressing is already included and this rate shall not be added thereto. (iii) Only dressed surface of stone shall be measured.
(a) Hammer dressed	sft (m ²)	78.7 846.7			
(b) Rough tooled dressed	sft (m ²)	150 1615.2			
(c) Chisel dressed	sft (m ²)	182 1954			
7.3 Miscellaneous Items					
7.3.1 Providing and fixing stone blocks from 2 to 6 cft each in cement mortar (1:6), including lift upto 20 ft (6 m).	cft (m ³)	475 16774	540 19058	7.7.1, 7.7.2 & 7.7.4	
7.3.2 Providing and fixing stone blocks, under 2 cft each in cement mortar (1:6), including lift upto 20 ft (6 m).	cft (m ³)	278 9830	343 12120	7.7.1, 7.7.2 & 7.7.8	

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
7.3.3 Making 1-1/2" x 1-1/2" groove in wall of stone masonry in cement, for fixing planks upto 9" deep.	plank	282.33			
7.3.4 Drilling holes in stone masonry upto 2" dia, per inch depth.	hole per in depth	90.75			The rate is not to be operated for holes exceeding 2" diameter
	(hole per cm depth)	35.73			

CHAPTER 8
ROOFING

Note:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 8 Roofing of "Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.1 RCC Slab Roofing & Roof Insulation				8.4 & 8.5.2	Add extra 6%, 15% & 23% on composite rates for 2nd, 3rd, 4th and subsequent floors respectively for items no. 8.1.1 to 8.1.10
8.1.1 Providing and laying cement concrete (1:2:4) on roof top to required slope including ramming, finishing, smoothing and curing etc. as per specification and complete in all respects.	cft (m ³)	47.2 1667	222 7855		
8.1.2 Providing and laying two coats of bitumen laid hot using 34 lb/100 sft over roof and blinded with sand at 1 cft/100 sft as per specification and complete in all respects. .	sft (m ²)	13.9 150	32.1 346		
8.1.3 Providing and laying single layer of tiles 9" x 4-1/2" x 1-1/2", grouted with cement sand mortar 1:3, laid over 1" mud plaster, over 4" thick earth, over 34 lbs per 100 sft bitumen coating blinded with sand at 1 cft/100 sft laid on top of RCC/Precast RCC roof slab, ,excluding polythene sheet as per specification and complete in all respects.	sft (m ²)	26.0 280	78.6 846		No payment for flush pointing will be made for new roofs.
8.1.4 Providing and laying single layer of tiles 9" x 4-1/2" x 1-1/2" grouted with cement sand mortar 1:3, laid over 1" thick mud mortar mixed with bhoosa over existing earth,including dressing & adjusting slopes of existing earth as per specifications, complete in all respects.	sft (m ²)	18.3 197	52.9 570		No payment for flush pointing will be made for new roofs.
8.1.5 Earth filling over roof including watering, ramming with 1" mud plaster, finished with gobi leeping as per specification over:-					same remarks under item 8.1.4 above

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) 3" thick earth filling & 1" mud plaster.	sft (m ²)	9.29 100.0	14.4 155		
(b) 4" thick earth filling & 1" mud plaster.	sft (m ²)	9.73 104.7	15.3 165		
8.1.6 Providing and laying roof insulation, comprising of single layer of tiles 9"x4-1/2"x1-1/2" grouted with cement sand mortar 1:3 laid over 2" thick earth (including 1" mud plaster) over thermopore sheet 1" thick , over polythene sheet 300 gauge over a layer of bitumen coating at 34 lbs/100sft, as per specification and complete in all respects:-	sft (m ²)	29.6 319	107 1150		Add extra 6%, 15% and 23% on composite rates from 14.1', to 26', 26.1 to 38', 38.1' to 50' and above & for subsequent floors of 12' height respectively.
8.1.7 Providing and laying roof insulation, comprising of single layer of tiles 9"x4-1/2"x1-1/2" grouted with cement sand mortar 1:3 laid over 2" thick earth (including 1" mud plaster) over jambolon board, over polythene sheet 300 gauge over a layer of bitumen, coating complete in all respects:					
(a) Jumbolon Board 1" thick	sft (m ²)	29.6 319	139 1497		
(b) Jumbolon Board 2" thick	sft (m ²)	29.6 319	201 2167		
8.1.8 Providing a coat of bitumen emulsion at the rate of 4.5 kg per 100 sft on walls and floors in ground floor, as per specification.	sft (m ²)	3.29 35.4	8.24 88.7		same remarks under item 8.2.4 above.
8.1.9 Providing and laying two layers of bitumenous building paper, with a coat of grease in between, under bearing of roof slab, beams, lintels, etc. over 3/8" thick cement sand plaster 1:2 for free expansion and contraction as per specification.	sft (m ²)	21.8 234	112 1205		Add extra 6%, 15% & 23% on composite rates for 2nd, 3rd, 4th and subsequent floors respectively.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.1.10 Providing & fixing Khaprail tiles on roofs, laid in cement sand mortar 1:3, including jointing, curing, etc. complete in all respects as per drawings and as per instructions of Engineer Incharge.					
(a) Size 150 x 150 mm (6"x 6") Grey Colour	sft (m ²)	24.2 261	94.2 1014		
(b) Size 225 x 225 mm (9"x 9") Grey Colour	sft (m ²)	19.4 208	61.4 661		
(c) Size 300 x 300 mm (12"x 12") Grey Colour	sft (m ²)	14.5 156	47.0 506		
8.2 Pre-cast Prestressed Concrete Girders/Slab Roofing				8.5.3	
8.2.1 Providing and laying roof in ground floor with precast prestressed concrete girders & slabs obtained from approved manufacturers (Izhar or equivalent) including cement sand plaster 1/2" thick (1:3) on top and cement pointing (1:2) flush underneath, as per drawing & specification, complete in all respects and including all other charges.					(i) Add extra 6%, 15% & 23% on composite rates for 2nd, 3rd, 4th and subsequent floors respectively. (ii) The rates are applicable to clear span lengths.
(a) Span Length upto 15 ft	sft (m ²)	11.83 127.4	138 1488		
(b) Span length 15.1 ft to 20 ft	sft (m ²)	11.50 123.7	140 1506		
(c) Span length 20.1 to 25 ft	sft (m ²)	8.52 91.7	166 1783		
(d) Span length 25.1ft to 30 ft	sft (m ²)	7.53 81.0	227 2439		

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.2.2 Providing and erecting in position pre-cast pre-stressed cement concrete double tee (TT) planks roofing at a height 30 to 40 ft of approved design procured from an approved manufacturers and designed for a superimposed dead load of 50 lbs/sft and a live load of 30 lbs/sft duly tested and certified by the manufacturer including loading, transportation, unloading, erection at site and placement in position as per line and level and as directed by the Engineer Incharge.					
(a) Span Length upto 40 ft	sft (m ²)		183 1967		
(b) Span Length 41-45 ft	sft (m ²)		194 2084		
(c) Span Length 46-50 ft	sft (m ²)		200 2149		
(d) Span Length 51-55 ft	sft (m ²)		212 2279		
(e) Span Length 56-60 ft	sft (m ²)		230 2475		
8.2.3 Providing and laying single layer tiles 9" x 4-1/2"x1-1/2" (first class tiles) at a height of 30 to 40 ft grouted with cement, sand mortar 1:3 laid over 3" thick mud on Double Tee Planks roofing covered by 2 coats of hot bitumen using 34 lbs/100 sft and a layer of polythene sheet 500 gauge (005" thick) including over laps, as per specifications and complete in all respects.	sft (m ²)	36.9 397	94.8 1020		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.3 Jack Arch Roofing				8.4 , 8.5.4	
8.3.1 Providing Jack arch roofing 4-1/2" thick laid in 1:5 cement sand mortar including an average depth of 4" cement concrete (1:3:6) in haunches and over crown, with 3" earth & 1" mud plaster, soffits of arches cement sand plaster 1:6 and 1/2" thick. The rate also includes bitumen coating, erecting and dismantling centring, laying skew bricks in cement sand mortar (1:3) and encasing exposed flanges of the joists with cement concrete 1:2:4 using stone aggregate, as per specifications and complete in all respects.:-	sft (m ²)	106.5 1146	260 2799	& 8.5.5	(i) For steel part and its erection etc., items 13.2.1 & 13.4.4 under Chapter 13- structural steel works be referred if supplied by the contractor. (ii) Add extra 6%, 15% & 23% on composite rates for 2nd, 3rd, 4th & subsequent floors respectively on items 8.3.1 & 8.3.2. (iii) If Rails/ R.S.Joists. are supplied by Railways then cutting of Rails /R.S.Joist, drilling holes, rivetting and erection should be paid for the items actually involved under Chapter-13. (iv) Payment of the tie rods complete be made under item of fabrication of heavy steel work under Chapter-13. (v) Bearing plates with stirrups etc. for duplicate rail girders as per type plan No.Q-24 be paid under item of fabrication of small iron work under Chapter-13.
8.3.2 Providing Jack arch roofing 4-1/2" thick laid in 1:5 cement sand mortar, including an average depth of 4" cement concrete (1:3:6) in haunches and over crown with 1/2" cement plaster 1:6 on top & soffits (except earth filling, mud plaster and gobi leeping). The rate also includes bitumen coating, erecting and dismantling centring. laying skew bricks in cement sand mortar 1:3 and encasing exposed flanges of the joists with cement concrete 1:2:4 using stone aggregate, as per specifications and complete in all respects:-	sft (m ²)	86.5 931	238 2566		
8.4 Plain/Corrugated G.I Sheet Roofing				8.4.9 & 8.5.7	
8.4.1 Providing Corrugated galvanized iron sheet roofing over the existing trusses / griders etc. including its fixing with G.I. bolts, nuts, limpet and bitumen washers, wind ties complete in all respects, without valleys and ridges as per drawing and specification & complete in all respects.					Add extra 6%, 15% & 23% on composite rates for heights from 14.1' to 26', 26.1' to 38', 38.1' to 50' and above for items 8.4.1 to 8.4.5

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) 20 S.W.G. sheets	sft (m ²)	19.4 208	109 1175		
(b) 22 S.W.G. sheets	sft (m ²)	19.4 208	92.9 1000		
(c) 24 S.W.G. sheets	sft (m ²)	19.4 208	79.6 857		
8.4.2 Providing and fixing plain galvanized iron sheets 20 S.W.G. 4" diameter rain water down pipe including clamps complete in all respects.	rft (m)	94.4 310	186 609		
8.4.3 Providing and fixing 4" dia M.S rain water down pipe including clamps complete in all respects.	rft (m)	94.4 310	518 1699		
8.4.4 Providing and fixing 20 S.W.G plain galvanized iron sheet flashing etc complete in all respects.	sft (m ²)	87.1 938	158 1705		
8.4.5 Providing and fixing 20 S.W.G plain galvanized iron sheet ridges including fixtures complete in all respects.					
(a) 6" lap and 18" overall length	rft (m)	94.4 310	514 1685		
(b) 9" lap and 24" overall length	rft (m)	116.2 381	541 1777		
(c) 12" lap and 30" overall length	rft (m)	116.2 381	571 1874		
8.5 Corrugated Asbestos Cement Sheet Roofing				8.4.10 & 8.5.8	
8.5.1 Supplying & fixing Asbestos cement corrugated sheet roofing of approved quality (Izhar or equivalent) over the existing trusses / griders etc. including necessary over laps & G.I. hook bolts, nuts, screws, limpet and, bitumastic washers, wind ties, etc. (excluding valleys and ridges, etc), complete at any height as per specification complete in all respects.	sft (m ²)	26.6 287	67.3 725		
8.5.2 Supplying & fixing corrugated asbestos cement sheet ridges & valleys at any height complete in all respects.	ft (m)	32.7 107.2	73.0 239		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.5.3 Extra labour for every erection of G.I. Sheets, flat sheet or asbestos sheet roofing, or corrugated fiber glass roofing above 20 ft (6 m) height in difficult position, including lifting with care and special scaffolding along live electric wires.	sft (m ²)	4.36 46.9			
8.6 Fiber Glass (Corrugated and Plain) Roofing				8.4.11 & 8.5.9	
8.6.1 Providing and fixing corrugated fiberglass sheet roofing over the existing trusses / grids etc at any height including all fittings as per specifications and complete in all respects.	sft (m ²)	26.6 287	212 2279		
8.6.2 Providing and fixing plain fiberglass sheet roofing at any height, including all fittings as per specifications and complete in all respects.	sft (m ²)	26.6 287	204.8 2205		
8.6.3 Providing and fixing corrugated fiber glass sheet roof drains/ridge at any height including all fittings as per specifications and complete in all respects.	sft (m ²)	32.7 352	188 2029		
8.6.4 Providing and fixing plain fiberglass sheet roof drains/ridge at any height including all fittings as per specifications and complete in all respects.	sft (m ²)	32.7 352	183 1970		
8.6.5 Providing and fixing corrugated fiberglass sheet north light glass at roof at any height including all fittings complete.	sft (m ²)	23.0 247	208 2240		
8.6.6 Providing and fixing plain fiberglass sheet north light glass at roof at any height including all fittings as per specifications and complete in all respects.	sft (m ²)	23.0 247	201 2166		
8.7 Roof Drainage Items				8.5.10 & 8.5.11	
8.7.1 Khassi parnalas in cement sand mortar (1:2) 12" outside width finished smooth with a floating coat of neat cement as per specifications, complete in all respects	ft (m)	80.0 263	99.73 327		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.7.2 Khuras on roof 2' x 2' x 1 1/2" of cement concrete (1:2:4) laid over 3" thick 1:4:8 concrete as per specifications, complete in all respects.	each	375	695		
8.7.3 Bottom Khurras on ground in size brick masonry in cement mortar 1:6, of size 4' x 2' x 4-1/2" laid over 3" cement concrete 1:4:8 as per specifications complete.	each	424	1112		
8.7.4 Supplying and fixing in position cast iron rain water down pipe as per specification (BS 416:Part-1-1990) excluding heads and shoes but including painting and clamps etc complete in all respects.					
(a) 4" dia (internal) cast iron down pipe	ft	64.5	612		
	(m)	212	187		
(b) 3" dia (internal) cast iron down pipe	ft	64.5	518		
	(m)	19.7	158		
8.7.5 Supplying & fixing in position rain water down pipe cast iron heads as per specification (BS 416:Part-1-1990) including cost of clamps holdfast and painting complete in all respects.	each	261	671		
8.7.6 Supplying & fixing shoes, bends or offsets of cast iron rain water down pipe as per specification (BS 416:Part-1-1990) including painting, complete in all respects.	each	96.8	409		
8.7.7 Supplying and fixing in position plain 22 gauge G.I sheet iron spouts 3" to 4" diameter as per specification complete in all respects.	each	315	409	8.6.9	
8.7.8 Supplying and fixing in position 22 gauge G.I sheet gutter semi-circular 8" (200 mm) dia as per specification, complete in all respects.	ft	58.1	180		
	(m)	191	590		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
8.7.9 Providing and fixing in position G.I sheet water spouts or parnalas as per drawing complete in all respects.	each	339			
8.7.10 Providing making drip course 2" x 1/2" under R.C.C. slab edges in outer opening, in cement sand mortar 1:2.	ft (m)	23.7 77.8	24.9 81.7		
8.7.11 Supply & erection of rain water down pipe UPVC including heads & shoes complete in all respect as per instructions of Engineer including cost of clamp holdfast, complete in all respects.					
(a) 75 mm (3") dia pipe	ft (m)	83.2 273	715 2344		
(b) 100 mm (4") dia pipe	ft (m)	133 437	1026 3365		
(c) 160 mm (6") dia pipe	ft (m)	133 437	1683 5522		
8.7.12 Supply & erection of rain water down pipe Asbestos cement pipes (Chrysotile cement pipes) including heads & shoes complete in all respect as per instructions of Engineer including cost of clamp holdfast, complete in all respects.					
(a) 80 mm (3") dia pipe	lft (m)	83.2 273	591 1938		
(b) 100 mm (4") dia pipe	lft (m)	133 437	731 2399		
(c) 150 mm (6") dia pipe	lft (m)	133 437	969 3180		
8.8 Miscellaneous Items					
8.8.1 Making jharries in existing brick masonry for providing recesses for bearing of R.C.C. roof slab including repairing the damaged face:-					Rate will be increased by 1.5 times for making recesses / jharries in stone masonry or plain concrete and 2
(a) for slabs upto 6" deep	ft (m)	27.8 91.3	29.3 96.0		

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) for slabs exceeding 6" upto 12" deep	ft (m)	39.9 131.0	42.6 140		
8.8.2 Making recess in existing brick masonry for bearing of beam girder, R.S. joist, ect. Including repairing damaged face:-					
(a) upto 1.0' height of girder or beam	each	60.5	66.5		
(b) for every 6" additional height or part thereof.	each	29.0	31.9		

CHAPTER 9**FLOORING**

Note:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 9 Flooring of "Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
9.1 Brick / Brick Tile Flooring				9.3.6, 9.4.1& 9.4.2	
9.1.1 Providing, laying, watering and ramming brick ballast 1-1/2" to 2" gauge mixed with 25% sand, for floor foundations, complete in all respects.	cft (m ²)	18.8 202	50.9 548		
9.1.2 Providing dry brick paving laid flat, sand grouted, including preparation of bed by watering, ramming, and bringing the same to proper camber by 1/2" thick mud plaster, complete in all respects	sft (m ²)	12.46 134	46.4 500		
9.1.3 Providing 4-1/2" thick dry brick on edge paving, sand grouted, including preparation of bed by watering, ramming and bringing the same to proper camber by 1/2" thick mud plaster, , complete in all respects	sft (m ²)	18.0 193	68.5 737		
9.1.4 Grouting 4-1/2" dry brick on edge flooring with cement sand mortar ratio 1:3., complete in all respects	sft (m ²)	12.10 130	16.8 181		
9.1.5 Providing flat brick flooring laid in 1:6 cement sand mortar over a bed of 3/4" thick cement sand mortar 1:6 , complete in all respects	sft (m ²)	23.6 254	65.3 703		
9.1.6 Providing brick on edge flooring, laid in 1:6 cement sand mortar over a bed of 3/4" thick cement sand mortar 1:6, complete in all respects	sft (m ²)	30.3 325.6	89.7 965		
9.1.7 Brick tiles 9" x 4-1/2" x 1-1/2" laid on edge 1:3 cement sand mortar over a bed of 3/4" thick cement mortar 1:6 , complete in all respects.	sft (m ²)	47.8 515	161 1735		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
9.1.8 Brick tiles 9"x4-1/2"x1-1/2" laid flat in 1:3 cement sand mortar over a bed of 3/4" thick cement sand mortar 1:6 , complete in all respects.	sft (m ²)	26.6 287	67.4 725		
9.2 Cement Concrete Tile Flooring / Skirting				9.3.8 & 9.4.4	
9.2.1 Providing cement concrete tiles laid flat in 1:2 cement sand mortar over 3/4" thick bed of cement sand mortar 1:2, complete in all respects.					
(a) 12" x 12" x 1"	sft (m ²)	32.2 346	77.9 838		
(b) 9" x 9" x 3/4"	sft (m ²)	32.2 346	83.7 901		
(c) 8" x 8" x 3/4"	sft (m ²)	32.2 346	83.8 902		
(d) 6" x 6" x 3/4"	sft (m ²)	32.2 346	83.9 904		
9.2.2 Providing coloured cement concrete tiles 8" x 8" x 3/4" of approved shade laid flat in 1:2 cement sand mortar over 3/4" thick cement sand mortar of 1:2, complete in all respects.	sft (m ²)	32.2 346	70.0 753.7		
9.2.3 Providing 3/4" thick cement concrete tile skirting laid in 1:2 cement sand mortar, over 3/4" thick cement sand mortar 1:2, complete in all respects.	sft (m ²)	26.3 283	82.0 883		
9.3 Cement Concrete Flooring				9.3.8 & 9.4.4	
9.3.1 Providing & laying topping of cement concrete 1:2:4 flooring including surface finishing and dividing into pannels as per specifications and complete in all respects:-					
(a) 1" thick	sft (m ²)	19.5 210	34.8 375		If glass, brass or Aluminum strips are used for panelling, it will be paid extra as per item No.9.4.5
(b) 1-1/2" thick	sft (m ²)	23.5 253	45.9 494		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(c) 2" thick	sft (m ²)	27.5 296	57.3 617		
(d) 3" thick	sft (m ²)	31.5 339	76.1 820		
(e) 4" thick	sft (m ²)	35.5 382	95.9 1032		
(f) 6" thick	sft (m ²)	47.2 508	136 1466		
9.3.2 Providing and laying conglomerate flooring (two layer work) with top layer of 1/2" thick wearing surface consisting of one part of cement and 2 parts of stone chips passing 3/16" sieve over bottom layer of cement concrete 1:2:4, including surface finishing and dividing into pannels as per specifications and complete in all respects.				9.4.3 & 9.4.5	If glass, brass or Aluminum strips are used for panelling, it will be paid extra as per item No.9.4.5
(a) 1-1/2" thick bottom layer	sft (m ²)	31.0 333	66.1 712		
(b) 2" thick bottom layer	sft (m ²)	34.5 371	77.0 829		
9.3.3 Add extra in cement concrete floor topping, if finished with pigment and polishing.	sft (m ²)	9.68 104.2	14.2 153		
9.3.4 Extra labour for each storey above ground for mosaic, conglomerate stone, tiles and wooden floor.	sft (m ²)	5.45 58.6			
9.3.5 Providing & laying cement concrete 1:2:4 flooring 3" thick for workshop mixed with iron dust/chipping, including surface finishing and dividing into panels as per specification complete in all respects.	sft (m ²)	31.5 339	80.4 866		
9.3.6 Providing grey cement skirting or dado 3/8" thick, including rounding of corner & straightening of top edge and finishing to smooth surface after plastering complete in all respects.					
(a) 1:2 cement sand mortar	sft (m ²)	43.6 469	49.4 531		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) 1:3 cement, sand mortar	sft (m ²)	34.9 376	39 420		
(c) Extra if skirting or dado is finished with pigment of any colour.	sft (m ²)	1.82 19.5	3.75 40.3		
9.4 Mosaic / Mosaic Tile Flooring and Skirting				9.4.5 & 9.4.8	
9.4.1 Providing and laying 1-3/8" thick mosaic flooring, consisting of 3/8" mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips laid over 1" thick flooring of 1:2:4 cement concrete including rubbing, polishing and finishing complete in all respects.					(i) If glass or brass or Aluminum strips are used for panelling, it will be paid extra as per item No.9.4.5. (ii) Add 2% if pigment of approved quality and shade is used.
(a) using grey cement	sft (m ²)	100.6 1082	137 1471		
(b) using white cement	sft (m ²)	100.6 1082	139 1498		
9.4.2 Providing and laying 1-1/2" thick mosaic flooring, consisting of 1/2" mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips laid over 1" thick flooring of 1:2:4 cement concrete including rubbing, polishing & finishing complete in all respects.					If glass or brass or Aluminum strips are used for panelling, it will be paid extra as per item No.9.4.5
(a) using grey cement	sft (m ²)	100.6 1082	139 1495		
(b) using white cement	sft (m ²)	100.6 1082	142 1526		
9.4.3 Providing and laying floor of mosaic marble chips/high strength terrazo tiles of minimum size 12"x 12", of approved shade and design laid in 1:2 cement mortar over 3/4" thick bedding of cement sand mortar 1:2 including rubbing, polishing and finishing complete in all respects.				9.4.6	
(a) Tile 1" thick	sft (m ²)	35.1 378	98.1 1056		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Tile 2" thick	sft (m ²)	35.1 378	121.3 1306		
9.4.4 Rubbing and chemical polishing old grit/ mosaic floor and dado, including repairing voids, uneven surface, complete in all respects.	sft (m ²)	14.5 156	16.5 178		
Note: If no polishishing is done, the composite rate for 9.4.4 above shall be reduced at this rate.	sft (m ²)		4.87 52.5		
9.4.5 Providing and fixing 5 mm thick and 1-1/2" wide strips for dividing flooring into panels.				10.5.9.7	Labour for fixing already included in items No.9.3.1,9.3.2 9.4.1 & 9.4.2 of this chapter.
(a) Glass	ft (m)		3.63 11.91		
(b) Brass	ft (m)		182 595.50		
(c) Marble	ft (m)		4.79 15.73		
9.4.6 Providing tile skirting laid in 1:2 cement, sand mortar, over 3/4" thick cement mortar 1:2 complete in all respects.					
(a) Mosaic tiles 3/4" thick in grey cement.	sft (m ²)	44.2 475	112 1207		
(b) Mosaic tiles 3/4" thick in white cement with matching colour pigment.	sft (m ²)	44.2 475	135 1457		
9.4.7 Providing and laying mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1/2" thick cement plaster 1:3, including rubbing, polishing and finishing complete in all respects.					
(a) using grey cement					
(i) 3/8" thick	sft (m ²)	94.4 1016	119 1276		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(ii) 1/2" thick	sft (m ²)	94.4 1016	124 1340		
(b) using white cement					
(i) 3/8" thick	sft (m ²)	94.4 1016	121 1298		
(ii) 1/2" thick	sft (m ²)	94.4 1016	129 1392		
9.5 Ceramic / Porcelain Tile Flooring / Skirting				9.4.8	The composite rates under item 9.5 for tile flooring / skirting are for Sonex / Master or equivalent quality of tiles / skirting.
9.5.1 Providing and laying floor of local ceramic white glazed / mat tiles 1/4" thick of approved quality and size laid in cement sand mortar 1:2 over bed of 3/4" thick cement mortar 1:2, complete in all respects.	sft (m ²)	43.6 469	143 1542		
9.5.2 Providing and laying floor of local coloured ceramic glazed / mat tiles 1/4" thick of approved quality and size, laid in 1:2 cement sand mortar, jointed in white cement and matching pigment on a bed of 3/4" thick cement mortar 1:2, complete in all respects.	sft (m ²)	43.6 469	145 1566		
9.5.3 Providing and laying floor of imported ceramic glazed / mat tiles of approved quality/make/ shade/design, jointed in white cement and matching pigment on a bed of 3/4" thick cement sand mortar 1:2, complete in all respects					
a) Tile size upto 15"x 15"	sft (m ²)	43.6 469	127 1369		
b) Tile size more than 15"x 15"	sft (m ²)	43.6 469	153 1650		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
9.5.4 Providing and laying floor of local porecelain glazed tiles of approved quality and shade / design, jointed in white cement with matching pigment and laid over 3/4" thick 1:2 cement sand mortar, complete in all respects.					
(i) Tile size 16" x 16"	sft (m ²)	43.6 469	175 1889		
(ii) Tile size 24"x 24"	sft (m ²)	43.6 469	192 2062		
9.5.5 Providing and laying floor of imported porecelain glazed tiles of approved quality and shade / design, jointed in white cement with matching pigment and laid over 3/4" thick 1:2 cement sand mortar complete in all respects.					
(i) Tile size 16" x 16"	sft (m ²)	43.6 469	186 2004		
(ii) Tile size 24"x 24"	sft (m ²)	56.9 612	221 2379		
9.5.6 Providing and laying dado/skirting of white glazed tiles of approved quality and size 1/4" thick jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick, including finishing complete in all respects.	sft (m ²)	70.2 755	170 1826		
9.5.7 Providing and laying dado/skirting of glazed coloured tile 1/4" thick jointed in white cement with matching pigment and laid over 1:2 cement sand mortar 3/4" thick, including finishing complete in all respects..	sft (m ²)	70.2 755	172 1848		
9.5.8 Providing and laying dado/skirting of local porecelain glazed tiles of approved quality and shade / design, jointed in white cement with matching pigment and laid over 3/4" thick 1:2 cement sand mortar complete in all respects.	sft (m ²)	58.3 628	190 2046		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
9.6 Marble & Granite Stone Flooring / Skirting and Marble slabs				9.4.7	
9.6.1 Providing and laying marble stone tile in floor, laid in white cement with matching color pigment, over 3/4" thick cement sand mortar 1:2, including jointing, curing, rubbing and chemical polishing complete in all respects and as per instructions of Engineer-in-charge.					
(a) Black Marble					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	134 1442.7		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	202 2170		
iii) Tile size 12" x 12" x 1" (300 x 300 x 25 mm)	sft (m ²)	43.6 469	239 2575		
(b) Ziarat White					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	149 1604		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	218 2344		
iii) Tile size 12" x 12" x 1" (300 x 300 x 25 mm)	sft (m ²)	43.6 469	250 2690		
(c) Nowshera Pink					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	161 1731		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	239 2575		
iii) Tile size 12" x 12" x 1" (300 x 300 x 25 mm)	sft (m ²)	43.6 469	271 2921		
(d) Boticina					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	132 1420		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	164 1766		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
iii) Tile size 12" x 12" x 1" (300 x 300 x 25 mm)	sft (m ²)	43.6 469	196 2113		
(e) Lasbela					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	126.5 1362		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	161 1731		
iii) Tile size 12" x 12" x 1" (300 x 300 x 25 mm)	sft (m ²)	43.6 469	186 1997		
(f) China verona					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	120 1293		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	161 1731		
(g) Badal					
i) Tile size 12" x 12" x 1/2" (300 x 300 x 12 mm)	sft (m ²)	43.6 469	97.5 1050		
ii) Tile size 12" x 12" x 3/4" (300 x 300 x 19 mm)	sft (m ²)	43.6 469	138 1483		
9.6.2 Providing and laying marble stone slab 1" thick in kitchen, staircase etc., laid in white cement mortar with matching color pigment over 3/4" thick base of cement sand mortar 1:2, including jointing, curing, rubbing and polishing complete in all respects.					
(a) Black	sft (m ²)	43.6 469	325 3502		
(b) Ziarat White	sft (m ²)	43.6 469	347 3733		
(c) Nowshera Pink	sft (m ²)	43.6 469	358 3849		
(d) Boticina	sft (m ²)	43.6 469	272 2925		
(e) Lasbela	sft (m ²)	43.6 469	272 2925		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(f) China verona	sft (m ²)	43.6 469	293 3156		
(g) Badal	sft (m ²)	43.6 469	231 2486		
9.6.3 Extra labour for rounding of edges of marble slabs including polishing.	lft	9.68			
9.6.4 Providing and laying Granite stone size 24" x 24" having varying thickness from 7/8" to 1" in floors, laid in white cement mortar with matching color pigment over 3/4" thick base of cement sand mortar 1:2 at ground floor, including jointing, curing, rubbing and chemical polishing complete in all respects..					
(a) Indian Glaxy Black	sft (m ²)	43.6 469	573 6174		
(b) Embred Pearl	sft (m ²)	49.6 534	1157 12455		
(c) Silver Pearl	sft (m ²)	49.6 534	1042 11212		
(d) Ten Brown	sft (m ²)	49.6 534	580 6239		
(e) Red Robee	sft (m ²)	49.6 534	637 6860		
9.6.5 Providing and laying 1/2" thick marble stone tiles dado or skirting in white cement with matching color pigment, laid on 1/2" thick base of cement sand mortar 1:2, including jointing, curing, rubbing and chemical polishing complete in all respects..					
(a) Jet Black	sft (m ²)	33.3 358	120 1290		
(b) Ziarat White	sft (m ²)	33.3 358	135 1452		
(c) Nowshera Pink	sft (m ²)	33.3 358	147 1579		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(d) Boticina	sft (m ²)	33.3 358	118 1267		
(e) Lasbela	sft (m ²)	33.3 358	112 1209		
(f) China verona	sft (m ²)	33.3 358	106 1140		
(g) Badal	sft (m ²)	33.3 358	83.3 897		
9.6.6 Providing and laying 7/8" to 1" thick granite stone dado or skirting in white cement with matching color pigment, laid on 1/2" thick base of cement sand mortar 1:2, including jointing, curing, rubbing and chemical polishing complete in all respects.					
(a) Indian Glaxy Black	sft (m ²)	58 628	613 6599		
(b) Embred Pearl	sft (m ²)	58 628	1218 13112		
(c) Silver Pearl	sft (m ²)	58.3 628	1097 11809		
(d) Ten Brown	sft (m ²)	58.3 628	613 6599		
(e) Red Robee	sft (m ²)	58.3 628	673 7250		
9.6.7 Providing, laying, fixing "Grannitta tiles in floors 300 x 300 x 8 mm size imported" of approved shade and design jointed in pigment laid in 1:2 cement, sand mortar over 3/4" thick plaster/bedding complete in all respects.	sft (m ²)	58.3 628	592 6372		
9.7 Wooden Flooring / Skirting				9.3.10 & 9.4.11	
9.7.1 Providing shisham wood boarding or strips flooring 3/4" thick (sawn to required size) tongued and grooved and splayed rebated fixed with brass screws on kail wood battens 1-1/2" x 2" placed at 12" centre to centre, including two coats of bitumen laid hot on the base, complete in all respects.	sft (m ²)	56.9 612	363 3909		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
9.7.2 Providing deodar wood boarding or strips flooring 3/4" thick (sawn to required size) tongued and grooved or splayed rebated fixed with brass screws on kail wood battens 1-1/2" x 2" size, placed at 12" centre to centre, including two coats of bitumen laid hot on the base, complete in all respects.	sft (m ²)	58.1 625	569 6125		
9.7.3 Providing and laying imported laminated wood flooring of approved quality / design/size including the under lay, laid over cement concrete base, complete in all respects.	sft (m ²)	19.4 208	166 1782		<i>The cost of base for laminated wood flooring is not included in the rate and is payable separately</i>
9.7.4 Providing and laying imported laminated wood skirting of approved quality / design/ size including the under lay, laid over cement concrete base, complete in all respects.	sft (m ²)	9.68 104.2	95.4 1026		
9.8 Rubber / VenyleTile Flooring				9.3.9 & 9.4.9	
9.8.1 Rubber / Venyle tiles flooring, consisting of 12" x 12" x 1/8" rubber tiles of approved quality, laid on concrete flooring.	sft (m ²)	23.0 247	121 1307		The cost of base floor for rubber / venyle flooring is not included in the rate and is payable separately.
9.9 Paver Tile Flooring					
9.9.1 Providing and fixing paver tiles (7000 psi) unglazed of different colours manufactured by Izhar/ Envircrete, or equivalent, over 2" thick sand base, as per specifications and details given in the drawing, including providing,levelling and compacting sand and preparation of the surface prior to laying of pavers / interlocking tiles (a) 80 mm thick interlocking pavers (i) Grey/natural colour	sft (m ²)	23.0 247	95.3 1025		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(ii) Pigmented colour	sft (m ²)	23.0 247	98.7 1063		
(b) 60 mm thick interlocking pavers					
(i) Grey/natural colour	sft (m ²)	23.0 247	79.1 851		
(ii) Pigmented colour	sft (m ²)	23.0 247	82.6 889		
9.10 Miscellaneous Items					
9.10.1 Cleaning and washing mosaic, marble, glazed tiles, etc., in floor and dado with caustic soda mixture.	sft (m ²)	1.79 19.3	2.46 26.5		
9.10.2 Supplying and filling sand under floors.	sft (m ³)	3.63 39.1	20.1 217		

CHAPTER 10
SURFACE RENDERING

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 10 Surface Rendering of "Technical Specification for Railway Infrastructure Works, Volume I (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).
- (3) Rates include scraping of existing white wash, distemper, colour wash, emulsion, paint etc.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
10.1 Mud Plaster & Gobri Leeping				10.4.5	
10.1.1 Mud plaster on floor or on roof upto 20ft (6m) height (excluding gobri leeping):-					
(a) 1/2" thick	sft (m ²)	5.45 58.6	6.62 71.3		
(b) 1" thick	sft (m ²)	5.45 58.6	7.80 84.0		
10.1.2 Gobri leeping over roofs upto 20ft (6m) height	sft (m ²)	1.60 17.2	1.64 17.6		
10.2 Gypsum Plaster				10.4.6	
10.2.1 Gypsum plaster upto 20 ft (6 m) height:-					
(a) 3/8" thick (9 mm)	sft (m ²)	13.6 146	17.1 184		
(b) 1/2" thick (12 mm)	sft (m ²)	13.6 146	18.0 194		
(c) 3/4" thick (19 mm)	sft (m ²)	17.8 192	24.9 268		
10.2.2 Providing under coat of Gypsum sand in ratio 1:1 (average thickness 1/2") upto 20 ft (6 m) height.	sft (m ²)	14.2 153	16.2 175		
10.3 Cement Sand Plaster				10.3, 10.4.1, 10.4.2 & 10.4.3	
10.3.1 Cement sand plaster 1:2 upto 20 ft (6 m) height:-					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) 3/8" thick (9 mm)	sft (m ²)	18.2 195.4	23.9 257.3		
(b) 1/2" thick (12 mm)	sft (m ²)	18.2 195	25.6 275		
(c) 3/4" thick (19 mm)	sft (m ²)	23.0 247	34.5 371		
10.3.2 Cement sand plaster 1:3 upto 20 ft (6 m) height:-					
(a) 3/8" thick (9 mm)	sft (m ²)	18.2 195	22.2 239		
(b) 1/2" thick (12 mm)	sft (m ²)	18.2 195	23.6 254		
(c) 3/4" thick (19 mm)	sft (m ²)	23.0 247	31.2 336		
10.3.3 Cement sand plaster 1:4 upto 20 ft (6 m) height:-					
(a) 3/8" thick (9 mm)	sft (m ²)	18.2 195	21.8 235		
(b) 1/2" thick (12 mm)	sft (m ²)	18.2 195	22.8 246		
(c) 3/4" thick (19 mm)	sft (m ²)	23.0 247	30.3 326		
10.3.4 Cement sand plaster 1:5 upto 20 ft (6 m) height:-					
(a) 3/8" thick (9 mm)	sft (m ²)	18.2 195	21.5 231		
(b) 1/2" thick (12 mm)	sft (m ²)	18.2 195	22.3 240		
(c) 3/4" thick (19 mm)	sft (m ²)	23.0 247	29.6 319		
10.3.5 Cement sand plaster 1:6 upto 20 ft (6 m) height:-					
(a) 3/8" thick (9 mm)	sft (m ²)	18.2 195	20.9 225		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) 1/2" thick (12 mm)	sft (m ²)	18.2 195	21.8 235		
(c) 3/4" thick (19 mm)	sft (m ²)	23.0 247	28.5 307		
10.3.6 Stucco cement plaster 2" (50 mm) thick 1:2:4 (cement, sand and shingle), upto 20 ft (6 m) height.	sft (m ²)	43.3 466	76.6 825		
10.3.7 Providing and laying machine sprayed plaster 1/2" thick, using cement and chips zero gauge, over the existing plastered and roughened surface, upto 20 ft (6 m) height:-					
(a) Ratio 1:1	sft (m ²)	17.4 188	33.0 355		
(b) Ratio 1:1-1/2"	sft (m ²)	17.4 188	32.1 346		
(c) Ratio 1:2	sft (m ²)	17.4 188	31.7 341		
10.3.8 Extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	sft (m ²)	1.82 19.5	6.96 75.0		
10.3.9 Extra labour for making vertical or Horizontal grooves in cement plaster upto 1/2" width and 3/8" depth.	ft (m)	1.82 5.96			
10.3.10 Extra for making cement sand plaster mixed with waterproofing admixture (febtite powder, etc.).					
(a) Cement plaster 1:2	sft (m ²)		0.96 10.36		
(b) Cement plaster 1:3	sft (m ²)		0.68 7.29		
(c) Cement plaster 1:4	sft (m ²)		0.56 6.05		
10.4 Cement Sand Pointing				10.3,	
10.4.1 Cement sand pointing flush, upto 20 ft (6 m) height:-				10.4.1,&	
(a) Ratio 1:2	sft (m ²)	16.3 176	20.6 222	10.4.6	

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Ratio 1:3 (Cement & sand)	sft (m ²)	16.3 176	19.7 212		
10.4.2 Cement sand pointing 1:2 flush, on floor.	sft (m ²)	12.10 130	16.4 177		
10.4.3 Cement sand pointing struck joints on walls, upto 20 ft (6 m) height:-					
(a) Ratio 1:2 (Cement & sand)	sft (m ²)	18.8 202	23.0 248		
(b) Ratio 1:3 (Cement & sand)	sft (m ²)	18.8 202	22.1 238		
10.4.4 Pointing flush on stone work, upto 20 ft (6 m) height:-					
(a) In cement mortar 1:3	sft (m ²)	15.1 163	18.5 199		
(b) On stone work raised in cement mortar 1:3.	sft (m ²)	28.4 306	31.6 340		
10.5 Colour/Cement/White Washing				10.3, 10.4.7 & 10.4.8	
10.5.1 Colour washing:-					
(a) New surface:					
(i) One coat	sft (m ²)	1.31 14.1	2.09 22.5		
(ii) Two coat	sft (m ²)	1.96 21.1	3.26 35.1		
(b) Old surface:					
(i) One coat	sft (m ²)	1.31 14.1	1.80 19.4		
(ii) Two coat	sft (m ²)	1.96 21.1	2.94 31.7		
10.5.2 Cement washing.	sft (m ²)	6.05 65.1	6.72 72.3		
10.5.3 White washing:-					
(a) New surface:					
(i) One coat	sft (m ²)	1.31 14.1	1.78 19.1		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(ii) Two coats	sft (m ²)	1.96 21.1	2.61 28.1		
(iii) Three coats	sft (m ²)	2.54 27.4	3.47 37.4		
(b) Old surface:					
(i) One coat	sft (m ²)	1.31 14.1	1.67 18.0		
(ii) Two coats	sft (m ²)	1.96 21.1	2.51 27.0		
10.6 Distempering				10.1 & 10.4.9	
10.6.1 Priming coat of chalk under distemper.	sft (m ²)	1.69 18.2	2.19 23.6		
10.6.2 Distempering:-					
(a) New surface:					
(i) One coat	sft (m ²)	2.64 28.4	4.51 48.6		
(ii) Two coat	sft (m ²)	3.90 41.9	6.39 68.7		
(iii) Three coat	sft (m ²)	5.15 55.5	8.23 88.6		
(b) Old surface:					
(i) One coat	sft (m ²)	2.40 25.8	3.65 39.3		
(ii) Two coat	sft (m ²)	3.90 41.9	5.77 62.1		
10.7 Extra for Work above 20 ft Height					
10.7.1 Extra labour for mud, cement or Gypsum plaster and pointing from 20 (6 m) and above, for each additional 10 ft (3 m) height, or part thereof.	sft (m ²)	3.27 35.2			
10.7.2 Extra labour for white washing, colour washing, cement washing, priming coat and distempering etc. from 20 (6 m) height and above requiring scaffolding, for every additional 10 ft (3 m) height or part thereof.	sft per coat (m ²)	0.08 0.84			The height will be taken from the floor, roof or ground underneath, as the case may be on the side towards which the work is to be done.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
10.8 Miscellaneous Items					
10.8.1 Raking and washing joints of stone masonry (old work).	sft (m ²)	7.26 78.2			
10.8.2 Raking and washing joints of brick masonry (old work).	sft (m ²)	3.63 39.1			

CHAPTER 11**WOOD WORK**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 11 Wood Work of "Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) No extra rate is to be paid for sawing as the rates are inclusive of this.
- (3) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m) .

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.1 Wood Work (General)				11.4 & 11.5.1	
11.1.1 Providing plain wood work sawn, wrought, planned & fixed in position, including cost of nails and screws etc complete in all respects.					
(a) Deodar wood	cft (m ³)	932 32908	6072 214463		
(b) Shisham wood	cft (m ³)	1573 55558	4031 142373		
11.1.2 Sawing wood by hand:-					
(a) Soft wood (deodar, kail or chir)	sft (m ²)	6.35 68.4			
(b) Hard wood (shisham, kikar or teak)	sft (m ²)	12.7 137			
11.1.3 Sawing wood by machine:-					
(a) Soft wood (deodar, kail or chir)	sft (m ²)	5.09 54.8			
(b) Hard wood (shisham, kikar or teak)	sft (m ²)	7.65 82.3			
11.1.4 Making and fixing sun-shade of deodar wood, including fixing brackets.	sft (m ²)	143 1537	524 5639		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.2 Panelled & Glazed Doors & Windows				11.4, 11.5.1 & 11.5.2	
11.2.1 Providing first class deodar wood wrought joinery in doors and windows, etc. panelled, or panelled and galzed, or fully galzed, fixed in position, including deodar wood chowkat, holdfast, hinges, tower bolts, chocks, rubber stop, cleats/G.I. Clamp handles and chord with hooks, etc. complete in all respects (excluding sliding bolt and lock):-					
(a) Panelled					
(i) 2" thick	sft (m ²)	161 1737	1283 13810		
(ii) 1-3/4" thick	sft (m ²)	161 1737	1135 12214		
(iii) 1-1/2" thick	sft (m ²)	161 1737	1059 11399		
(b) Panelled & glazed with 5mm thick plain glass					
(i) 2" thick	sft (m ²)	161 1737	1169 12580		
(ii) 1-3/4" thick	sft (m ²)	161 1737	1095 11787		
(iii) 1-1/2" thick	sft (m ²)	161 1737	1028 11063		
(c) Fully glazed with 5mm thick plain glass					
(i) 2" thick	sft (m ²)	161 1737	1102 11863		
(ii) 1-3/4" thick	sft (m ²)	161 1737	1028 11071		
(iii) 1-1/2" thick	sft (m ²)	161 1737	975 10497		
11.2.2 Extra for brass fittings to doors and windows, except for hinges which shall be of iron:-					
(a) Deodar wood panelled or panelled and glazed or fully glazed.	sft (m ²)	5.25 56.6	44.1 475		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Deodar wood wire gauzed shutters.	sft (m ²)	2.07 22.3	29.6 318		
11.2.3 Providing & fixing approved quality rim lock.	each	321	948		
11.2.4 Providing and fixing handle lock of approved make/quality	each	426	1163		
11.2.5 Providing 1-1/2" thick deodar wood panelled or panelled and glazed, doors and windows, with mild steel chowkat as detailed below, fixed in position complete in all respects (excluding sliding bolt and lock) with:-					
(a) M.S. angle iron 1-1/2" x 1-1/2" x 1/4" welded with M.S. flat 2" x 1/4"					
(i) Panelled	sft (m ²)	167 1800	915 9845		
(ii) Panelled & glazed with 5mm thick plain glass	sft (m ²)	167 1800	877 9437		
(iii) Fully glazed with 5mm thick plain glass	sft (m ²)	167 1800	799 8602		
(b) M.S tee iron 1-1/2" x 1-1/2" x 1/4" welded with M.S. flat 1/2" x 1/4".					
(i) Panelled	sft (m ²)	167 1800	883 9507		
(ii) Panelled & glazed with 5mm thick plain glass	sft (m ²)	167 1800	846 9104		
(iii) Fully glazed with 5mm thick plain glass	sft (m ²)	167 1800	768 8269		
11.2.6 Providing first class deodar wood wrought joinery in sliding windows 1-1/2" thick in cabin fully glazed, fixed in position as per type 0-42/R-I including chowkat, hold fast, tower bolts, handles flat iron 2" x 1/4" on top and bottom and 1-1/2"x1/8" at bottom only fixed to frame, etc. complete in all respects.	sft (m ²)	279 3005	1348 14508		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.2.7 Providing casement windows (excluding chowkat) panelled or panelled and glazed, or fully glazed, flush, ledged & battened and fixed in position including holdfasts, hinges, etc. complete in all respect as per specification.					
(a) Deodar wood frame (3" x 1-1/2") & 3/4" panel	sft (m ²)	131.1 1411	634 6821		
(b) Deodar wood battened 3/4" & ledged 3/4", 2' apart	sft (m ²)	80.7 868.4	529 5695		
11.3 Framed, Ledged, Braced, Battened Doors & Windows				11.4, 11.5.1, 11.5.2, 11.5.5 to 11.5.7	
11.3.1 Providing deodar wood framed, braced and battened doors and windows, complete with iron fittings and fixed in position, excluding wooden chowkats, sliding bolts & lock, complete in all respect.					
(a) 2-1/4" thick, with 1-1/4" battens and 1" planks.	sft (m ²)	179 1923	1149 12370		
(b) 1-3/4" thick, with 1" battens and 3/4" planks.	sft (m ²)	161 1737	985 10608		
(c) 1-1/2" thick, with 3/4" battens and 3/4" planks.	sft (m ²)	155 1670	955 10285		
11.3.2 Providing 1" thick battened doors and windows fitted in position, complete with iron fittings, without chowkats.	sft (m ²)	240 2579	664 7145		
11.4 Wire Gauzed Doors & Windows				11.4, 11.5.1, 11.5.2, 11.5.8 & 11.5.9	
11.4.1 Providing and fixing first class deodar wood wrought joinery work in wire gauze doors and windows with 22 SWG G.I. wire gauze, 12x12 meshes per square inch including iron fittings, wooden strips etc. complete in all respects.					
(a) Deodar wood framing 1-3/4" thick with wire gauze fixed in position;					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(i) Without springs or spring hinges	sft (m ²)	174 1874	518 5575		
(ii) With springs or spring hinges.	sft (m ²)	174 1874	565 6084		
(b) Deodar wood framing 1-1/2" thick, with wire gauze fixed in position;					
(i) Without springs or spring hinges	sft (m ²)	174 1874	479 5152		
(ii) With springs or spring hinges.	sft (m ²)	174 1874	522 5619		
(c) G.I. Wire gauze 22 SWG, 12x12 meshes per square inches, fixed to chowkat with 3/4" thick deodar wood strip and screws.	sft (m ²)	65.5 706	169 1817		
(d) G.I. Wire gauze 22 SWG, 12x12 meshes per square inches, fixed to chowkat with 1/2" strip on separate frame of deodar wood 2"x2".	sft (m ²)	90.8 977	378 4074		
11.4.2 Providing and fixing spring hinges, to wire gauzed doors:-					
(a) Brass	each	96.8	757		
(b) Iron Enameled	each	96.8	317		
11.4.3 Providing and fixing G.I.wire gauze 22 SWG 12x12 meshes per square inch, fixed to steel window with flat iron patti 1/2" x 1/8" and machine made screws, complete in all respects.	sft (m ²)	25.2 271	64.1 690		
11.4.4 Providing and fixing expended metal, fixed to steel window with flat iron patti 1/2" x 1/8" and machine made screws, complete in all respects.	sft (m ²)	25.2 271	61.4 661		
11.5 Hallow & Solid Flush Doors				11.4, 11.5.1, 11.5.2 & 11.5.3	
11.5.1 Providing 1-1/2" thick hollow flush doors, with commercial ply (3 Ply) on both faces of deodar wood shutter frame 1-1/4" thick and partial wood braces at about 4" apart and deodar wood lipping 1-1/2" x 3/8", fixed in position including chromium plated fitting, complete in all respects (excluding chowkat lock & sliding bolt):	sft (m ²)	108.9 1172	336 3620		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.5.2 Providing 24 SWG aluminum kick plate, fixed in position with screws, on bottom rail of flush doors.	ft (m)	36.3 119.1	53.6 176		
a) 4" high	ft (m)	36.3 119.1	53.6 176		
b) 6" high	ft (m)	36.3 119.1	62.3 204		
c) 8" high	ft (m)	36.3 119.1	71.0 233		
11.5.3 Providing and fixing 1-1/2" thick hollow flush doors & windows with commercial ply (3 ply) on both faces of deodar wood shutter frame 1-1/4" thick and deodar wood braces at about 4" apart and deodar wood lipping 1-1/2"x 3/8" fixed to deodar wood dolly frame of full width of jamb for 9" to 13-1/2" walls made of 2"x 1-1/2" vertical battens and cross pieces at 6" c/c including commercial ply and deodar wood fillets, etc. complete in all respects. The rate also includes chromium plated fittings but excludes sliding bolts and lock.	sft (m ²)	242 2605	670 7217		
11.6 Wooden / Steel Chowkats for Doors & Windows				11.4 & 11.5.1, 11.5.2 & 11.5.8.2	
11.6.1 Providing and fixing deodar wood chowkat (3"x4") for doors, windows and C. windows, including holdfast etc. complete in all respects.	sft (m ²)	28.1 302	338 3643		
11.6.2 Providing and fixing MS sheet 16 gauge chowkat, molded in the shape of wooden chowkat including application of bitumen compound inside the chowkat and filling it with CC 1:3:6 including cost of hold fast 2 Nos. round iron at bottom of chowkat complete in all respects as per instruction of Engineer Incharge:					
(a) Size 2" x 5"	sft (m ²)	31.7 341	99.3 1069		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Size 2" x 10"	sft (m ²)	31.7 341	136 1469		
(c) Size 2" x 14"	sft (m ²)	47.6 512	185 1993		
11.6.3 Providing and fixing mild steel chowkat of doors, windows, C. windows, etc. including holdfast, making and threading holes for hinges etc. complete:-					
(a) M.S. angle iron 1-1/2" x 1-1/2" x 1/4" welded with M.S. Flat 2" x 1/4"	sft (m ²)	42.4 456	154 1661		
(b) M.S. tee iron 1-1/2" x 1-1/2" x 1/4" welded with M.S. Flat 1/2" x 1/4"	sft (m ²)	42.4 456	114 1230		
11.7 Wooden almirah/wardrobe/showcase/ cabin				11.4, 11.5.1 & 11.5.2	
11.7.1 Providing and fixing deodar wood almirahs:-					
(a) 12" depth, including boxing with 3/4" thick back, shelves, shutter and brass fittings, etc complete in all respects.	sft (m ²)	226 2431	1423 15319		
(b) 12" depth, with 3/4" thick shelves, shutters, brass fittings, etc. complete in all respects, (without boxing and back)	sft (m ²)	165 1780	729 7847		
11.7.2 Providing and fixing wooden box type wardrobe 22" deep, including 3/4" thick boxing and shelves, hanger rods, hard board back, drawers, brass fittings, locking arrangements handles, internal bolts, shoe, rods etc. including three coats of enamel paints on internal side, complete in all respects.					
(a) Partal wood boxing and back, deodar wood shelves and leaves, etc.	sft (m ²)	289 3106	1018 10959		If hollow flush door leaves 1" thick with commercial ply (3 ply) on both sides of deodar wood frame is used, the composite rate will be reduced by Rs.12.00 per Sft.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Deodar wood boxing, and deodar wood shelves and leaves and back etc.	sft (m ²)	289 3106	1482 15957		
11.7.3 Providing and fixing in position ward robe box type 2 ft deep made of lamination sheet including lamination board door shutters piano hinges, hawees handles, catchers, locks all labour and material complete.	sft (m ²)	313 3365	775 8344		
11.7.4 Providing & fixing in position show case made of lamination sheets depth 2'-0" and height 2'-0" to 8'-0" including all labour and material C.P. Brass mongry, sliding glass shutters, lamination sheet doors complete in all respects.	sft (m ²)	140 1506	563 6058		
11.7.5 Providing and fixing kitchen wall cabinet made of lamination board including all labour and material C.P. Brass mongrey and fittings etc. complete.	sft (m ²)	173 1864	751 8087		
11.7.6 Fixing wooden almirahs and wardrobes:-	sft (m ²)	83.2 895.5			
11.8 Wooden Planking/Shelves				11.4 & 11.5.1	
11.8.1 Providing deodar wood planking in eave boards, etc planed on both sides, rebated and fixed in position, including nails and screws, bolts and brackets:-					
(a) 1" (25 mm) thick	sft (m ²)	55.7 599	474 5101		
(b) 3/4" (19 mm) thick	sft (m ²)	55.7 599	369 3974		
(c) 1/2" (13 mm) thick.	sft (m ²)	55.7 599	265 2851		
11.8.2 Providing and fixing deodar wood shelves, including brackets:-					
(a) 1" (25 mm) thick	sft (m ²)	55.7 599	474 5101		
(b) 1-1/2" (31 mm) thick	sft (m ²)	55.7 599	683 7351		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(c) 2" (50 mm)thick.	sft (m ²)	55.7 599	892 9601		
11.9 Fixing Glass Panes to Doors & Windows				11.4 & 11.5.11	
11.9.1 Glazing with plate glass 5 mm thick including the cost of deodar wood fillets and putty, upto any height complete in all respects.	sft (m ²)	50.5 544	153 1646		
11.9.2 Glazing with plate glass 8 mm thick including the cost of deodar wood fillets and putty, upto any height complete in all respects	sft (m ²)	50.5 544	196 2110		
11.9.3 Glazing with tinted glass including the cost of deodar wood fillet, nails and putty, upto any height complete in all respects.					
(a) Tinted glass 5 mm thick	sft (m ²)	52.9 570	195 2097		
(b) Tinted glass 8 mm thick	sft (m ²)	52.9 570	247 2658		
11.9.4 Glazing with tampered plate glass 5 mm thick including the cost of deodar wood fillets and putty, complete in all respects.	sft (m ²)	50.5 544	231 2489		
11.9.5 Glazing with reinforced plate glass 5 mm thick including the cost of deodar wood fillets and putty, complete in all respects.	sft (m ²)	50.5 544	192 2070		
11.10 Doors & Windows Fixtures				11.5.1 & 11.5.2	
11.10.1 Providing & Fixing:-					
(a) Cleats for doors and windows, including hinges and screws.	each	62.9	188		
(b) Cleats with brass hooks for roof ventilators.	each	77.4	178		
(c) G.I. Hook with clamps for doors.	each	3.23	25.2		
(d) Doors stop of 1-1/2" dia rubber block.	each	12.10	50.6		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.10.2 Extra for providing and fixing iron double spring hinges, with brass fittings (it shall include brass finger plate, 6" tower bolt).	sft (m ²)	4.61 49.6	13.0 140		
11.10.3 Providing and fixing approved quality lock for drawer/box, complete in all respects.	each	60.5	66.5		
11.10.4 Providing and fixing hydraulic door closer heavy duty, approved superior quality including screws etc, complete in all respects.	each	315	2515		
11.10.5 Supplying and fixing tower bolts including screws for doors and windows, complete in all respects.					
(a) Iron Tower Bolts 6" long	each	12.10	100		
(b) Brass/chromium plated tower bolts 6" long	-do-	12.10	243		
11.10.6 Supplying and fixing handles with screws complete for doors and windows.					
(a) Iron handles	each	19.4	144		
(b) Brass/chromium plated handles	each	19.4	285		
11.10.7 Providing and fixing, sliding bolt to doors, complete in all respects.					
(a) Iron sliding bolt, 10" (250 mm) long	each	98.3	373		
(b) Iron sliding bolt, 12" (300 mm) long	each	98.3	428		
(c) Brass sliding bolt, 10" (250 mm) long	each	98.3	758		
(d) Brass sliding bolt, 12" (300 mm) long	each	98.3	868		
(e) C.P.brass sliding bolt, 10" (250 mm) long	each	98.3	1033		
(f) C.P.brass sliding bolt, 12" (300 mm) long	each	98.3	1198		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.11 Wooden Partitions				11.4 & 11.5.1	
11.11.1 Providing & fixing partition, including framework of deodar wood 2"x3" at 2' c/c, complete in all respects.					
(a) Sheets on one side of frame work;					
(i) Hard board	sft (m ²)	22.7 244	260 2799		
(ii) Ply wood Teak (3 Ply)	sft (m ²)	22.7 244	260 2799		
(iii) Ply wood commercial (3 Ply)	sft (m ²)	22.7 244	208 2240		
(iv) Chip Board 1/2" thick	sft (m ²)	22.7 244	208 2240		
(b) Sheets on both side of frame work;					
(i) Hard board	sft (m ²)	26.5 285	287 3093		
(ii) Ply wood Teak (3 Ply)	sft (m ²)	26.5 285	345 3715		
(iii) Ply wood commercial (3 Ply)	sft (m ²)	26.5 285	241 2596		
(iv) Chip Board 1/2" thick	sft (m ²)	26.5 285	241 2596		
11.12 Wooden / Gypsum Borar / Thermopore False Ceiling				11.4 & 11.5.1	
11.12.1 Providing and fixing false ceiling, including framework of deodar wood 2"x2" at 2' centres on either side, cost of M.S. Clamps, making holes in walls and repairing damaged surfaces complete in all respects,with:-					
(a) Hard board	sft (m ²)	30.3 326	305 3286		
(b) Chip Board 1/2" thick	sft (m ²)	30.3 326	283 3049		
(c) Ply wood Teak (3 Ply)	sft (m ²)	30.3 326	294 3168		
(d) Ply wood commercial (3 Ply)	sft (m ²)	30.3 326	279 2999		
(e) Thermopore 1" thick	sft (m ²)	30.3 326	273 2940		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.12.2 Providing and fixing false ceiling of Gypsum board of prime quality as per approved shade/design fixed/ laid on aluminum T-section size 1" x 1" x 1" x 1/8" hanged with aluminum string 1/16" dia fixed to rawl plug complete in all respect.	sft (m ²)	26.6 287	122 1317		
11.12.3 Providing and fixing false ceiling of Plaster of paris as per approved shade and design fixed/ laid on aluminum T-section size 1" x 1" x 1" x 1/8" hanged with aluminum string 1/16" dia fixed to rawl plug complete in all respect.	sft (m ²)	26.6 287	153 1643		
11.12.4 Providing and fixing false ceiling of Thermopore sheet of prime quality as per approved shade/design fixed/ laid on aluminum T-section size 1" x 1" x 1" x 1/8" hanged with aluminum string 1/16" dia fixed to rawl plug complete in all respect.	sft (m ²)	13.3 143.3	78.8 848		
11.13 Wooden Panelling				11.4 , 11.5.1 & 11.5.3.3	
11.13.1 Providing and fixing panelling including deodar wood frame work 1"x3/4" at appropriate spacing not exceeding 2' including cost of nails, screws and deodar wood moulding on top of panelling etc, complete in all respects, with:-					
(a) Hard board	sft (m ²)	28.2 304	141 1521		
(b) Vin board	sft (m ²)	28.2 304	134 1445		
(c) Chip board 1/2" thick	sft (m ²)	28.2 304	118 1268		
(d) Deodar wood 1/2" thick	sft (m ²)	64.5 695	345 3712		
11.13.2 Providing and fixing 3 ply over hard board/Vin board/Chip board panelling complete in all respects including the cost of deodar wood moulding on top of panelling:-					
(a) Commercial ply (3 ply)	sft (m ²)	28.2 304	58.1 626		
(b) Teak ply (3 ply)	sft (m ²)	28.2 304	110.9 1194		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
11.14 Miscellaneous Items					
11.14.1 Providing and fixing deodar wood architrave 3"x1-1/2" of approved design including moulding etc. complete in all respects.	ft (m)	96.8 318	328 1077		
11.14.2 Fixing doors & windows including chowkats, complete in all respects.					
(a) Fixing door, including chowkats	sft (m ²)	17.3 186			
(b) Fixing windows, including chowkats	sft (m ²)	8.64 93.0			
11.14.3 Supplying & fixing formica of approved quality and shade including cost of glue/solution, complete in all respects.	sft (m ²)	6.05 65.1	34.9 376		
11.14.4 Making and fixing 1" thick kail or chir wood notice board with frame, complete in all respects	sft (m ²)	80.7 868	225 2426		
11.14.5 Dismantling and refixing eave boards.	ft (m)	22.5 73.7			
11.14.6 Providing and fitting curtain railing of approved design / quality to doors and windows, fixed over 4"x3/4" deodar wood strip, including painting, complete in all respects.	ft (m)	15.1 49.6	158 519		

CHAPTER 12
PAINTING & VARNISHING

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in chapter 12 "Painting & Varnishing" of "Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) The rates include charges for scaffolding and other arrangements.
- (3) The rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
12.1 Cleaning & Scraping of Painted Surfaces				12.4	
12.1.1 Cleaning painted wood work with oil and water.	sft (m ²)	1.45 15.6	2.36 25.4		
12.1.2 Oiling wood work with boiled linseed oil.	sft (m ²)	1.45 15.6	4.17 44.9		
12.1.3 Scraping and brushing blisters of old paints, from wood work.	sft (m ²)	2.90 31.3			
12.1.4 Scraping, brushing and removing old paint, from metal surface.	sft (m ²)	14.5 156			
12.1.5 Burning off or rubbing down with pumice stone, old paint from wood work.	sft (m ²)	9.08 97.7	9.24 99.5		
12.1.6 Removing with caustic soda, old paint from wood work.	sft (m ²)	3.63 39.1	3.70 39.8		
12.1.7 Removing paint or varnish from wall.	sft (m ²)	7.26 78.2			
12.1.8 Scraping rust from old rail or girders.	sft (m ²)	10.89 117.2	11.35 122.2		
12.1.9 Chiselling old paint from brick work.	sft (m ²)	14.5 156	14.9 160		
12.1.10 Cleaning glasses, with chalk and spirit, etc.	sft (m ²)	9.68 104.2	9.92 106.8		
12.1.11 Cleaning and oiling rafter or rolled steel beams.	sft (m ²)	3.63 39.1	4.30 46.2		
12.2 Painting Old Surfaces				12.3, 12.4 & 12.5	
12.2.1 Painting corrugated surfaces, patent roofing, etc with oil paint;					

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) First coat	sft (m ²)	6.39 68.8	11.3 121		
(b) Each subsequent coat.	sft (m ²)	4.84 52.1	7.31 78.6		
12.2.2 Painting sashes, fanlights, glazed or gauzed doors and windows;					
(a) First coat	sft (m ²)	3.87 41.7	6.39 68.8		
(b) Each subsequent coat.	sft (m ²)	3.29 35.4	5.24 56.4		
12.2.3 Painting doors and windows, of type other than those under item 12.2.2;					
(a) First coat	sft (m ²)	6.39 68.8	10.74 116		
(b) Each subsequent coat.	sft (m ²)	4.84 52.1	8.11 87.3		
12.2.4 Painting guard bars, gates of iron bars, gratings, railing boiler tube, tie bar and wooden fencing (including standards, braces, etc) and similar open work;					
(a) First coat	sft (m ²)	3.87 41.7	6.10 65.7		
(b) Each subsequent coat.	sft (m ²)	3.29 35.4	5.00 53.8		
12.2.5 Painting fillets, framings, skirting, pipes, gutters and similar linear work, not exceeding 6" in girth;					
(a) First coat	ft (m)	3.29 10.80	5.52 18.1		
(b) Each subsequent coat.	ft (m)	2.32 7.62	4.03 13.2		
12.2.6 Painting small detached articles, not exceeding one square foot of painted surface;					
(a) First coat	each	13.92	18.2		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Each subsequent coat.	each	10.89	13.12		
12.2.7 Painting small detached articles, exceeding one square foot but not exceeding three square feet of painted surface;					
(a) First coat	each	27.8	40.7		
(b) Each subsequent coat.	each	15.7	22.2		
12.2.8 Painting railway girders and other heavy railway steel structures, including scaffolding upto 20ft height as per specifications complete in all respects.				12.4.4	
(a) First coat	sft (m ²)	9.68 104.2	17.5 189		
(b) Each subsequent coat.	sft (m ²)	7.87 84.7	10.04 108.1		
12.3 Painting New Surfaces				12.3 & 12.4.1 to 12.4.7 & 12.5	The rates of painting new surfaces under subsection 12.3 are by using best quality paints such as ICI, Berger or Equivalent as specified /approved by Engineer in-charge.
12.3.1 Preparing surface and painting corrugated surface, patent roofing etc;					
(a) Priming Coat	sft (m ²)	6.92 74.5	14.3 154		
(b) Each subsequent coat of paint.	sft (m ²)	3.61 38.8	9.66 104.0		
12.3.2 Preparing surface and painting sashes, fan light, glazed or guazed doors and windows, etc. any type (including edges);					
(a) Priming coat	sft (m ²)	3.61 38.8	7.89 85.0		
(b) Each subsequent coat of paint.	sft (m ²)	2.32 25.0	5.75 61.9		

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
12.3.3	Preparing surface and painting of doors and windows, of type other than those under item 12.3.2 (including edges);				
	(a) Priming coat	sft (m ²)	6.92 74.5	13.3 143.6	
	(b) Each subsequent coat of paint.	sft (m ²)	3.61 38.8	8.99 96.8	
12.3.4	Preparing surface and painting guard bars, gates of iron bars, gratings, railing, boiler tube, tie bar and wooden fencing (including standards, braces, etc.) and in similar open work;				
	(a) Priming coat	sft (m ²)	4.3 45.9	8.05 86.6	
	(b) Each subsequent coat of paint.	sft (m ²)	2.32 25.0	5.35 57.6	
12.3.5	Preparing surface and painting of fillets, framing, skirtings, pipes, gutters and similar linear work, not exceeding 6" girth.				
	(a) Priming coat	sft (m)	3.29 35.4	6.18 66.5	
	(b) Each subsequent coat of paint.	sft (m)	1.55 16.7	4.01 43.2	
12.3.6	Preparing surface and painting of small detached articles, not exceeding one sft of painted surface;				
	(a) Priming coat	per no.	14.5	27.9	
	(b) Each subsequent coat of paint.	per no.	7.24	17.9	
12.3.7	Preparing surface and painting of small detached articles, exceeding one sft. but not exceeding 3 sft of painted surface;				
	(a) Priming coat	per no.	28.4	54.0	
	(b) Each subsequent coat of paint.	per no.	12.7	31.9	

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
12.3.8 Extra for knotting and stopping to priming coat on new surface of wood.	sft (m ²)	0.73 7.82	0.81 8.73	12.4.4	
12.3.9 Preparing surface and painting with epoxy paint of approved quality, on heavy steel (foot over bridges) complete in all respect.	sft (m ²)	11.81 127.1	24.8 267		
12.3.10 Preparing surface and Painting railway girders and other heavy railway steel structures, including scaffolding upto 20ft height as per specifications complete in all respects;					
(a) Priming coat	sft (m ²)	12.71 136.8	20.6 222		
(b) Each subsequent coat.	sft (m ²)	7.21 77.6	12.55 135.1		
12.4 Painting with Emulsion Paint				12.3, 12.4.1, 12.4.8, 12.4.9 & 12.5	The rates of painting new surfaces under subsection 12.4 are by using best quality paints such as ICI, Berger or Equivalent as specified /approved by Engineer in-charge.
12.4.1 Preparing surface and painting with emulsion paint:-					
(a) Priming coat	sft (m ²)	4.43 47.7	17.61 189.5		
(b) Second and each subsequent coat	sft (m ²)	3.39 36.5	13.31 143.3		
12.4.2 Preparing surface and painting exteriors of buidings with weather shield paint:-					
(a) Priming coat	sft (m ²)	4.43 47.7	9.35 100.6		
(b) Second and each subsequent coat	sft (m ²)	3.39 36.5	7.15 77.0		
12.4.3 Preparing surface and painting interiors of buiding with textured paint complete in all respect.					
(a) Priming coat	sft (m ²)	4.43 47.7	17.55 188.9		
(b) Second and each subsequent coat	sft (m ²)	3.39 36.5	13.31 143.3		

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
12.5 Polishing				12.3, 12.4.1, 12.4.14, 12.4.15 & 12.5	
12.5.1 French polishing complete:-					
(a) On new work.	sft (m ²)	50.8 547	58.4 629		
(b) on old work.	sft (m ²)	26.6 287	30.5 328		
12.6 Varnishing				12.3, 12.4.1, 12.4.13 & 12.5	
12.6.1 Varnishing wood work, including cleaning and preparing surface:-					
(a) First Coat	sft (m ²)	3.87 41.7	11.24 121		
(b) Second Coat	sft (m ²)	1.94 20.8	7.54 81.2		
(c) Third Coat	sft (m ²)	1.94 20.8	6.39 68.8		
12.7 Painting/Varnishing above 20 ft					
12.7.1 Extra labour for painting, varnishing etc. from 20' height and above for every additional 10' height or part thereof requiring scaffolding.	sft (m ²)	1.94 20.8			The height will be taken from the floor, roof or ground underneath as the case may be, on the side towards which the work is to be done.
12.8 Painting with Coaltar/ Bitumen Solignum & Creosote				12.3, 12.4.1, 12.4.15 & 12.5	
12.8.1 Bitumen coating to plastered or cement concrete surface:-					
(a) 9 kg per 100 sft	sft (m ²)	3.63 39.1	14.41 155		
(b) 6.3 kg per 100 sft	sft (m ²)	2.90 31.3	10.49 113.0		
(c) 4.5 kg per 100 sft	sft (m ²)	2.4 25.8	7.79 83.8		

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
12.8.2 Coaltar painting:-					
(a) First Coat, laid hot	sft (m ²)	2.40 25.8	10.80 116.2		
(b) Second Coat, laid hot	sft (m ²)	1.16 12.5	6.59 71.0		
12.8.3 Solignum painting:-					
(a) one coat, applied hot	sft (m ²)	3.99 43.0	5.56 59.8		
(b) two coats, applied hot	sft (m ²)	6.05 65.1	8.69 93.5		
12.8.4 Cresote painting:-					
(a) one coat, applied hot	sft (m ²)	3.99 43.0	5.03 54.2		
(b) two coats, applied hot.	sft (m ²)	6.05 65.1	7.77 83.7		
12.9 Miscellaneous Items					
12.9.1 Painting traffic lane 5" wide with road marking enamel.	ft (m)	1.94 6.35	4.96 16.29		

CHAPTER 13**STRUCTURAL STEEL / ALUMINIUM WORKS**

Note:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in chapter 13 "Technical Structural Steel / Aluminium Works" of "Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) The rates for all finished works include the removal of surplus debris, unused material and by products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.1 Fabrication of Small Steel Works				13.3	
13.1.1 Fabrication of small steel work, such as gusset plates, knees, bends, stirrups, straps, rings, etc, including cutting, drilling, rivetting, handling, assembling and fixing but excluding erection in position.	per kg	86.4	185	13.4.1 to 13.4.7, 13.4.14 & 13.5	
13.1.2 Making bolts and nuts of steel rods.	per kg	69.3	201		
13.1.3 Hoop iron netted trelliss work fixed with nails.	sft (m ²)	53.78 578.92			
13.2 Fabrication of Heavy Steel Works, i.e. Trusses, Girder & Tanks etc.				13.3	
13.2.1 Fabrication of heavy steel works, with angle, tees, flat iron, round iron and sheet iron for making trusses, girders, tanks, gate leaves, special type iron grills, etc. including cutting, drilling, rivetting/welding, handling, assembling and fixing but excluding erection in position.	per kg	34.6	120	13.4.1 to 13.4.7, 13.4.14 & 13.5	
13.3 Rivetting Works				13.3,13.4.	
13.3.1 Rivitting 1/8" to 1 "				1,13.4.5 & 13.5	
a) Rivetting 1/8" to 3/8" dia.	per no.	1.00	7.60		
b) Revit 1/2"	per no.	1.69	13.8		
c) Revit 5/8"	per no.	1.89	28.3		
d) Revit 3/4"	per no.	4.11	42.6		
e) Revit 7/8"	per no.	4.60	58.5		
f) Revit 1"	per no.	5.45	60.4		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.3.2 Cutting out revits size 1/8" to 1 "					
a) Rivetting 1/8" to 3/8" dia.	per no.	2.66			
b) Revit 1/2"	per no.	4.45			
c) Revit 5/8"	per no.	6.17			
d) Revit 3/4" to 7/8"	per no.	8.47			
e) Revit 1"	per no.	10.4			
13.4 Erection of Small/Heavy Steel Works				13.4.1, 13.4.8 to 13.4.10 & 13.5	
13.4.1 Erection and fitting in position iron trusses, staging of water tanks, manufactured girders, steel tanks, etc.	per kg	9.68			
13.4.2 Fixing corrugated iron sheet, including rivetting, etc.	sft (m ²)	15.5 167			
13.4.3 Erecting cast iron sheet tanks upto 20' height.	per kg	11.65			
13.4.4 Erecting rolled steel beams or old rails in roofs, etc. erection and fixing in position.	per kg	7.4			
13.4.5 Erecting rolled steel beams or rails, erection for posts, gate leaves, special type iron grills, etc. (other than in roofs).	per kg	3.7			
13.4.6 Fitting and erection of gutters of sheet iron.	ft (m)	96.8 318			
13.5 Providing & Fixing Steel Doors & Windows				11.7	
13.5.1 Providing and fixing steel grated doors, complete with locking arrangement, angle iron frames 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre.	sft (m ²)	285 3070	873 9402		
13.5.2 Providing and fixing steel grated doors with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre, with locking arrangement.	sft (m ²)	298 3210	988 10636		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.5.3 Providing and fixing grating in opening, including fixing at site with flat iron 2" x 3/8" and 3/4" square bars at 4" centre to centre.	sft (m ²)	133.1 1433	412 4429.91		
13.5.4 Providing and fixing G.I. Wire gauze 24 SWG 12x12 meshes per square inch fixed to steel windows or doors with flat iron 1/16" thick and screws, complete in all respects.	sft (m ²)	29.3 316	39.2 422		
13.5.5 Providing and fixing steel windows with openable glazed panells, using beam section for frame 1-1/2" x 1" x 5/8" x 1/8", Z-section for leaves 3/4" x 1" x 3/4" x 1/8", T-section sashes 1" x 1" x 1/8", glass panes, wooden screed for glazing embedded over a thin layer of putty duly screwed with leaves, brass fittings holdfast, duly painted, complete in all respects, including all cost of material and labour, etc., as per approved design and as directed by the engineer-in-charge:-					
(a) without wire gauze:-					
(i) Glass Pane 3 mm thick.	sft (m ²)	119.7 1289	442 4762		
(ii) Glass Pane 4 mm thick.	sft (m ²)	119.7 1289	451 4859		
(iii) Glass Pane 5 mm thick.	sft (m ²)	119.7 1289	457 4924		
(b) fixed with wire gauze 22 SWG					
(i) Glass Pane 3 mm thick.	sft (m ²)	108.6 1169	471 5073		The composite rate will be reduced by Rs.6.00 per Sft. If 24 SWG wire gauze is used.
(ii) Glass Pane 4 mm thick.	sft (m ²)	108.6 1169	480 5170		
(iii) Glass Pane 5 mm thick.	sft (m ²)	108.6 1169	486 5235		
Note 1:					
Reduction in the composite rates under 13.5.5 above in case of fixed panels.	sft (m ²)		63.0 678		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.5.6 Providing and fixing in position steel pipe window, partly fixed and partly sliding made of hollow steel pipe of 16 guage, fixing wire guaze 22 SWG, glazing with tinted glass 5 mm thick including holdfast, handles, latches, hooks, sliding rail and wheels, painting including steel pipe grill complete	sft (m ²)	99.2 1068	402 4325		
13.5.7 Making and fixing steel door with 20 SWG sheet fixed on 1-1/4"x1-1/4"x1/8" angle iron frame & Chowkat of angle iron frame 2"x2"x3/16" including locking arrangement complete.	sft (m ²)	79.3 854	222 2393		
13.5.8 Providing and fixing panelled door of M.S. sheet, with forged door leaves of M.s. sheet 22 S.W.G. fitted in hollow frame chowkat 3"x4-1/2" made of M.S. sheet 18 S.W.G. filled with plain cement concrete 1:3:6 etc. complete, with all fittings and hammer painting, including carriage to site and fixing in position.	sft (m ²)	160 1721	417 4489		
13.6 Providing & Fixing Steel Railings					
13.6.1 Providing and fixing stair railing (all types and designs) of hard wood, including bends and corner screwed to 5/8" x 5/8" M.S. square bars 2.75 ft. high at 5.5 inch centre to centre fixed in steps of stairs, M.S. flat 1/2" x 1/4" welded to bars, painting/polishing 3 coats, etc. complete.	ft (m)	513 1683	997 3270		
13.6.2 Providing and fixing terrace railing of 2" i/d conduit pipe 16 SWG, welded with 5/8" x 5/8" square bar 2.75 ft. high fixed at 5" centre to centre, in reinforced cement concrete slab with suitable arrangement, complete in all respects, as per design and drawing.	ft (m)	120.3 395	700 2296		
13.6.3 Providing and fixing M.S. angle iron 1-1/2"x 1-1/2"x1/4" edge protector nozing of steps of stairs, having holdfast of 3/8" dia. M.S. bars 8" long welded at 2' centre to centre & embedded in cement concrete on steps, compete in all respects.	ft (m)	39.3 129.0	140 461		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.6.4 Providing and fixing stair railing of 2-1/2" i/d G.I. pipe welded with 5/8" x 5/8" square M.S. bars 2'-9" high fixed in each step, complete in all respects including painting three coats.	ft (m)	92.5 303	577 1893		
13.7 Providing & Fixing Steel Grill for Windows				13.3, 13.4.1, 13.4.14 to 13.4.17 & 13.5	
13.7.1 Providing and fixing M.S. flat 1/2" x 1/8" or M.S. Square 1/4" x 1/4" grill in windows, of approved design, including painting 3 coats, complete in all respects.	sft (m ²)	238 2559	321 3457		
13.8 Providing & Fixing Steel Gates				13.3, 13.4.1, 13.4.14 to 13.4.17 & 13.5	
13.8.1 Providing and fixing collapsible gate made of 2"x2"x1/4" tee iron at top and bottom, channel iron verticals 3/4" x 1/4"x1/4"x1/8" at 3" to 5" centre to centre (approximate) and flat iron crosses 3/4"x3/16" and best quality rollers at bottom of 3" diameter including holdfast, handles 12" long of 3/4"x1/4"x1/4"x1/8" channel iron, locking arrangement inside and outside, painting 3 coats of black Japan enamel, complete in working order.	sft (m ²)	299 3218	630 6782		
13.8.2 Providing and fixing 24 SWG G.I. sheet rolling shutter, consisting of steel frame of M.S. channel 2"x 1-1/4"x1/8" angle iron 1-1/2" x 1-1/2"x1/8" M.S. flat 1"x1/8" G.I. Pipe 1-1/2" dia, springs 2' centre to centre, rollers 24" SWG G-I. Covering 1 ft. x 1 ft. handles, holdfast, and painting three coats, complete in all respects.	sft (m ²)	204 2193	357 3839		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.9 Providing & Fixing Aluminum Doors & Windows				11.5	
13.9.1 Providing and fixing aluminum door consisting of chowkat of special type 'U' section 4"x1-3/4" and leaf of rectangular section 2" x1-3/4" jointed with sheet metal screws including pivoted hinges, 6" handles. 9" tower bolts on top and bottom and 5 mm thick glass fixed with special type rubber channel etc. complete in all respect as approved by the Engineer Incharge.	sft (m ²)	195 2101	1087 11703		Note:- For rate of items 13.9.1 to 13.9.4 (i) The composite rates are based on Pakistan Cables aluminum sections (1.6mm thickness) Natural colour.
13.9.2 Providing and fixing aluminum windows sliding, consisting of chowkat of special type 'U' section 4"x1" and leaf with vertical styles 2"x1", 1-1/4" x 1" bottom rail 2-1/2"x1" and top rail 1-1/4"x1" including latch, screws, sliding wheels, 5 mm. glass sheet fixed with special rubber channel etc. complete in all respects as approved by the Engineer Incharge.	sft (m ²)	131 1407	471 5068		(ii) For Pak Alco or other equivalent approved sections of the same thickness, the composite rates will be reduced by 20%, (iii) For sections 2mm in thickness, the composite rates will be increased by 10%.
13.9.3 Providing and fixing aluminum wire gauze shutter to windows consisting of special type section 1-5/8"x1/2" with Aluminum wire gauze of 16x16 mesh per square inch fixed with special rubber channel including cost of wheels, screws, etc. complete as approved by the Engineer Incharge.	sft (m ²)	30.3 326	151 1625		
13.9.4 Providing and fixing frame work of aluminum sections D 11, D 15 & D 16 and glazing with glass sheet fixed with rubber ring as per design and approved by Engineer Incharge:- (a) With plain glass sheet; (i) 5 mm thick (ii) 8 mm thick (b) With tinted glass sheet; (i) 5 mm thick (ii) 8 mm thick	sft (m ²) sft (m ²) sft (m ²) sft (m ²)	54.5 586 54.5 586 54.5 586 54.5 586	191 2061 230 2479 230 2479 274 2952		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.10 Providing & Fixing Barbed Wire Fencing / Razor Wire Fencing				13.3, 13.4.1, 13.4.14 to 13.4.17 & 13.5	
13.10.1 Providing and fixing barbed wire fencing consisting of 1-1/2"x1-1/2"x3/16" angle iron post 3-1/4 ft. long 5 to 6 ft. centre to centre embedded in cement concrete 1:2:4, base of size 9"x9"x12", and three rows of barbed wire, painting posts, etc., complete in all respects.	ft (m)	16.4 53.9	111 364		
13.10.2 Providing and fixing barbed wire fencing on compound wall, consisting of 1-1/2"x1-1/2"x 3/16" angle iron post 3' long 4' apart embedded in cement concrete 1:2:4 base of size 6" x 6" x 9" and 4 rows of barbed wire, including binding wire, painting posts, etc. complete in all respects.	ft (m)	27.4 0.90	146 4.79		
13.10.3 Providing and fixing barbed wire fencing with 4 horizontal and 2 number cross wires fixed with posts of R.C.C. 1:2:4 straining posts 7' x 9" x 9" at 100 centre to centre stiffening posts 7' x 6" x 6" at 50 ft. interval and intermediate post 7' x 5" x 5" at 8 ft. centre to centre, including cost of steel, its fabrication and placing of steel reinforcement, eye bolts, washers, etc. Also including base concrete (1:2:4) with shuttering and excavation as per P.R. Type No.F-64 complete.	ft (m)	39.2 129	128 421		(i) Vertical bars in straining and stiffening posts to be 4 Nos. each 1/2" dia for intermediate posts to be 4 Nos. of 3/8" dia. (ii) Stirrups for all posts to be 1/4" dia at 12" centre to centre.
13.10.4 Providing and fixing fencing consisting of 1-1/2" dia G.I pipe (medium quality) at 6' c/c embedded in cement concrete (1:2:4) base of size 9" x 9" x 18" deep and 2" x 2" G.I mesh chain link fencing wire fixed to pipe with G.I hooks complete in all respects.					Measurement shall be made of only mesh chain link area.
(a) 8 SWG chian link wire	ft (m)	109 357	353 1159		
(b) 10 SWG chian link wire	ft (m)	109 357	272 892		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
13.10.5 Supply and fixing razor barbed wire fencing consisting of 1 1/2"X1 1/2"X3/16" angle iron post 2'-6" long 10' center to center embedded in C.C 1:2:4 case of size 3"X9"X6" painting posts etc. Complete in all respect.	ft (m)	38.72 127.0	321.9 1056		
13.11 Miscellaneous Items					
13.11.1 Cutting rails, rolled steel joists and beams, with hacksaw:- (a) upto 6" size.	cut	290			
(b) above 6" size.	cut	436			
13.11.2 Cutting rails or rolled steel beams of size upto 6" with jim.	cut	136			
13.11.3 Bending rolled steel beams or rails.	bend	145	453		
13.11.4 Drilling holes, in plates upto 1/2" thick per inch dia or part thereof.	hole	51.4	-		
13.11.5 Extra for drilling holes in plates over 1/2" thick per inch dia, or part thereof.	hole	26.7	-		
13.11.6 Providing, cutting and fixing iron bars for 1/2" dia for barred windows.	bar	55.3	67.6		
13.11.7 Cutting G.I. Sheets.	each cut	29.8	-		
13.11.8 Notching web or foot of rail posts.	notch	645	858		

CHAPTER 14**PILE FOUNDATIONS**

Notes:

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 14 Pile Foundations of "Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).
- (3) If concrete mixer or high frequency vibrator, etc., is supplied by the department, all charges including depreciation will be recovered from the contractor.

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
14.1 Providing Cast-in-Situ Bored RCC Piles				14.4 & 14.5.1 to 14.5.4 & 14.5.6	
14.1.1 Boring of RCC piles in common soil, including lowering of steel cage and casting in situ bored reinforced concrete piles with nominal concrete mix, using 10% extra cement in dry mix, including all labour and material (except the cost of steel reinforcement and labour for its fabrications etc. which will be paid separately) complete in all respects as per specification.					
(a) Nominal Mix 1:2:4 (fc' =3000 psi)					
(i) 18" (450 mm) dia pile	ft (m)	893.1 2930	1233 4045		fc' = 28 days compressive cylinder strength of concrete.
(ii) 24" (600 mm) dia pile	ft (m)	1584 5197	2187 7176		
(iii) 30" (750 mm) dia pile	ft (m)	2354 7725	3293 10804		
(iv) 36" (900 mm) dia pile	ft (m)	3378 11083	4733 15528		
(v) 42" (1050 mm) dia pile	ft (m)	4600 15093	6443 21140		
(vi) 48" (1200 mm) dia pile	ft (m)	5995 19669	8403 27570		
(vii) 78" (1950 mm) dia pile	ft (m)	6673 21895	13031 42754		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Nominal Mix 1:1-1/2:3 (fc' = 4000 Psi)					
(i) 18" (450 mm) dia pile	ft	893	1281		
	(m)	2930	4204		
(ii) 24" (600 mm) dia pile	ft	1584	2273		
	(m)	5197	7458		
(iii) 30" (750 mm) dia pile	ft	2354	3426		
	(m)	7725	11242		
(iv) 36" (900 mm) dia pile	ft	3378	4926		
	(m)	11083	16161		
(v) 42" (1050 mm) dia pile	ft	4600	6706		
	(m)	15093	22001		
(vi) 48" (1200 mm) dia pile	ft	5995	8746		
	(m)	19669	28695		
(vii) 78" (1950 mm) dia pile	ft	6673.15	13936		
	(m)	21895	45725		
(c) Nominal Mix 1:1:2 (fc' = 5000 Psi)					
(i) 18" (450 mm) dia pile	ft	893	1366		
	(m)	2930	4482		
(ii) 24" (600 mm) dia pile	ft	1584	2423		
	(m)	5197	7951		
(iii) 30" (750 mm) dia pile	ft	2354	3660		
	(m)	7725	12009		
(iv) 36" (900 mm) dia pile	ft	3378	5263		
	(m)	11083	17269		
(v) 42" (1050 mm) dia pile	ft	4600	7165		
	(m)	15093	23509		
(vi) 48" (1200 mm) dia pile	ft	5995	9346		
	(m)	19669	30665		
(vii) 78" (1950 mm) dia pile	ft	6673	15521		
	(m)	21895	50925		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
14.2 Fabrication of Steel				14.4 & 14.5.1 to 14.5.4 & 14.5.6	The rate includes wastage and over laps, etc.
14.2.1 Fabrication of mild steel reinforcement conforming to ASTM A615 bar cage for RCC bored piles, including cutting, bending, laying in position, welding & fastening including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from the bars):-					
(a) Deformed steel bars (Grade 40)	per kg	9.68	104		
(b) Deformed steel bars (Grade 60)	per kg	16.34	115		
14.3 Testing of Piles				14.5.3 & 14.5.6	i)The cost of casting test piles shall be paid seperately under items nos. 14.1 ii) For intermediate test load rate may be calculated by interpolation.
14.3.1 Carrying out load test on piles including cost of making suitable load platform to hold the test load, arrangment of load material & its placing on load platform, providing and installation of necessary equipment like pressure gauge, hydraulic jack, removal and disposal of load material, complete in all respects including submission of test report as per specification.					
(a) 250 ton/sft	each test	73568	253455		
(b) 500 ton/sft	each test	77924	408217		
(c) 750 ton/sft	each test	79666	560366		
(d) 1000 ton/sft	each test	82280	713387		
14.4 Miscellaneous Items					
14.4.1 Providing & installation of liner of M.S sheet 10 mm thickness for piles.	kg	12.10	89.1		
14.4.2 Providing & fixing Elastromeric Bearing Pads imported including their fixing with epoxy coating as per approved design complete in all respects as per specification.	cm ³	6.05	40.70		

CHAPTER 15**WELL FOUNDATIONS**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 15 Well Foundations of "Technical Specification for Railway Infrastructure Works, Volume I, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).
- (3) Well curbs to be laid at spring level or as deep as possible.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
15.1 Excavation of Well in Dry				15.4.3	
15.1.1 Excavation of well in dry upto 20 ft below ground level, and disposal of soil within one chain as per specification.					
(a) in ordinary soil or sand;					
(i) from 0' to 5' (0 to 1.500 m) depth.	cft (m ³)	5.39 191			
(ii) from 5.1' to 10' (1.530 m to 3.000 m) depth	cft (m ³)	5.63 199			
(iii) from 10.1' to 15' (3.030 m to 4.500 m) depth.	cft (m ³)	6.34 224			
(iv) from 15.1' to 20' (4.530 m to 6.000 m) depth.	cft (m ³)	7.27 257			
(b) in hard soil;					
(i) from 0' to 5' (0 to 1.500 m) depth .	cft (m ³)	6.57 232			
(ii) from 5.1' to 10' (1.530 m to 3.000 m) depth	cft (m ³)	6.87 243			
(iii) from 10.1' to 15' (3.030 m to 4.500 m) depth.	cft (m ³)	7.51 265			
(iv) from 15.1' to 20' (4.530 m to 6.000 m) depth.	cft (m ³)	8.44 298			
(c) in shingle and gravel, etc.;					
(i) from 0' to 5' (0 to 1.500 m) depth.	cft (m ³)	14.2 501			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(ii) from 5.1' to 10' (1.530 m to 3.000 m) depth	cft (m ³)	14.7 518			
(iii) from 10.1' to 15' (3.030 m to 4.500 m) depth.	cft (m ³)	15.3 541			
(iv) from 15.1' to 20' (4.530 m to 6.000 m) depth.	cft (m ³)	16.4 580			
15.2 Dry Sinking of Wells				15.4.3	
15.2.1 Dry sinking of well, including loading, and removing excavated material within one chain as per specification.					
(a) In ordinary soil or sand					
(i) from 0' to 5' (0 m to 1.500 m) depth.	cft (m ³)	14.5 513			
(ii) from 5.1' to 10' (1.530 m to 3.000 m) depth.	cft (m ³)	21.8 769			
(iii) from 10.1' to 15' (3.030 m to 4.500 m) depth.	cft (m ³)	29.0 1026			
(iv) from 15.1' to 20' (4.530 m to 6.000 m) depth.	cft (m ³)	36.3 1282			
(v) from 20.1' to 25' (6.030 m to 7.500 m) depth.	cft (m ³)	43.6 1539			
(vi) from 25.1' to 30' (7.530 m to 9.000 m) depth.	cft (m ³)	50.8 1795			
(vii) from 30.1' to 35' (9.030 m to 10.500 m) depth.	cft (m ³)	58.1 2051			
(viii) from 35.1' to 40' (10.530 m to 12.000 m) depth.	cft (m ³)	65.3 2308			
(ix) from 40.1' to 45' (12.030 m to 13.500 m) depth.	cft (m ³)	72.6 2564			
(x) from 45.1' (13.530 m) to any depth.	cft (m ³)	79.9 2821			
(b) in hard soil;					
(i) from 0' to 5' (0 m to 1.500 m) depth.	cft (m ³)	25.4 897			
(ii) from 5.1' to 10' (1.530 m to 3.000 m) depth.	cft (m ³)	32.7 1154			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(iii) from 10.1' to 15' (3.030 m to 4.500 m) depth.	cft (m ³)	39.9 1410			
(iv) from 15.1' to 20' (4.530 m to 6.000 m) depth.	cft (m ³)	47.2 1667			
(v) from 20.1' to 25' (6.030 m to 7.500 m) depth.	cft (m ³)	54.5 1923			
(vi) from 25.1' to 30' (7.530 m to 9.000 m) depth.	cft (m ³)	61.7 2180			
(vii) from 30.1' to 35' (9.030 m to 10.500 m) depth.	cft (m ³)	69.0 2436			
(viii) from 35.1' to 40' (10.530 m to 12.000 m) depth.	cft (m ³)	76.2 2692			
(ix) from 40.1' to 45' (12.030 m to 13.500 m) depth.	cft (m ³)	83.5 2949			
(x) from 45.1' (13.530 m) to any depth.	cft (m ³)	90.8 3205			
(c) In hard strata such as shingle, gravel etc.;					
(i) from 0' to 5' (0 m to 1.500 m) depth.	cft (m ³)	39.9 1410			
(ii) from 5.1' to 10' (1.530 m to 3.000 m) depth.	cft (m ³)	47.2 1667			
(iii) from 10.1' to 15' (3.030 m to 4.500 m) depth.	cft (m ³)	54.5 1923			
(iv) from 15.1' to 20' (4.530 m to 6.000 m) depth.	cft (m ³)	61.7 2180			
(v) from 20.1' to 25' (6.030 m to 7.500 m) depth.	cft (m ³)	69.0 2436			
(vi) from 25.1' to 30' (7.530 m to 9.000 m) depth.	cft (m ³)	76.2 2692			
(vii) from 30.1' to 35' (9.030 m to 10.500 m) depth.	cft (m ³)	83.5 2949			
(viii) from 35.1' to 40' (10.530 m to 12.000 m) depth.	cft (m ³)	90.8 3205			
(ix) from 40.1' to 45' (12.030 m to 13.500 m) depth.	cft (m ³)	98.0 3462			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(x) from 45.1' (13.530 m) to any depth.	cft (m ³)	105.3 3718			
15.3 Wet Sinking of Wells				15.3, 15.4.1 to 15.4.6 & 15.4.7	
15.3.1 Wet sinking of well, in ordinary soil (value of C upto 5), for depths below spring level, as per specification, including charges of machinery, shoring, kentledge and removal of excavated spoil within one chain:-					The outer dimensions of the curb shall form basis of payment.
(a) from 0' to 10' (0 to 3.000 m) depth.	cft (m ³)	69.9 2469			C means cohesion of soil which is measure of clay content in the soil
(b) above 10.1' to 20' (3.030 m to 6.000 m) depth.	cft (m ³)	78.7 2778			
(c) above 20.1' to 30' (6.030 m to 9.000 m) depth.	cft (m ³)	96.8 3419			
(d) above 30.1' to 40' (9.030 m to 12.000 m) depth.	cft (m ³)	126 4445			
(e) above 40.1' to 50' (12.030 m to 15.000 m) depth.	cft (m ³)	140 4939			
(f) above 50.1' to 60' (15.030 m to 18.000 m) depth.	cft (m ³)	157 5556			
(g) above 60.1' to 70' (18.030 m to 21.000 m) depth.	cft (m ³)	161 5698			
(h) above 70.1' to 80' (21.030 m to 24.000 m) depth.	cft (m ³)	166 5848			
(l) above 80' (24.000 m) to any depth.	cft (m ³)	180 6350			
15.3.2 Wet sinking of well, in cohesive soil (value of C more than 5), for depths below spring level as per specification, including charges of machinery, shoring, kentledge and removal of excavated spoil within one chain:-					The outer dimensions of the curb shall form basis of payment.
(a) from 0' to 10' (0 to 3.000 m) depth.	cft (m ³)	96.8 3419			
(b) above 10.1' to 20' (3.030 m to 6.000 m) depth.	cft (m ³)	119 4193			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(c) above 20.1' to 30' (6.030 m to 9.000 m) depth.	cft (m ³)	135 4779			
(d) above 30.1' to 40' (9.030 m to 12.000 m) depth.	cft (m ³)	182 6442			
(e) above 40.1' to 50' (12.030 m to 15.000 m) depth.	cft (m ³)	242.0 8547			
(f) above 50.1' to 60' (15.030 m to 18.000 m) depth.	cft (m ³)	300 10583			
(g) above 60.1' to 70' (18.030 m to 21.000 m) depth.	cft (m ³)	370 13073			
(h) above 70.1' to 80' (21.030 m to 24.000 m) depth.	cft (m ³)	449 15874			
(l) above 80' (24.000 m) to any depth.	cft (m ³)	535 18913			
15.3.3 Wet sinking of well, in shingle, or gravel etc. for depths below spring level as per specification including charges of machinery, shoring, kentledge and removal of excavated spoil within one chain:-					The outer dimensions of the curb shall form basis of payment.
(a) from 0' to 10' (0 to 3.000 m) depth.	cft (m ³)	121 4274			
(b) above 10.1' to 20' (3.030 m to 6.000 m) depth.	cft (m ³)	155 5470			
(c) above 20.1' to 30' (6.030 m to 9.000 m) depth.	cft (m ³)	213 7514			
(d) above 30.1' to 40' (9.030 m to 12.000 m) depth.	cft (m ³)	293 10361			
(e) above 40.1' to 50' (12.030 m to 15.000 m) depth.	cft (m ³)	421 14865			
(f) above 50.1' to 60' (15.030 m to 18.000 m) depth.	cft (m ³)	605 21369			
(g) above 60.1' to 70' (18.030 m to 21.000 m) depth.	cft (m ³)	765 27027			
(h) above 70.1' to 80' (21.030 m to 24.000 m) depth.	cft (m ³)	968 34190			
(l) above 80' (24.000 m) to any depth.	cft (m ³)	1210 42737			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
<p>15.4 Providing & Laying RCC Curbs</p> <p>15.4.1 Providing, making and laying R.C.C. well curb in position, using coarse sand for concrete, including all kinds of forms, moulds, curing, shuttering, rendering and finishing the exposed surface, (including screening & washing of aggregate:-</p> <p>(a) Ratio 1:1-1/2:3.</p> <p>(b) Ratio 1:2:4.</p> <p>15.4.2 Providing and fixing structural steel cutting edge for well curb.</p>	<p>cft (m³)</p> <p>cft (m³)</p> <p>kg</p>	<p>261 9231</p> <p>261 9231</p> <p>9.7</p>	<p>509 17985</p> <p>486 17155</p> <p>91</p>	<p>15.3, 15.4.1 & 15.4.7</p>	<p>(i) The rate does not include cost of steel reinforcement and labour for its fabrication and laying in positions etc complete, which is payable separately under item 5.6.1.</p>
<p>15.5 Providing False Brick Masonry on Wells & its Dismantling</p> <p>15.5.1 Providing false brick masonry on wells in 1:8 cement sand mortar and its dismantling after sinking of wells to required depth including the scraping of the released brick sand their stacking within 100 ft (30 m).</p>	<p>cft (m³)</p>	<p>76.6 2704</p>	<p>209 7393</p>	<p>15.3.4, 15.4.2 & 15.4.7</p>	<p>In case scraped released bricks are used for brick masonry of buildings or other than buildings it shall be paid under the appropriate item of brick masonry with released bricks in chapter 6. Brick Masonry</p>

CHAPTER 16**PROTECTION & DIVERSION WORKS**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 16 River Protection & Diversion Works of "Technical Specification for Railway Infrastructure Works, Volume I, (2016)".
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).
- (3) The composite rates of the items of this chapter in which stone, boulders or spawl are used do not include the carriage of these materials from the quarry to site of work, which will be paid separately by road, and/or rail, whichever means of transport is approved before the commencement of work. The supply and carriage to site of work of all other materials, required in these items, is included in their composite rates.
- (4) The quantity of finished and completed item of work shall ordinarily form the basis of payment.
- (5) Where stone, boulder or spawl is issued from stock and contractor is paid for its carriage and/or labour only, or where such stone product is supplied, carried or handled by the contractor in which no laying is required, the actual sack measurement (without any reduction factor) shall form the basis of payment of supply or carriage of the stone, boulder or spawl, etc.
- (6) In case of the items in which the rates include carriage of sacks, bushing, pilchi, sarkanda or farash etc: within one mile (1.6 km):-
 - (i) the cost of the carriage within one mile (1.6 km) shall not be deducted from the carriage charges to follow thereafter from the point of supply.
 - (ii) if the site of work happens to be within one mile (1.6 km) of the source of supply, the materials will be collected and measured at site of work and no extra carriage would be admissible in such cases.
 - (iii) where the site of the work is situated at more than one mile (1.6 km) distance from the source of supply, the point of supply will be fixed carefully by the Engineer-in-charge in such a way that the carriage charges would be arrived at most economically. Extra carriage will be admissible from the place of supply of the material which will be considered its starting point. The demarcation of the place of supply will be pre-determined before calling the tenders.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.1 Cutting Pilchi, Farash & Sarkanda, making Bundles and Launching them in Position				16.2, 16.3.1 & 16.4	
16.1.1 Cutting pilchi, farash or Sarkanda including carriage within one mile (1.6 km).	cft (m ³)	11.04 390			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.1.2 Weaving mattresses.	cft (m ³)	20.9 738			
16.1.3 Making compact round pilchi, farash or sarkanda round bundles of specified size for the work.	cft (m ³)	14.2 500	15.6 550		Measured in the shape of compact round bundles and of size specified for the work, before filling at site.
16.1.4 Launching of Pilchi, Farash or sarkanda round bundle etc. and placing in position.	cft (m ³)	6.97 246			
16.2 Supplying jute bags, filling them with sand/earth and laying them in position				16.2, 16.3.2 & 16.4	
16.2.1 Supplying and filling jute bags:-					The rate does not include supply of sand or earth for filling bags, which will be paid extra.
(a) Supplying and filling jute bags 1.25 cft capacity, with sand or earth, sewing and stacking in dry.	bag	32.7	89.7		
(b) Supplying and filling jute bags 1.25 cft capacity, with sand or earth, sewing and laying in position under water.	bag	50.8	107.8		
16.2.2 Supplying & filling new jute bags:-					The rate does not include supply of sand or earth for filling bags, which will be paid extra.
(a) Supplying and filling new jute bags 4 to 5 cft capacity, with sand or earth, sewing and stacking in dry.	bag	72.6	187		
(b) Supplying and filling new Jute bags 4 to 5 cft capacity, with sand or earth, sewing and laying in position, under water.	bag	116.2	231		
16.2.3 Carriage of jute bags 1.25 cft capacity, filled with sand or earth:-					
(a) 1st, chain (30 m)	no.	2.90			
(b) 2nd, to 4th chain (30 m to 120 m) Rate for each chain (30 m)	no.	1.05			
(c) 5th and subsequent chains (120 m to 150 m and beyond) Rate for each chain (30 m)	no.	0.41			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.2.4 Carriage of new jute bags 4 to 5 cft capacity filled with sand or earth:-					
(a) 1st, chain (30 m)	no.	11.62			
(b) 2nd, to 4th chain (30 m to 120 m) Rate for for each chain (30 m)	no.	4.07			
(c) 5th and subsequent chains (120 m to 150 m and beyond) Rate for each chain (30 m)	no.	1.57			
16.3 Supplying boulders, Munj or Patha Trungers & G.I. Wire nets				16.2, 16.3 & 16.4	
16.3.1 Supplying and stacking within 5 chains (150 m):-					The rate of the boulder is at source and lead will be payable at the site of work against corresponding rate in chapter 2
(a) Boulders 9" (225 mm) and above	cft (m ³)	21.0 743	21.7 766		
(b) Over size shingle 3" to 9" (75 to 225 mm)	cft (m ³)	14.1 496	18.5 652		
(c) Mixed graded shingle	cft (m ³)	16.7 589	21.1 744		
16.3.2 Supplying and stacking Munj or Patha Trungers 6" x 6" (150 x 150 mm) mesh to hold 3 cft (0.085 m ³) of boulders.	each	90.8	152		
16.3.3 Providing and weaving G.I wire netting for wire crates with G.I wires of approved size (including siding & partition to make crate):-					
(a) 6" mesh;					
(i) 15 SWG wire	sft (m ²)	13.6 146	17.5 189		
(ii) 10 SWG wire	sft (m ²)	14.5 156	26.5 286		
(iii) 8 SWG wire	sft (m ²)	14.5 156	33.3 359		
(b) 4" mesh;					
(i) 15 SWG wire	sft (m ²)	17.4 188	23.4 252		
(ii) 10 SWG wire	sft (m ²)	19.4 208	37.4 402		
(iii) 8 SWG wire	sft (m ²)	19.4 208	47.5 512		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.3.4 Supplying welded mesh manufactured from 6" x 6" (150 x 150 mm) mesh, 8 SWG G.I. Wire, including all charges complete:-					
(a) 3.15 m x1.05 m x1.05 m fitted with two equally spaced divider 1.05 m x1.05 m	each		3737		
(b) 2.1 m x1.05 m x1.05 m fitted with one centrally spaced divider 1.05 m x1.05 m	each		2745		
(c) 1.05 m x 1.05 m x 1.05 m	each		1394		
16.3.5 Supplying weld mesh manufactured from 4" x 4" (100 mm x 100mm) mesh, 8 SWG G.I. Wire, including all charges complete:-					
(a) 3m x 1m x1m fitted with two equally spaced dividers 1m x 1m	each		4320		
(b) 2m x 1m x1m fitted with one centrally spaced dividers 1m x1m	each		3075		
(c) 1m x1mx1m	each		1647		
16.4 Supplying and dumping at site boulders/ brick bats etc. without boats.				16.2. 16.3 & 16.4	
16.4.1 Providing and laying shingle on top of bund, including handling of materials within three chains (90 m).	cft (m ³)	7.26 256	11.66 412		
16.4.2 Supplying & dumping at site without boat, including handling of materials within three chains (90 m):-					The rate includes supply of brickbats to site of work.
(a) Stone or boulder	cft (m ³)	12.7 449	13.4 472		
(b) Shingle or spawl	cft (m ³)	12.7 449	17.1 604		
(c) Brick bats	cft (m ³)	9.80 346	29.5 1041		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.5 Supplying and Dumping Boulders/Brick Bats with Boats				16.2. 16.3 & 16.4	
16.5.1 Supplying & dumping by boat, including loading into boats within three chains (150 m) lead, and hire charges of boat and boatman:-					
(a) stone or boulder	cft (m ³)	21.8 769	22.4 793		
(b) shingle or spawl	cft (m ³)	21.8 769	26.2 925		
(c) brickbats	cft (m ³)	18.9 667	38.5 1361		The rate includes supply of brickbats to site of work.
16.5.2 Providing and filling brickbats in crates (excluding cost of crates).	cft (m ³)	16.7 590	36.4 1284		same remarks as against item 16.5.1 (c) above
16.5.3 Supplying & filling bricks in crates and hand packing (excluding cost of crates).	cft (m ³)	20.3 718	33.0 1164		same remarks as against item 16.5.1 (c) above
16.5.4 Supplying and filling in wire crates, including sewing crates (excluding cost of crates):-					
(a) Stone or boulder	cft (m ³)	23.2 821	23.9 844		
(b) Shingle or spawl	cft (m ³)	23.2 820.6	27.6 976		
16.5.5 Extra for anchoring boat, for dumping by boats or tipping crates.	cft (m ³)	2.56 90.3			
16.5.6 Extra for tipping crates (in addition to anchoring boats).	cft (m ³)	11.62 410			
16.6 Providing and Laying Pilchi Revetment				16.2.1 16.3.1 & 16.4	
16.6.1 Providing and laying pilchi revetment, including carriage upto one mile (1.6	sft (m ²)	7.26 78.2	29.3 316		
16.6.2 Providing and laying surface protection with pilchi mattresses, carriage upto one mile (1.6 km).	sft (m ²)	18.2 195	20.6 222		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.7 Providing and laying Stone Pitching				16.2.2, 16.3.2 & 16.4	
16.7.1 Providing and laying stone pitching, dry hand packed, behind retaining walls.	cft (m ³)	14.5 513	15.2 536		
16.7.2 Providing and laying stone pitching, dry hand packed with surface levelled off to the correct section in floors of bridges along banks and in aprons etc.:-					
(a) Top layer on slope	cft (m ³)	36.3 1282	37.0 1305		
(b) Top layer on level	cft (m ³)	32.7 1154	33.3 1177		
16.7.3 Providing and laying stone or spawl filling, dry hand packed in floor of bridges along banks and in aprons etc.:-					
(a) On slope (other than top layer)	cft (m ³)	11.91 421	17.2 607		
(b) On level (other than top layer)	cft (m ³)	9.68 342	15.0 528		
16.7.4 Providing and laying stone pitching, hand packed with surface levelled off to the correct section and voids filled in 1:8 cement sand mortar, in floors of bridges along banks and in aprons etc.:-					The cost of pitching stone does not include the lead charges from quarry to site of work, as per note 3 at the start of this chapter.
(a) Top layer on slope	cft (m ³)	54.1 1909	74.5 2632		
(b) Top layer on level	cft (m ³)	50.4 1781	70.9 2503		
(c) Stone pitching on slope or level (other than top layer).	cft (m ³)	28.7 1014	49.1 1736		
16.7.5 Grouting stone pitching or apron, etc. in:-					
(a) cement sand mortar 1:3	sft (m ²)	16.4 176	53.6 577		
(b) cement sand mortar 1:8	sft (m ²)	15.1 163	39.3 424		

Description	Unit	Rate (PKR)		Railway Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
16.7.6 Sand grouting in stone apron, with high pressure hose.	sft (m ²)	5.57 59.9	14.9 161		
16.7.7 Grouting stone filling or pitching, with bajri.	sft (m ²)	9.08 97.7	32.2 346		
16.7.8 Removing stone and repitching hand packed, on slopes or level after making good damaged slope/portion.	cft (m ³)	42.5 1500			
16.8 Miscellaneous Items					
16.8.1 Collecting and stacking boulders from nullah beds or loose shale, or from any other site, within 3 chains (90 m) lead.	cft (m ³)	11.62 410			
16.8.2 Levelling and dressing stone filling under blocks and grouting with shingle.	cft (m ³)	9.68 342	11.00 389		
16.8.3 Grouting jharies between blocks with bajri.	cft (m ³)	9.68 342	25.1 886		
16.8.4 Breaking stone into spawls and stacking.	cft (m ³)	8.71 308			

CHAPTER 17**ROAD AND ROAD STRUCTURES**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 17 "Technical Road & Road Structures" of "Specification for Railway Infrastructure Works, Volume II, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused materials and by-products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
17.1 Sub Base Course					
17.1.1 Providing and laying sub-base course of brick on edge 4-1/2" thick, including compaction to required camber, grade and density.	cft (m ³)	38.5 1359	173 6128	17.5.2 to 17.5.4	The nominal thickness of bricks shall be taken for the purpose of measurement and payment.
17.1.2 Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHTO dry density, including carriage of all material to site of work, except crushed stone aggregate, for which supply within three miles is included in the rate.				17.5.2 to 17.5.4	No reduction in the rate will be made if carriage of crushed stone aggregate or gravel is less than three miles.
(a) Pit run or bed run gravel	cft (m ³)	33.5 1182	39.1 1381		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) Crushed stone aggregate as per specifications	cft (m ³)	33.5 1182	41.4 1462		(i) For the carriage of gravel or crushed stone aggregate, the whole distance to the site of work shall be calculated on the basis of the rate of actual means of transport used in carriage, i.e. road and/or rail, as the case may be and it shall be reduced by the carriage rates for the 1st three miles (4.8 km). (ii) It shall be payable from the nearest approved quarry. (iii) The quantity of material for payment of carriage shall be taken on the basis of the finished and consolidated measurements of the sub-base.
17.2 Base Course				17.6.2 to 17.6.4	
17.2.1 Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone, screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHTO dry density, including carriage of all materials to site of work except crushed stone aggregate, for which supply within three miles is included in the rate.	cft (m ³)	33.5 1182	47.6 1680		Same as item against 17.1 2

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
17.3 Bitumen Work & Surfacing					
17.3.1 Providing and laying bituminous priming coat, using 10 lbs, kerosene oil and 10 lbs bitumen (binder) per 100sft.	sft (m ²)	1.45 0.16	11.2 1.21	17.8.1 to 17.8.4	
17.3.2 Providing and laying bituminous tack coat using 15 lbs of bitumen (binder) per 100sft.	sft (m ²)	1.45 0.16	8.90 0.96	17.9.1 to 17.9.4	
17.3.3 Providing surface treatment to roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating and spraying bitumen, spreading bajri and rolling with road roller (including its operation cost, fuel and hire charges, etc) etc, complete, including carriage of all materials to site of work except crushed stone aggregate, for which supply within three miles is included in the rate.				17.10.1 to 17.10.4	i) No reduction in the rate will be made if carriage of crushed stone aggregate or gravel is less than three miles. ii) For carriage of crushed stone same remarks as against item 17.1.2 above
(a) 1st coat;					
(i) 40 lbs, bitumen, and 5.5 cft bajri of nominal size 1" per 100sft	sft (m ²)	2.79 30.1	24.2 260		
(ii) 35 lbs, bitumen and 4.0 cft bajri of nominal size 3/4"per 100sft.	sft (m ²)	2.79 30.1	21.4 230		
(b) 2nd coat;;					
(i) 25 lbs, bitumen and 2.75 cft bajri of nominal size 1/2"per 100sft.	sft (m ²)	2.15 23.1	15.6 168		
(ii) 18 lbs, bitumen and 2.0 cft bajri of nominal size 3/8" per 100sft.	sft (m ²)	2.15 23.1	11.72 126		
(c) 3rd coat;					
(i) 14 lbs, bitumen and 1.5 cft bajri of nominal size 1/4"per 100sft.	sft (m ²)	1.47 15.8	8.63 92.9		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
17.3.4 Resurfacing of road, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating and spraying of bitumen, and spreading bajri/crushed stone aggregate and rolling with road roller (including its operation cost, fuel and hire charges, etc) complete, including carriage of all materials to site of work except crushed stone aggregate, for which supply within three miles is included in the rate.					
(a) Bitumen and bajri					
(i) 22 lbs, bitumen and 2.5 cft bajri of nominal size 1/2".	sft (m ²)	1.33 14.3	13.0 140		
(ii) 20 lbs, bitumen, and 2.0 cft bajri of nominal size 3/8".	sft (m ²)	1.33 14.31	11.79 126.92		
17.3.5 Providing and laying plant premix bituminous carpet mixed in batching plant and laid with paver premix including compaction, finishing to required camber, grade and density (including seal coat) complete in all respect:-				17.11.1 to 17.11.4	Mixing and rolling to be done by mechanical means.
(a) 4.0% Bitumen	sft per in thick (m ² per cm thick)	10.9 46.0	42.4 1.8		
(b) 5.0% Bitumen	sft per in thick (m ² per cm thick)	10.9 45.99	48.5 2.1		
17.3.6 Scarifying old road surface, including removal of debris within one chain.	sft (m ²)	2.40 25.8			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
17.4 Dry Brick Pavement/Soling				17.5.1 & 17.5.4	
17.4.1 Providing and laying dry brick pavement/soling in streets or roads, etc. sand grouted, laid in proper camber, including preparation, watering, compaction of bed to proper camber and sand cushion.	cft (m ³)	29.8 1051	165 58.2		The nominal thickness of bricks shall be taken for the purpose of measurement and payment.
17.5 Road Edging					
17.5.1 Providing and laying road edging of 3" wide and 9" deep brick on edge, complete in all respect:-	ft (m)	8.47 27.8	27.0 88.6	17.7.1 to 17.7.4	
17.5.2 Providing and laying road edging of 6" wide and 18" deep precast concrete kerb stone (1:2:4) of approved quality complete in all respect.	ft (m)	16.9 55.6	144 472	17.12.1 to 17.12.3	
17.6 Supplying and fixing Cats - Eye.				17.13.1 to 17.13.3	
17.6.1 Cats-eye single (Flush / raised surface) Plastic	each	182	457		
17.6.2 Cats-eye double (Flush / raised surface) Plastic	each	182	490		
17.6.3 Cats-eye single (Flush / raised surface) Aluminum	each	182	622		
17.6.4 Cats-eye double (Flush / raised surface) Aluminum	each	182	721		

CHAPTER 18**INSTALLATION OF TUBE WELLS**

Note:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 18 Installation of Tube Well5 of "Technical Specification for Railway Infrastructure Works, Volume II, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
18.1 Percussion Drilling for Tube Well				18.2,	
18.1.1 Drilling of Bore holes for tube well by percussion method in all types of soil except shingle and rock, from ground level upto 100 ft (30 m) depth, including sinking, collection of 100 % corings and withdrawing of casing pipe, complete as per specifications.				18.3.1 to	
				18.3.6 &	
				18.4.1	
(a) Internal dia of bore 3"(75 mm)	ft	51.4			
	(m)	169			
(b) Internal dia of bore 4"(100 mm)	ft	78.8			
	(m)	259			
(c) Internal dia of bore 5"(125 mm)	ft	156			
	(m)	510			
(d) Internal dia of bore 6" (150 mm)	ft	246			
	(m)	808			
(e) Internal dia of bore 8" (200 mm)	ft	394			
	(m)	1293			
(f) Internal dia of bore 10" (250 mm)	ft	492			
	(m)	1616			
(g) Internal dia of bore 12"(300 mm)	ft	537			
	(m)	1763			
18.1.2 Drilling of Bore holes for tube well by percussion method in all types of soil except shingle and rock, from a depth of 100.1 ft to 200 ft (30 to 60 m) below ground level, including sinking, collection of 100 % corings and withdrawing of casing pipe, complete as per specifications.					
(a) Internal dia of bore 5"(125 mm)	ft	185			
	(m)	606			
(b) Internal dia of bore 6" (150 mm)	ft	281			
	(m)	923			
(c) Internal dia of bore 8" (200 mm)	ft	455			
	(m)	1491			
(d) Internal dia of bore 10" (250 mm)	ft	537			
	(m)	1763			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(e) Internal dia of bore 12" (300 mm)	ft (m)	591 1939			
18.1.3 Drilling of Bore holes for tube well by percussion method in all types of soil except shingle and rock, from a depth of 200.1 ft to 300 ft (60 to 90 m) below ground level, including sinking , collection of 100 % corings and withdrawing of casing pipe, complete as per specifications.					
(a) Internal dia of bore 5" (125 mm)	ft (m)	219 718			
(b) Internal dia of bore 6" (150 mm)	ft (m)	311 1020			
(c) Internal dia of bore 8" (200 mm)	ft (m)	492 1616			
(d) Internal dia of bore 10" (250 mm)	ft (m)	591 1939			
(e) Internal dia of bore 12" (300 mm)	ft (m)	657 2154			
18.1.4 Drilling of Bore holes for tube well by percscsion method in all types of soil except shingle and rock, from a depth of 300.1 ft to 400 ft (90 to 120 m) below ground level, including sinking, collection of 100 % corings and withdrawing of casing pipe, complete as per specifications.					
(a) Internal dia of bore 8" (200 mm)	ft (m)	537 1763			
(b) Internal dia of bore 10" (250 mm)	ft (m)	657 2154			
(c) Internal dia of bore 12" (300 mm)	ft (m)	739 2424			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
<p>18.2 Direct Rotary/Reverse Rotary Drilling in Common Soil</p> <p>18.2.1 Direct rotary/ reverse rotary drilling of bore for tube wells in all type of soil except shingle, gravel and rock including sinking, collection of 100 % corings & withdrawing of casing pipe complete as per specifications.</p> <p>(a) From ground level to 250 ft (75 m), below ground level:</p> <p>(i) 15" (375 mm) to 18" (450 mm) i/d</p> <p>(ii) 20" (500 mm) to 26" (650 mm) i/d</p> <p>(b) Exceeding 250 ft (75 m) depth below</p> <p>(i) 15" (375 mm) to 18" (450 mm) i/d</p> <p>(ii) 20" (500 mm) to 26" (650 mm) i/d</p>	<p>ft (m)</p> <p>ft (m)</p> <p>ft (m)</p> <p>ft (m)</p>	<p>603 1980</p> <p>868 2847</p> <p>748 2455</p> <p>1123 3683</p>		<p>18.2, 18.3.1 to 18.3.6 & 18.4.1</p>	
<p>18.3 Direct Rotary/Reverse Rotary Drilling in Shingle & Gravel</p> <p>18.3.1 Direct rotary/ reverse rotary drilling of bore for tube wells in shingle, gravel and rock, including sinking, collection of 100 % corings & withdrawing of casing pipe complete as per specifications.</p> <p>(a) From ground level to 250 ft (75 m), below ground level:</p> <p>(i) 12" (300 mm) to 18" (450 mm) i/d</p> <p>(ii) 20" (500 mm) to 26" (650 mm) i/d</p> <p>18.3.1 (b) Exceeding 250 ft (75 m) depth below ground level:</p> <p>(i) 12" (300 mm) to 18" (450 mm) i/d</p> <p>(ii) 20" (500 mm) to 26" (650 mm) i/d</p>	<p>ft (m)</p> <p>ft (m)</p> <p>ft (m)</p> <p>ft (m)</p>	<p>1361 4464</p> <p>1840 6038</p> <p>1633 5357</p> <p>2721 8929</p>		<p>18.2, 18.3.1 to 18.3.6 & 18.4.1</p>	<p>Location and depth of shingle, gravel or rock is to be determined from the bore log.</p>

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
18.4 Collection & Preservation of Coring and Water Samples from Bore Holes				18.3.1.7	
18.4.1 Providing strong box of deodar wood 4' x 2½' x 9" with compartments, lock and locking arrangement, and preserving in it the corings / samples of strata collected from bore hole and supply to the approved soil testing laboratory for testing.	job for each bore hole	1042	16040		
18.4.2 Collection and submission at approved soil testing laboratory of two water samples in bottles from each bore hole for testing.	set of two bottles per bore hole	436	490.6		
18.5 Providing & Installing Brass Strainers				18.3.2 & 18.4.2	
18.5.1 Providing and installing Brass Strainer of approved make \ quality in tubewell bore hole, including socket, special sockets, studs etc. complete as per specification.					Cost/labour of jointing both ends is included in the rate.
(a) 2" (50 mm) i/d 5/32" (4 mm) thick	ft (m)	26.1 85.8	765 2511		
(b) 3" (75 mm) i/d 5/32" (4 mm) thick	ft (m)	26.1 85.8	1293 4243		
(c) 4" (100 mm) i/d 3/16" (5 mm) thick	ft (m)	34.8 114.3	1567 5140		
(d) 5" (125 mm) i/d 3/16" (5 mm) thick	ft (m)	40.2 132	1693 5555		
(e) 6" (150 mm) i/d 3/16" (5 mm) thick	ft (m)	43.6 142.9	1642 5389		
(f) 7" (175 mm) i/d 3/16" (5 mm) thick	ft (m)	52.3 172	1948 6392		
(g) 8" (200 mm) i/d 3/16" (5 mm) thick	ft (m)	65.3 214	2600 8530		
(h) 9" (225 mm) i/d 3/16" (5 mm) thick	ft (m)	65.3 214	2655 8710		
(i) 10" (250 mm) i/d 3/16" (5 mm) thick	ft (m)	74.7 245	2774 9102		
(j) 10" (250 mm) i/d 1/4" (6 mm) thick	ft (m)	74.7 245	3434 11267		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(k) 12" (300 mm) i/d 1/4" (6 mm) thick	ft (m)	74.7 245	3710 12173		
(l) 15" (375 mm) i/d 1/4" (6 mm) thick	ft (m)	87.1 286	4713 15462		
(m) 18" (450 mm) i/d 1/4" (6 mm) thick	ft (m)	87.1 286	5186 17014		
(n) 20" (500 mm) i/d 1/4" (6 mm) thick	ft (m)	104.5 343	5852 19201		
(o) 22" (550 mm) i/d 1/4" (6 mm) thick	ft (m)	104.5 343	6656 21839		
18.6 Providing & Installing M.S Bail Plug				18.3.2 & 18.4.2	
18.6.1 Providing and installing M.S. Bail plug of approved make / quality in tubewell bore hole complete as per specification:-					In the case of increase or decrease in the length of bail plug, the rate will be increased or decreased as per rates given against item No. 18.7.1 of this chapter for the respective diameter.
(a) 2" (50 mm) i/d 1.5 ft (450 mm) long.	each	41.1	648		
(b) 3" (75 mm) i/d 1.5 ft (450 mm) long.	each	41.1	876		
(c) 4" (100 mm) i/d 2 ft (600 mm) long.	each	51.4	1551		
(d) 5" (125 mm) i/d 2 ft (600 mm) long.	each	51.4	1584		
(e) 6" (150 mm) i/d 2 ft (600 mm) long.	each	73.5	2159		
(f) 7" (175 mm) i/d 2 ft (600 mm) long.	each	73.5	2452		
(g) 8" (200 mm) i/d 2 ft (600 mm) long.	each	85.7	2530		
(h) 9" (225 mm) i/d 2 ft (600 mm) long.	each	85.7	2727		
(i) 10" (250 mm) i/d 2 ft (600 mm) long.	each	85.7	3676		
(j) 12" (300 mm) i/d 2 ft (600 mm) long.	each	102.9	4250		
(k) 15" (375 mm) i/d 2 ft (600 mm) long.	each	102.9	5255		
(l) 18" (450 mm) i/d 2 ft (600 mm) long.	each	128.6	6068		
(m) 20" (500 mm) i/d 2 ft (600 mm) long.	each	137	6627		
(n) 22" (550 mm) i/d 2 ft (600 mm) long.	each	137	7286		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
18.7 Providing & Installing M.S Blind Pipe				18.3.2 & 18.4.2	
18.7.1 Providing and installing M.S. blind pipe of socketed & welded, M.S. reducer (where necessary) of approved make / quality in tubewell bore hole, including jointing/welding with strainer, etc. complete as per specification:-					
(a) 2" (50 mm) i/d 1/8" (3 mm) thick	ft (m)	51.7 169.8	250 819		
(b) 3" (75 mm) i/d 1/8" (3 mm) thick	ft (m)	51.7 169.8	349 1144		
(c) 4" (100 mm) i/d 1/8" (3 mm) thick	ft (m)	64.7 212	450 1475		
(d) 5" (125 mm) i/d 3/16" (5 mm) thick	ft (m)	64.7 212	802 2630		
(e) 6" (150 mm) i/d 3/16" (5 mm) thick	ft (m)	92.4 303	824 2703		
(f) 7" (175 mm) i/d 3/16" (5 mm) thick	ft (m)	92.4 303	1038 3407		
(g) 8" (200 mm) i/d 3/16" (5 mm) thick	ft (m)	107.8 354	1285 4215		
(h) 9" (225 mm) i/d 3/16" (5 mm) thick	ft (m)	107.8 354	1571 5154		
(i) 10" (250 mm) i/d 1/4" (6 mm) thick	ft (m)	107.8 354	1923 6309		
(j) 12" (300 mm) i/d 1/4" (6 mm) thick	ft (m)	129.4 424	2329 7643		
(k) 15" (375 mm) i/d 1/4" (6 mm) thick	ft (m)	129.4 424	2714 8906		
(l) 18" (450 mm) i/d 1/4" (6 mm) thick	ft (m)	161.7 531	3429 11250		
(m) 20" (500 mm) i/d 1/4" (6 mm) thick	ft (m)	172 566	4022 13198		
(n) 22" (550 mm) i/d 1/4" (6 mm) thick	ft (m)	172 566	4165 13667		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
18.8 Shrouding of Tube Well Bore with Gravel				18.3.3 & 18.4.3	
18.8.1 Shrouding with graded pea gravel 3/8" (10 mm) to 1/8" (3 mm) around tubewell in bore hole complete as per specification:-	100 cft (m ³)	3122 1103	11207 3958		The rate includes wastage, etc.
18.9 Testing/Developing of Tube Well				18.3.5,1 8.3.6 &18.4.5	
18.9.1 Testing and developing of tubewell of size 6" i/d and above complete as per specifications:-					Compressor, accessories along with working staff, to be supplied by Railways.
(a) Upto 1.5 cusecs (42 l) discharge.	hr	786			
(b) Above 1.5 (42 l) cusecs discharge.	hr	951			
18.10 Supplying & Erecting DWT Pumps				18.4.6	
18.10.1 Supplying and erecting electric driven Deep Well Turbine Pump (PECO or KSB or Equivalent) alongwith electric motor of suitable H.P. coupled through hollow shaft, complete with accessories i.e. foot valve with strainer, suction pipe 10 ft (3 m) long, back valve with bypass connection, sluice valve, pressure gauge with cock and nipple, water meter of suitable size, star delta starter, main switch volt. and amp meter etc as per specification and / or as directed by the Engineer Incharge.					
(a) 25 H.P. Electric Driven D.W.T. Pump complete of 1 cusec (28 l) discharge at 128' head with 90' setting.	each	9075	251075		
(b) 35 H.P. Electric Driven D.W.T. Pump complete of 1-1/2 (42 l) cusecs discharge at 130' head with 90' setting.	each	9075	284075		
(c) 50 H.P. Electric Driven D.W.T. Pump complete of 2 cusecs (56 l) discharge at 30' head with 90' setting.	each	9075	322575		

CHAPTER 19**WATER SUPPLY**

Note:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 19 Water Supply System of " Technical Specification for Railway Infrastructure Works, Volume II, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.1 Providing & Laying Cast Iron Pipes				19.6.1, 19.7.1 to 19.7.6, 19.7.8, 19.7.9 & 19.8	
19.1.1 Providing, laying, cutting, jointing, testing and disinfecting grey cast iron spun pipes in trenches with spigot and socket, caulked lead joint (BS 416 Part-1), including cost of jointing material, such as lead, yarn, etc. complete as per specifications.					i) Cost of providing and installing specials is not included in the rate. ii) Labour includes the cost of jointing material
(a) 3" (75 mm) i/d	ft (m)	81.7 268	499 1637		
(b) 4" (100 mm) i/d	ft (m)	107.3 352	616 2022		
(c) 6" (150 mm) i/d	ft (m)	153 503	1121 3677		
(d) 8" (200 mm) i/d	ft (m)	182 596	1883 6177		
19.1.2 Providing, laying, cutting, jointing, testing and disinfecting grey cast iron (C.I) spun pipes in trenches with flanged joints (BS 2035), including cost of jointing materials such as nuts & bolts, rubber sheets etc. complete as per specifications.					i)Cost of providing and installing specials is not included in the rate. ii) Labour includes the cost of jointing material
(a) 3" (75 mm) i/d	ft (m)	37.2 122.1	454 1491		
(b) 4" (100 mm) i/d	ft (m)	40.8 134.0	550 1804		
(c) 6" (150 mm) i/d	ft (m)	61.4 201.6	1029 3376		
(d) 8" (200 mm) i/d	ft (m)	67.7 222.2	1769 5803		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.2 Providing & Fixing Cast Iron Specials/Fixtures				19.6.1, 19.7.1 to 19.7.6, 19.7.8, 19.7.9,1 9.7.14 & 19.8	
19.2.1 Providing and fixing cast iron special of BSS class "B" (such as bend, tee, cross collar, reducer, tail piece, flanged spigot, cap, flanged socket, taper, angle branch, plug, etc.) for cast iron pipe line, complete:-					
(a) C.I. S.S.Specials with spigot and socket joints:					
(i) 1-1/2" (38mm) to 4" (100mm) i/d	kg	127.9	202		
(ii) 6" (150 mm to 8 (200 mm)" i/d"	kg	88.1	163		
(b) C.I.flanged specials, with flanged joints:					
(i) 1-1/2" (38mm) to 4" (100mm) i/d	kg	117.6	192		
(ii) 6" (150mm) to 8" (200mm) i/d	kg	74.2	149		
19.2.2 Providing and fitting C.I./G.I. Flanges on pipes, including turning, threading, facing and fitting etc., complete in all respects:-					
(i) 1-1/2" (38mm) to 4" (100mm) i/d	kg	43.1	123		
(ii) 6" (150mm) to 8" (200mm) i/d	kg	88.8	168		
19.2.3 Cutting C.I. Pipe, and welding spigot or socket, flanged or tyton end, after finishing ends of pipes:-					
(a) 1-1/2" (38mm) to 4" (100mm) i/d	per inch i/d of pipe		88.4		
	per cm i/d		34.8		
(b) 6" (150mm) to 8" (200mm) i/d	-do- -do-		109.4 43.1		
19.2.4 Providing and fixing, fire hydrants B.S.S. quality and weight of 2-1/2" (65 mm) dia (including cost of jointing material):-	each	204	3504		Connecting pipes and special if used, will be paid extra.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.2.5 Providing and fixing sluice valve of BSS quality (BS 5163) and weight Class 'B' for cast iron pipeline (including cost of jointing material):-					
(a) Sluice Valve 3" (75 mm) i/d	each	847	6087		
(b) Sluice Valve 4" (100 mm) i/d	each	1029	7399		
(c) Sluice Valve 5" (125 mm) i/d	each	1815	9498		
(d) Sluice Valve 6" (150 mm) i/d	each	1997	10780		
19.2.6 Providing and fixing, air valve (Kitz Japan make or equivalent) 3" dia of B.S.S. quality and weight (BS 1074) complete with jointing material.					
(a) Single	each	60.5	3101		
(b) Double	each	60.5	5011		
19.2.7 Supplying and installation of Brass Non return valves (Kitz Japan make or equivalent) on pipe complete with jointing material.					
(a) size 12 mm (1/2") Ø dia	each	303	797.5		
(b) size 19 mm (3/4") Ø dia	each	303	963		
(c) size 25 mm (1") Ø dia	each	303	1238		
(d) size 38 mm (1-1/2") Ø dia	each	303	2833		
(e) size 50 mm (2") Ø dia	each	303	3603		
(f) size 75 mm (3") Ø dia	each	303	9393		
(g) size 100 mm (4") Ø dia	each	303	13823		
19.3 Providing & Laying Galvanized Iron (GI) Pipes				19.6.1, 19.7.1 to 19.7.6, 19.7.8, 19.7.10 & 19.8	
19.3.1 Providing, laying, cutting, jointing, testing and disinfecting GI pipeline in trenches, with socket joint, using GI pipes of B.S.S. Class 'B' working pressure ' (medium quality IIL or equivalent) including specials and valves etc. complete as per specifications.					i) Cost of sockets, tees, elbows, bends, crosses, unions and plugs etc., is included in the rates. ii) In case these items are to be operated for internal GI piping (1"
(a) 1/2" (15 mm) dia	ft (m)	6.78 22.2	62.9 206.3		
(b) 3/4" (20 mm) dia	ft (m)	7.77 25.5	79.8 262		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(c) 1" (25 mm) dia	ft (m)	9.43 30.9	97 317		3/4" and 1/2" dia) in bath room / laboratories, the composite rate be reduced by 8% and specials mentioned in note 1 above be paid under chapter 20.
(d) 1-1/4" (32 mm) dia	ft	9.55	152		
(e) 1-1/2" (40 mm) dia	ft (m)	9.61 31.5	176 578.6		
(f) 2" (50 mm) dia	ft (m)	10.06 33.0	241 791		
(g) 2-1/2" (65 mm) dia	ft (m)	10.55 34.6	306 1004		
(h) 3" (80 mm) dia	ft (m)	11.9 39.1	391 1282		
(i) 4" (100 mm) dia	ft (m)	13.3 43.5	557 1828		
(j) 5" (125 mm) dia	ft (m)	15.5 50.8	749 2457		
(k) 6" (150 mm) dia	ft (m)	15.8 51.7	882 2893		
19.3.2 Providing, laying, cutting, jointing, testing and disinfecting G.I. Pipe line in trenches, with flanged joints, using G.I. Pipe of B.S.S. class 'B' (medium quality ILL or equivalent including specials and valves etc. complete as per specifications.					
(a) G.I Flanged Joints					
(i) 1-1/2" (38 mm) i/d	ft (m)	9.73 31.9	186 610		
(ii) 2" (50 mm) i/d	ft (m)	9.73 31.9	253 829		
(iii) 2-1/2" (65 mm) i/d	ft (m)	10.54 34.6	318 1045		
(iv) 3" (75 mm) i/d	ft (m)	11.50 37.7	404 1324		
(v) 4" (100 mm) i/d	ft (m)	12.64 41.5	578 1897		
(vi) 6" (150 mm) i/d	ft (m)	18.1 59.3	904 2965		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.4 Providing and Laying Unplasticised Polyvinyle Chloride (UPVC) Pressure Pipes				19.6.1, 19.7.1 to	
19.4.1 Providing, laying, cutting, jointing, testing and disinfecting UPVC pressure pipeline in trenches (conforming to BS 3505 manufactured by Dadex/Beta or equivalent) jointed with socket, elbow, tee, bend and plug bend etc.manufactured by the respective manufacturer complete as per specifications.				19.7.6, 19.7.8, 19.7.12 & 19.8	Cost of sockets, tees, elbows, bends, crosses, unions and plugs etc., is included in the rates.
(a) UPVC Pressure Pipes Class B (6 Bar)					
(i) 3" (75 mm) i/d	ft (m)	6.49 21.3	140 461		
(ii) 4" (100 mm) i/d	ft (m)	8.54 28.0	194 635		
(iii) 5" (125 mm) i/d	ft (m)	10.22 33.5	271 890		
(iv) 6" (150 mm) i/d	ft (m)	10.22 33.5	379 1244		
(v) 8" (200 mm) i/d	ft (m)	14.4 47.4	582 1911		
(v) 10" (250 mm) i/d	ft (m)	20.04 65.8	1135 3725		
(v) 12" (300 mm) i/d	ft (m)	25.0 82.0	1573 5162		
(b) UPVC Pressure Pipes Class D (12 Bar)					
(i) 2" (50 mm) i/d	ft (m)	5.28 17.3	97.6 320		
(ii) 3" (75 mm) i/d	ft (m)	6.52 21.4	201 658		
(iii) 4" (100 mm) i/d	ft (m)	8.54 28.0	331 1086		
(iv) 5" (125 mm) i/d	ft (m)	10.22 33.5	484 1589		
(v) 6" (150 mm) i/d	ft (m)	10.29 33.7	710 2328		
(vi) 8" (200 mm) i/d	ft (m)	10.36 34.0	1080 3542		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.5 Providing and Laying Polypropylene Random Copolymer (PPRC) Pipes & Fittings				19.6.1, 19.7.1 to 19.7.8, 19.7.12 & 19.8	
19.5.1 Providing, laying cutting, jointing, testing PPRC pipeline in walls/trenches with pipes (confirming to DIN 8077/8078, PN 20 manufactured by Dadex/Beta or equivalent & fittings conforming to DIN 16962,PN25 of the same manufacturer) for cold/hot water supply systems including specials complete in all respect as per specifications.					Cost of sockets, tees, elbows, bends, crosses, unions and plugs etc., is included in the rates.
(i) 3/4" (20 mm) external dia, 32 mm internal dia	Rft (m)	19.6 64.3	108 353		
(ii) 1" (25 mm) external dia	Rft (m)	19.6 64.3	146 478		
(iii) 1-1/4" (32 mm) external dia	Rft (m)	19.6 64.3	345 1131		
(iv) 1-1/2" (40 mm) external dia	Rft (m)	19.6 64.3	523 1717		
(v) 2" (50 mm) external dia	Rft (m)	19.6 64.3	865 2836		
(vi) 2-1/2" (63 mm) external dia	Rft (m)	19.6 64.3	1287 4223		
19.6 Providing & Fixings Hand Pumps & Pressure Pipes					
19.6.1 Supplying and fixing 2-1/2" dia G.I. Pipe hand pump machine 3' long with brass accessories and iron handle etc. complete in all respect.	each	363	1463		The composite rate may be increase by 15% for every additional 1 ft length of the hand pump machine
19.6.2 Supplying and fixing perforated 1- 1/4" G.I. Pipe with brass strainer for hand pump, complete:-	ft of filter (m of filter)	215 706	386 1267		
19.6.3 S upplying and fixing plunger valves for hand pump complete.	each	121.0	1221		
19.6.4 Supplying and fixing brass cup for top and bottom and sleeves etc. for hand pump.	kg	151.3	481		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.6.5 Supplying and fixing leather cup bucket/rubber ring of plunger valve for hand pump.	each	60.5	193		
19.6.6 Hand pump and pressure pipe cutting pipes above 2" dia.	cut	142.2			
19.6.7 Threading pipe ends 1-1/2" to 4" dia.	each end	105.9			
19.6.8 Assembling 1-1/2" dia pressure pipe.	each end	383			
19.6.9 Boring and fixing 1-1/2" dia, pressure pipe:-					
(a) in ordinary soil	ft (m)	125.0 410			
(b) in clay	ft (m)	234 768			
(c) in shingle	ft (m)	343 1125			
19.6.10 Repair to hand pump, pulling out and refitting.	ft (m)	51.4 169			
19.7 Supply and Installation of Water Pumps					
19.7.1 Supplying and installation of Goldamatic water pumps complete in all respect, as per instructions of Engineer Incharge.					
(a) Model G1, 0.5 H.P motor 15 m suction & 30 m head (non automatic)	each	1210	10450		
(b) Model G2, 1 H.P motor, 21 m suction & 30 m head (non automatic)	each	1210	13530		
(c) Model G3, 2 H.P motor. 27 m suction & 35 m head (non automatic)	each	1210	16500		
(d) Model G4, 2.5 H.P motor. 38 m suction & 38 m head (non automatic)	each	1210	19580		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
19.8 Supply and installation of water storage tanks (polyethylene) Blue.					
19.8.1 Supplying and installation of vertical water storage tanks (polyethylene) blue (Dura or equivalent), complete in all respect, as per instructions of Engineer Incharge.					
(a) Size 200 gln capacity	each	1464	16314		
(b) Size 250 gln capacity	each	1464	18514		
(c) Size 300 gln capacity	each	1464	21814		
(d) Size 500 gln capacity	each	1464	27864		

CHAPTER 20**PLUMBING AND SANITARY INSTALLATIONS**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 20 Plumbing & Sanitary Installations of "Technical Specification for Railway Infrastructure Works, Volume II, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).
- (3) The rates include cutting and making good of the surface of walls, roofs, floors, etc. where necessary.

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.1 Providing & Fixing Water Closets, Urinals & other Sanitary ware				20.4 to 20.6, 20.7.1, to 20.7.3, 20.7.15, 20.8, & 20.9	The rates of sanitary ware included under subsection 20.1 are for best quality locally manufactured sanitary ware such as Sonex, Master, and Faisal or equivalent (Class A) as specified /approved by Engineer in-charge.
20.1.1 Providing and fixing glazed earthenware water closet european type, of approved make/size, excluding seat & cover complete in all respects:-					
(a) White	each	484	6521		
(b) Coloured	each	484	6895		
20.1.2 Providing and fixing double seat and cover only for european style water closet.					
(a) bakelite	each	6.30	886		
(b) plastic	each	6.30	501		
20.1.3 Providing and fixing white / coloured glazed earthenware water closet squatter type combined with foot rest, 19" measured between flushing rims complete in all respects.					
(a) White	each	375	1999		
(b) Coloured	each	393	2237		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.1.4 Providing and fixing white / coloured glazed earthenware water closet, squatter type, without foot rest, 19" measured between flushing rims complete in all respects.					
(a) White	each	393	1742		
(b) Coloured	each	393	1962		
20.1.5 Providing and fixing glazed earthenware flat back urinal complete in all respects.	each	439	3211		
20.1.6 Providing and fixing glazed earthenware low down flushing cistern 3 gallons (13.63 litres) capacity, including bracket set, copper connection, etc. complete in all respects.					
(a) white	each	439	2698		
(b) coloured	each	439	3028		
20.1.7 Providing and fixing low down flushing cistern 3 gallons (13.63 litres) capacity, including bracket set, copper connection, etc. complete in all respects.					
(a) white enamelled cast iron	each	439	3784		
(b) plastic	each	439	1818		
(c) stainless steel	each	439	1928		
20.1.8 Providing and fixing cast iron high level flushing cistern, including cost of bracket set, copper connection, etc complete in all respects.					
(a) 3 gallons (13.63 litres) capacity	each	469	1691		
(b) 1 gallons (4.55 litres) capacity	each	469	1966		
20.1.9 Providing and fixing choricum plated soap dish complete.	each	30.3	432		
20.1.10 Providing and fixing glazed earthenware soap dish complete.	each	30.3	322		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.1.11 Providing and fixing, chromium plated toilet paper holder complete.	each	40.3	557		
20.1.12 Providing and fixing chromium plated towel rail complete.					
(a) 60 cm (24") long and 2 cm (3/4") dia	each	40.3	667		
(b) 50 cm (20") long and 1.5 cm (1/2") dia	each	40.3	557		
(c) circular type	each	40.3	447		
20.1.13 Providing and fixing looking glass 5 mm thick, neatly fitted on masonry walls etc., as per instructions of Engineer In-charge complete.					
(a) Looking glass (Class A) with deodar wood frame	sft (m ²)	50.4 543	197 2120		
(b) Looking glass (Class A) without frame fitted on masonite sheet.	sft (m ²)	24.2 261	126 1355		
(c) Looking glass (Class A) with beveled edge frame.	sft (m ²)	24.2 261	159 1714		
(d) Looking glass (Class A) with plastic frame.	sft (m ²)	24.2 261	126 1355		
20.1.14 Providing and fixing glass shelf 60cm x 13 cm (24" x 5") with 5 mm thick glass complete.					
(a) with chromium plated brackets and railing	each	87.0	769		
(b) glass shelf only, without chromium plated brackets and railing.	each	60.5	281		
20.1.15 Providing and fixing glazed earthen ware shelf 60cm x 13 cm (24" x 5") with chromium plated bracket and railing.					
(a) white	each	87.0	604		
(b) coloured	each	87.0	494		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.1.16 Providing and fixing superior quality:-					
(a) plastic soap dish	each	30.3	212		
(b) plastic toilet paper holder	each	40.3	352		
(c) plastic towel rail	each	40.3	352		
(d) plastic shelf 60 x 13 cm (24" x 5") with bracket.	each	40.3	407		
20.1.17 Supplying and fixing, telephone shower with flexible pipe 4 ft (1.3 m) long, complete.					
(a) Plastic	each	121	1111		
(b) Chromium Plated	each	121	1727		
(c) Chromium Gold	each	121	2761		
20.1.18 Supplying and fixing Muslim shower with flexible pipe 3 ft (1m) long complete.					
(a) Plastic	each	121	1078		
(b) Chromium Plated	each	121	1881		
(c) Chromium Gold	each	121	2871		
20.1.19 Supplying and fixing wall shower of complete in all respect.					
(i) Plastic	each	121	1551		
(ii) Chromium Plated	each	121	1925		
(iii) Chromium Gold	each	121	2871		
20.1.20 Providing and fixing, shower rose Complete:-					
(a) Size 1/2" x 4" (5 mm x 100 mm)					
(i) Plastic	each	40.3	546		
(ii) Chromium Plated	each	40.3	1910		
(iii) Chromium Gold	each	40.3	2790		
(b) Size 3/4" x 6" (20mm x 150 mm)					
(i) Plastic	each	40.3	920		
(ii) Chromium Plated	each	40.3	2460		
(iii) Chromium Gold	each	40.3	3560		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.1.21 Supplying and fixing, flexible pipe 3 ft (1 m) long, for telephone shower, complete.					
(a) Plastic	each	48.4	323		
(b) Chromium Plated	each	48.4	598		
(c) Chromium Gold	each	48.4	1038		
20.1.22 Supplying and fixing, rose with handle for telephone shower, complete.	each	48.4	2468		
20.1.23 Providing and fixing glazed earthenware colored/white coupled set including WC, flushing tank, rubber connection and bacolite seat as per instructions of Engineer In-charge.					
(a) Bathroom coupled set Master or equivalent (White)	set	1210	16060		
(b) Bathroom coupled set Master or equivalent (Coloured)	set	1210	16610		
20.1.24 Providing and fixing bath room accessories set consisting of looking glass, shelf, towel rail, towel ring, toilet paper holder, soap dish and brush holder complete in all respects and as per instructions of Engineer Incharge.					
(a) Plastic	set	605	1925		
(b) Chrome Plated	set	1210	14165		
(c) Chrome Gold	set	1210	17412		
20.1.25 Providing and fixing bath cabinet of approved quality neatly fitted on masonry wall in toilets complete in all respect as instruction of Engineer in-charge.					
(a) Supreme quality (Class A)	each	121.0	2871		
(b) Good quality (Class B)	each	121.0	2321		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.2 Providing & Fixing Sinks, Wash Hand Basin, Bath Tubs				20.4 to 20.6, 20.7.4, 20.7.5, 20.7.16, 20.7.17 20.8,& 20.9	The rates of saintary ware included under subsection 20.2 are for best quality locally manufactured sanitary ware such as Sonex, Master, and Faisal or equivalent (Class A) as specified /approved by Engineer in-charge.
20.2.1 Providing and fixing 22" x 16" glazed earthenware wash hand basin including bracket set, waste pipe and waste coupling, etc. complete:-					
(i) white, with pedestal	each	484	5852		
(ii) coloured, with pedestal	each	484	5962		
(iii) white, without pedestal	each	439	3937		
(iv) coloured, without pedestal	each	439	4047		
20.2.2 Providing and fixing stainless steel sink, including bracket set, waste pipe and waste coupling, etc. complete:-					
(a) with single drain board size 105 x 45 cm (42"x18").	each	439	5656		
(b) with double drain board size 150 x 60 cm (60"x24")	each	439	15776		
20.2.3 Providing and fixing glazed earthenware sink, including bracket set, waste pipe and waste coupling complete.					
(a) 60 x 45 cm (24"x18")	each	439	5332		
(b) 37.5 x 45 cm (15"x18")	each	439	4452		
20.2.4 Providing and fixing, angle iron brackets for:-					
(a) wash hand basin and cistern.	each	60.5	941		
(b) sinks.	each	60.5	941		
20.2.5 Supplying and fixing, earthen ware pedestal for 22" x 16" wash hand basin of approved make /quality.	each	48.4	1148		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.2.7 Supplying and fixing, bath tub (5'x2.5'x1.2'5(1.5x0.75x0.375M) Complete with all acceries of approved quality / make.					
(a) Fiber Glass		3267	14817		
(b) Ecrylic		3267	18117		
20.3 Providing & Fixing Various Valves, Cocks & Traps				20.4 to 20.6, 20.7.18 to 20.7.21, 20.8,& 20.9	The rates of saintary ware included under subsection 20.3 are for best quality locally manufactured sanitary ware such as Sonex, Master, and Faisal or equivalent (Class A) as specified /approved by Engineer in-charge.
20.3.1 Providing and fixing, chromium plated stop cock, heavy of approved quality.					
(a) 3/4" (20mm)	each	40.33	1360		
(b) 1/2" (15mm)	each	40.3	1140		
20.3.2 Providing and fixing, chromium plated stop cock, heavy of approved quality					
(a) 3/4" (20mm) dia	each	40.3	535		
(b) 1/2" (15mm) dia	each	40.3	425		
20.3.3 Providing and fixing underground stop cock 1/2" (15mm) with chromium plated cover of approved quality.	each	56.5	474		
20.3.4 Providing & fixing, chromium plated bib cock of approved quality					
(a) 3/4" (20mm) dia	each	40.3	1085		
(b) 1/2" (15mm) dia	each	40.3	1030		
20.3.5 Providing and fixing chromium plated tee stop cock 1/2" (15mm) dia of approved quality.	each	40.3	1118		
20.3.6 Providing & fixing chromium plated mixing valve (large size), for wash hand basin, sink or shower of approved quality.	each	50.4	875		
20.3.7 Providing & fixing, gun metal gate valve (screwed) of approved quality.					
(a) 1-1/4" (30 mm) dia.	each	60.5	501		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) 1-1/2" (40 mm) dia.	each	60.5	556		
(c) 2" (50 mm) dia.	each	60.5	1106		
(d) 2-1/2" (65 mm) dia.	each	60.5	1271		
(e) 3" (75 mm) dia.	each	60.5	1711		
20.3.8 Providing and fixing, chromium plated or brass oxidised, swan neck cock 1/2" (15mm) dia of approved quality.					
(a) single way.	each	40.3	799		
(b) double way.	each	60.5	2096		
(c) three way.	each	80.7	2886		
20.3.9 Providing and fixing, union brass cock of approved quality					
(a) 1/2" (15mm) dia	each	40.3	425		
(b) 3/4" (20mm) dia	each	40.3	563		
20.3.10 Providing and fixing, floor trap of cast iron, of approved quality including concrete chamber all round, and C.I. grating:-					
(a) 4" x 2" (100 mm x 50 mm).	each	121.0	569		
(b) 4" x 3" (100 mm x 75 mm)	each	121.0	624		
20.3.11 Providing and fixing, 'P' trap, of approved quality including concrete chamber with G.I. grating:-					
(a) 4" (100 mm) of cast iron.	each	100.8	1877		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
(b) 4" (100 mm) glazed.	each	100.8	529		
20.3.12 Providing and fixing 4" (100 mm) gully trap, of approved quality including cement concrete cost of PVC grating 6" x 6" (150 x 150 mm) and masonry chamber 12" x 12" (300 x 300 mm).	each	151	872		
20.3.13 Providing and fixing, brass stop cock/bib cock of approved quality					
(a) 1/2" (15 mm) dia.	each	40.3	238		
(b) 3/4" (20 mm) dia.	each	40.3	425		
20.3.14 Providing and fixing, chromium plated bottle trap of approved quality with waste pipe, etc. of approved quality complete:-					
(a) 1-1/4" (30 mm) dia	each	60.5	853		
(b) 1-1/2" (40 mm) dia	each	60.5	963		
20.3.15 Providing and fixing, brass ball float valve of approved quality.					
(a) 1/2" (15 mm) dia.	each	50.4	600		
(b) 3/4" (20 mm) dia.	each	50.4	655		
(c) 1" (25 mm) dia.	each	50.4	765		
(d) 1-1/4" (30 mm) dia.	each	50.4	985		
(e) 1- 1/2" (40mm) dia.	each	50.4	1205		
(f) 2" (50 mm) dia.	each	50.4	1535		
20.3.16 Supplying and fixing, C.I. water hydrant/control valve of special type with brass spindle and detachable spanner required to be fixed with 2" (50 mm) to 3" (75 mm) dia pipe of approved quality. Also includes 3/4" (20 mm) dia G.I. bend complete.	each	48.4	3898		
20.4 Providing & Laying Soil, Waste and Vent Pipes				20.4 to 20.6, 20.8, & 20.9	
20.4.1 Providing & fixing, cast iron soil pipe of approved quality with:-					
(a) Lead caulked, yarn joint;					
(i) 4" (100 mm) dia	ft (m)	40.6 133	564 1850		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
(ii) 2" (50 mm) dia.	ft (m)	16.2 53.2	348.9 1145		
(b) Cement caulked joint;					
(i) 4" (100 mm) dia	ft (m)	10.60 34.8	523 1717		
(ii) 2" (50 mm) dia..	ft (m)	4.24 13.9	332 1088		
20.4.2 Providing and fixing, Asbestos Cement (A.C) / fiber cement. soil pipe (DADEX or equivalent) with cement caulked joint, including all specials complete in all respects.					
(a) 60 mm (2-1/4") i/d.	ft (m)	8.48 27.8	73.8 242		
(b) 80 mm (3-1/4") i/d.	ft (m)	9.42 30.9	148 487		
(c) 100 mm (4") i/d.	ft (m)	10.60 34.8	172 563		
(d) 150 mm (6") i/d.	ft (m)	14.14 46.4	249 816		
20.4.3 Providing and fixing, cast iron specials, such as tee, bend, collar, cross, etc. plain type of approved quality.					
(a) lead caulked joint	kg	75.0	187		
(b) cement caulked joint	kg	73.5	153		
20.4.4 Providing and fixing, uPVC Pipes for Soil, Waste & Vent System (DADEX or equivalent) including cost of all specials complete in all respects.					
(a) 40 mm (1-1/2") i/d	ft (m)	9.68 31.8	176 579		
(b) 50 mm (2") i/d	ft (m)	14.5 47.6	451 1478		
(c) 75 mm (3") i/d	ft (m)	19.4 63.5	799 2622		
(d) 110 mm (4-1/2") i/d	ft (m)	24.2 79.4	2179 7148		
(e) 160 mm i/d (6-1/2") i/d	ft (m)	29.0 95.3	639 2098		

Description	Unit	Rate (PKR)		Railways Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.5 Providing & Fixings C.I Manhole Covers				20.4 to 20.6, 20.7.22 20.8,& 20.9	
20.5.1 Supplying and fixing, cast iron manhole cover with frame, etc. (Heavy Type) of approved quality complete.					
(b) 18" (450 mm) dia.	each	60.5	1216		
(c) 24" (600 mm) dia.	each	80.7	1896		
20.5.2 Supplying & fixing, C.I. manhole cover without frame, heavy type of approved quality complete.					
(a) 12" (300 mm) dia.	each		495		
(b) 18" (450 mm) dia.	each		1155		
(c) 24" (600 mm) dia.	each		1815		
20.6 Providing & Laying RCC Pipe in Trenches				21.4 to 21.6	
20.6.1 Providing, laying, cutting, jointing and testing of R.C.C. pipe 4" (100mm) dia in 1:1-1/2 3, in cement concrete, laid in trenches as per specifications complete in all respects.	ft (m)	20.3 66.6	130 427		
20.7 Providing & Laying G.I Pipe Fittings				19.6.1, 19.7.1 to 19.7.6, 19.7.8, 19.7.10 & 19.8	
20.7.1 Supplying and fixing, G.I. pipe fittings such as, socket, nipple, elbow, check nut and plug (ordinary or reducing) of approved quality as per specifications and complete in all respects.					
(a) 1/2" (15 mm) dia.	each	13.31	35.3		
(b) 3/4" (20 mm)dia.	each	13.31	46.3		
(c) 1" (25 mm)dia.	each	15.1	92.1		
(d) 1-1/4" (30 mm) dia.	each	30.3	116		
(e) 1-1/2" (40 mm) dia.	each	33.9	135		
(f) 2" (50 mm) dia.	each	33.9	204		
(g) 2-1/2" (62 mm)dia.	each	33.9	353		
(h) 3" (75 mm) dia.	each	38.7	572		
(i) 4" (100 mm) dia.	each	54.5	835		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.7.2 Supplying and fixing G.I. Bend, bush, crosspleces and Tees (ordinary or reducing) of approved quality complete in all respects.					
(a) 1/2" dia.	each	21.8	80.1		
(b) 3/4" dia.	each	21.8	101		
(c) 1" dia.	each	24.2	162		
(d) 1-1/4" dia.	each	34.5	265		
(e) 1-1/2" dia.	each	36.3	344		
(f) 2" dia.	each	39.3	567		
(g) 2-1/2" dia.	each	39.3	1051		
(h) 3" dia.	each	42.4	1439		
(i) 4" dia.	each	54.5	2804		
20.7.3 Supplying and fixing, G.I. Union nuts, wheel valves, sluice valves, etc of approved quality complete in all respects.					
(a) 1/2" dia.	each	21.8	110		
(b) 3/4" dia.	each	21.8	137		
(c) 1" dia.	each	24.2	184		
(d) 1-1/4" dia.	each	34.5	260		
(e) 1-1/2" dia.	each	36.3	344		
(f) 2" dia.	each	39.3	479		
(g) 2-1/2" dia.	each	39.3	974		
(h) 3" dia.	each	42.4	1285		
(i) 4" dia.	each	54.5	2386		
20.8 Miscellaneous Items					
20.8.1 Providing and fixing, chromium plated waste coupling of approved quality.					
(a) 3 cm (1-1/4").	each	60.5	204		
(b) 4 cm (1-1/2").	each	60.5	259		

Description	Unit	Rate (PKR)		Railways Speci- fication	Remarks
		Labour	Composite		
1	2	3	4	5	6
20.8.2 Providing and fixing, rubber plug with chain of approved quality.					
(a) 3 cm (1-1/4").	each	2.42	90.4		
(b) 4 cm (1-1/2").	each	2.42	90.4		
20.8.3 Providing and fixing, waste pipe of PVC of approved quality.					
(a) 3 cm (1-1/4").	each	30.3	63.3		
(b) 4 cm (1-1/2").	each	30.3	74.3		
20.8.4 Providing and fixing, flushing bend of PVC of approved quality.					
(a) 3 cm (1-1/4").	each	26.9	81.9		
(b) 4 cm (1-1/2").	each	26.9	70.9		
20.8.5 Providing and fixing, 1.5 cm (1/2") dia connection including check nuts etc of approved quality.					
(a) Plastic/rubber connection.	each	24.2	222		
(b) copper connection.	each	24.2	332		

CHAPTER 21**SEWERAGE & RCC PIPE SEWERS**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 21 Sewerage & RCC Pipe Sewers of "Specification for Railway Infrastructure Works, Volume II, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
21.1 Providing & Laying Reinforced Concrete (RCC) Pipes in Trenches				21.4 to 21.6	
21.1.1 Providing and laying R.C.C. pipe, moulded with cement concrete 1:1-1/2:3, with spigot, socket or collar joint, etc. including cost of reinforcement, conforming to B.S. 5911: Part-I, 1981 Class "L" including carriage, lowering in trenches to correct alignment and grade, jointing, cutting pipe where necessary, finishing and testing, etc. complete:-					
(a) 4"(100 mm) i/d.	ft (m)	25.2 82.7	141 464		
(b) 6" (150 mm) i/d.	ft (m)	30.3 99.3	207 679		
(c) 9" (225 mm) i/d	ft (m)	56.5 185	275 901		
21.1.2 Providing & laying R.C.C. pipe sewers, moulded with cement concrete 1:1-1/2:3 conforming to ASTM specification C-76-79, Class II, Wall B, including carriage, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc. complete:-					
(a) 12" (300 mm) i/d.	ft (m)	57.5 189	431 1416		
(b) 15" (375 mm) i/d.	ft (m)	71.8 236	512 1679		
(c) 18" (450 mm) i/d.	ft (m)	86.2 283	691 2268		
(d) 21" (525 mm) i/d.	ft (m)	107.8 353.6	828 2718		
(e) 24" (600 mm) i/d.	ft (m)	123.2 404	981 3219		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(f) 27" (685 mm) i/d.	ft (m)	184 602	1421 4662		
(g) 30" (760 m m) i/d	ft (m)	220 723	1507 4945		
(h) 33" (840 mm) i/d.	ft (m)	275 903	1667 5469		
(i) 36" (910mm) i/d.	ft (m)	339 1112	2077 6814		
(j) 42" (1070 mm) i/d.	ft (m)	440 1445	2805 9205		
(k) 48" (1220mm) i/d.	ft (m)	840 2756	3359 11021		
(l) 54" (1370 mm) i/d.	ft (m)	1176 3859	4509 14794		
(m) 60" (1520 mm) i/d.	ft (m)	1470 4824	5595 18358		
(n) 66" (1680 mm) i/d.	ft (m)	2352 7718	6730 22082		
(o) 72" (1830 mm) i/d.	ft (m)	2940 9647	8396 27548		
21.1.3 Providing & laying R.C.C. pipe sewers, moulded with cement concrete 1:1-1/2:3 conforming to ASTM specification C-76-79, Class III, Wall B, including carriage, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc. complete:-					
(a) 12" (300 mm) i/d.	ft (m)	57.5 189	437 1434		
(b) 15"(375 mm) i/d.	ft (m)	71.8 236	523 1715		
(c) 18" (450 mm) i/d.	ft (m)	86.2 283	697 2286		
(d) 21" (525 mm) i/d.	ft (m)	107.8 354	955 3133		
(e) 24" (600 mm) i/d.	ft (m)	123.2 404	1355 4446		
(f) 27" (690 mm) i/d.	ft (m)	184 602.1	1465 4807		
(g) 30" (760 mm) i/d.	ft (m)	220 723	1529 5017		
(h) 33" (840 mm) i/d.	ft (m)	275 903	1722 5649		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(i) 36" (910 mm) i/d.	ft (m)	339 1112	2132 6994		
(j) 42" (1070 mm) i/d.	ft (m)	440 1445	2981 9782		
(k) 48" (1220 mm) i/d.	ft (m)	840 2756	3524 11563		
(l) 54" (1370 mm) i/d.	ft (m)	1176 3859	4564 14975		
(m) 60" (1520 mm) i/d.	ft (m)	1470 4824	5760 18899		
(n) 66" (1680 mm) i/d.	ft (m)	2352 7718	7104 23309		
(o) 72" (1830 mm) i/d.	ft (m)	2940 9647	8836 28992		
21.1.4 Providing & laying R.C.C. pipe moulded with cement concrete 1:1-1/2:3 conforming to ASTM specification C-76-79, Class II, Wall B, fixed with R.C.C. collar for culvert, bridges etc., including carriage, lowering in trenches to correct alignment and grade, cutting pipes where necessary, gape filled with cement concrete 1:2:4 complete in all respect:-					
(a) 12" (310 mm) i/d.	ft (m)	57.5 189	431 1416		
(b) 15" (380 mm) i/d.	ft (m)	71.8 236	512 1679		
(c) 18" (460 mm) i/d.	ft (m)	86.2 283	691 2268		
(d) 21" (530 mm) i/d.	ft (m)	107.8 354	828 2718		
(e) 24" (610 mm) i/d.	ft (m)	123.2 404	981 3219		
(f) 27" (690 mm) i/d.	ft (m)	184 602	1421 4662		
(g) 30" (760 mm) i/d.	ft (m)	220 723	1507 4945		
(h) 33" (840 mm) i/d.	ft (m)	275 903	1667 5469		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(i) 36" (910 mm) i/d.	ft (m)	339 1112	2077 6814		
(j) 42" (1070 mm) i/d.	ft (m)	440 1445	2805 9205		
(k) 48" (1220 mm) i/d.	ft (m)	840 2756	3359 11021		
(l) 54" (1370 mm) i/d.	ft (m)	1176 3859	4509 14794		
(m) 60" (1520 mm) i/d.	ft (m)	1470 4824	5595 18358		
(n) 66" (1680 mm) i/d.	ft (m)	2352 7718	6730 22082		
(o) 72" (1830 mm) i/d.	ft (m)	2940 9647	8396 27548		
21.2 Providing & Laying Non Reinforced Concrete Pipes in Trenches				21.4 to 21.6	
21.2.1 Providing and laying non-reinforced concrete pipe moulded with cement concrete 1:1-1/2:3 conforming to ASTM Specification C-14-73, Class-2, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing, cutting pipe where necessary, finishing and testing, etc. complete:-					
(a) 4" (100 mm) i/d.	ft (m)	25.2 82.7	75.4 247		
(b) 6" (150 mm) i/d.	ft (m)	30.3 99.3	102 336		
(c) 8" (200 mm) i/d.	ft (m)	42.4 139	129 422		
(d) 9" (225 mm) i/d.	ft (m)	56.5 185	157 515		
(e) 10" (250 m m) i/d.	ft (m)	61.5 202	179 586		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
21.3 Lowering of Sub Soil Water Table & Laying of Pipe Sewers in Trenches				21.4 to 21.6	
21.3.1 Lowering of sub soil water table, by installation of tubewells along sewer line for laying of pipe sewer in trenches complete in all respects.					(i) This rate shall be payable, in addition to the item of excavation below SSWL for sewers & manholes under chapter, earthwork and laying of sewer pipe under items 21.1 and 21.2
(a) 0-1 ft. (0-0.300 m) below SSWL.	ft (m of laid sewer)		215 705		
(b) 0-2 ft. (0-0.600 m) below SSWL.	-do-		417 1368		(ii) The grant of these rates shall be subject to approval of Chief Engineer.
(c) 0-3 ft. (0- 0.900 m)below SSWL.	-do-		691 2267		(iii) The rate includes cost of providing pumps, POL,
(d) 0-4 ft. (0-1.200 m) below SSWL.	-do-		987 3238		
(e) 0-5 ft. (0-1.500 m) below SSWL.	-do-		1395 4576		and all operation charges at the site of work etc.
(f) 0-6 ft. (0-1.800 m) below SSWL.	-do-		1725 5660		
(g) 0-7 ft. (0-2.100 m) below SSWL.	-do-		2086 6845		
(h) 0-8 ft. (0-2.400 m) below SSWL.	-do-		2364 7756		
(i) 0-9 ft. (0-2.700 m) below SSWL.	-do-		2493 8178		
(j) 0-10 ft. (0-3.000 m) below SSWL.	-do-		2869 9412		
(k) 0-11 ft. (0-3.300 m) below SSWL.	-do-		3186 10452		
(l) 0-12 ft. (0-3.600 m) below SSWL.	-do-		3525 11567		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
21.4 Construction Gully Grating Chamber with Gully Trap				21.4 to 21.6	
21.4.1 Constructing gully grating chamber, 12"x 12" (300 mm x300 mm) complete in all respects:-					Pipe connection to be paid separately.
(a) With C.I. Gully Trap, weighing 81 lbs, frame hinged safety type.	each	2373	3127		
(b) Concrete Gully Trap.	each	1252.6	3233		
21.5 Providing Manhole Chambers & Manhole Covers				21.4 to 21.6	
21.5.1 Extra for making and finishing benching floor work in manhole chamber, with 1/8" (3 mm) thick cement finish.	100 sft (m²)	1256.0 135	1712 184		
21.5.2 Providing and fixing 1-1/4" x 1-1/4" x 3/16" angle iron step in manhole chambers, including carriage and setting the same in work to correct lines and levels.	each	60.40	204		
21.5.3 Fixing manhole frame and cover in R.C.C. slab, including carriage to site.	set	266			
21.5.4 Providing and fixing 3" (75 mm) thick R.C.C. manhole cover 22" (550 mm) dia with tee shaped C.I. Frame of 20" (500 mm) clear i/d (frame weighing 37.324 KG or one maund) as per H.Q.E. Sketch No.3295 complete in all respects.	set	296	2875		
21.5.5 Providing and fixing "6 thick R.C.C. manhole cover with 3" x 3" x 1/4" angle iron frame 22" i/d as per H.Q.E. Sketch No.3297 complete in all respects.	set	463	4168		
21.5.6 Providing and fixing "6 thick R.C.C. manhole cover with 3" x 3" x 1/4" angle iron frame 24" i/d as per H.Q.E. Sketch No.3297 complete in all respects.	set	295	3999		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
21.6 Desilting of Disposal Works, Collecting Tanks & Wells					
21.6.1 Desilting of disposal work collecting tank, including removal of sludge within 3 chains (90 m).	100 cft (m ³)		467 165		
21.6.2 Silt clearing 10' (3 m) dia. wells and					
(a) Upto 10' (3 m) depth of slush.	well	6556			
(b) Beyond 10' (3 m) depth of slush.	well	13119			

CHAPTER 22**SUI GAS**

Notes:-

- (1) The items of work included in this chapter, shall conform to the relevant specifications, given in Chapter 23 Sui Gas Supply System of "Specification for Railway Infrastructure Works, Volume II, (2016)"
- (2) Rates for all finished works include the removal of surplus debris, unused material and by-products and their stacking within 100 ft (30 m).
- (3) The rates include cutting and making good of the surface of walls, roofs, floors, etc. where necessary.
- (4) All materials should conform to specifications of Sui Northern Gas Pipeline & Sui Southern Gas Pipeline Companies.

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
22.1 Supplying & Laying High Pressure Sui Gas Pipeline				23.4 to 23.6	
22.1.1 Supplying, laying, cutting, jointing and welding in position high pressure sui gas pipe line (class medium of IIL or equivalent) wrapped with fiber sheet & coated with approved bitumen compound complete in all respect as per specification. One wrap two coats;					The rate does not include digging and back filling of trenches which is payable separately.
(a) 1" (25 mm) dia Pipe (M.S. Pipe 8 SWG).	ft (m)	22.1 72.5	90 295		
(b) 1-1/2" (38 mm) dia Pipe (M.S. Pipe 8 SWG).	ft (m)	31.8 104.3	130 427		
(c) 2" (50 mm) dia Pipe (M.S. Pipe 7 SWG).	ft (m)	33.5 109.9	169 555		
(d) 3" (75 mm) dia Pipe (M.S. Pipe 6 SWG).	ft (m)	40.1 132	257 842		
(e) 4" (100 mm) dia Pipe (M.S. Pipe 5 SWG).	ft (m)	49.7 163	356 1169		
(f) 6" (150 mm) dia Pipe (M.S. Pipe 5 SWG).	ft (m)	63.8 209	567 1861		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
22.2 Supplying & Laying Low Pressure Sui Gas Pipeline				23.4 to 23.6	
22.2.1 Supplying, laying, cutting and jointing in position low pressure sui gas pipe line for internal fittings (G.I. Pipe, class medium of IIL) complete in all respect as per specification.					(i) The rate includes making & repairing holes in wall and roof etc.
(a) 1/2" (12.5 mm) dia	ft (m)	10.22 33.5	66.3 217.6		(ii) Cost of sockets, tees, elbows, union, reducers, nipples etc. is included in the rates.
(b) 3/4" (19 mm) dia	ft (m)	10.22 33.5	83.2 273		
(c) 1"(25 mm) dia	ft (m)	12.16 39.9	103 339		
(d) 1-1/4" (31 mm) dia	ft (m)	12.16 39.9	149 490		
(e) 1-1/2" (38 mm) dia	ft (m)	14.1 46.3	171 561		
(f) 2" (50 mm) dia	ft (m)	20.0 65.6	239 786		
22.3 Supplying & Fixing in Position Sui Gas Appliances & Their Fittings				23.4 to 23.6	
22.3.1 Supplying & fixing in position approved quality Sui Gas Burners:-					
(a) Single Burner.	each	242	1067		
(b) Double Burner.	each	242	1947		
(c) Commercial Burner;					
(i) 12 Nozzles.	each	242	2167		
(ii) 18 Nozzles.	each	242	2607		
(iii) 24 Nozzles.	each	242	3102		
(iv) 32 Nozzles.	each	242	3762		
22.3.2 Supplying and fixing Sui Gas lamp of superior quality including bracket complete.	each	242	765		
22.3.3 Supplying and fixing in position approved quality Sui Gas room heaters of superior quality with exhaust etc:-					

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(a) Single Plate.	each	484	3454		
(b) Double Plate.	each	484	6754		
22.3.4 Providing and fixing in position Sui gas water heater best quality manufacturer with fittings including thermostat, safety valve etc.:					
(a) 35 Gallon capacity.	each	968	17468		
(c) 55 Gallon capacity.	each	968	33968		
22.3.5 Providing and fixing in position approved quality Instant Gas water heaters with fittings including thermostat, safety valve etc:-					
(a) 6 Gallon capacity.	each	968	10318		
(b) 12 Gallon capacity.	each	968	14718		
22.3.6 Supplying and fixing in position approved quality Sui Gas cooking range:-					
(a) Three Burners.	each	363	17963		
(b) Five Burners.	each	363	20163		
22.3.7 Providing and fixing Bunsen burner, complete.	each	60.5	446		
22.3.8 Supplying and fixing in position approved quality fittings of Sui Gas appliances:-					
(a) Black pipe for single burner.	each	60.5	77		
(b) Black pipe for double burner.	each	60.5	78		
(c) Jet.	each	60.5	71.5		
(d) C.I. Tikkee.	each	60.5	127		
(e) C.I. Grating.	each	60.5	149		
(f) Bush	each	60.5	93.5		
(g) Regulator Plug.	each	60.5	82.5		
(h) Copper pipe for pilot burner.	each	60.5	259		
(i) Peeble regulator.	each	60.5	446		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(j) Regulator 043.	each	60.5	2371		
(k) Regulator 143.	each	60.5	4131		
(l) Exhaust for room heater.	each	484.0	1144		
(m) Thermostat for water heater.	each	605.0	2365		
(n) Knob.	each	60.5	105		
(o) Radiant plate for heater.	each	60.5	446		
22.4 Supplying & Fixing in Position Valves/Cocks etc.				23.4 to 23.6	
22.4.1 Supplying and fixing in position approved quality ball valve (Kitz Japan):-					
(a) 1/2" dia.	each	121.0	836		
(b) 3/4" dia.	each	121.0	1056		
(c) 1" dia.	each	121.0	1221		
(d) 1-1/2" dia.	each	121.0	1716		
(e) 2" dia.	each	121.0	2156		
22.4.2 Supplying and fixing in position approved quality Audco type valve or Eclips cocks:-					
(a) 3/4" dia.	each	60.5	336		
(b) 1" dia.	each	121.0	562		
(c) 1-1/2" dia.	each	121.0	674		
(d) 2" dia.	each	121.0	894		
22.4.3 Making connection with existing Sui Gas Pipe line complete in all respect.	per in dia per conection per cm dia per conection	793 312	870 342		
22.4.4 Providing & fixing Brass cocks, complete 1/4":-					
(a) One way.	each	60.5	336		
(b) Two way.	each	60.5	446		

CHAPTER 23**MISCELLANEOUS**

Note:-

- (1) Rate for all finished works include the removal of surplus debris, unused material and by products and their stacking within 100 ft (30 m).

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
23.1 Miscellaneous Items					
23.1.1 Notice board made of cement sand moter 1:3.	sft (m ²)	30.3 326	39.6 427		The board is to be of cement plaster 1/2" thick, with 2" wide and 1" thick beading.
23.1.2 Fixing handles to iron hammer.	each	151.3			
23.1.3 Supplying Bamboo Jhandies 10' to 12' with iron shoes, and flags 15" square.	each	62.9	261		
23.1.4 Supplying wooden pegs for levelling 1-1/2" dia 6" long.	each	6.05	6.56		
23.1.5 Supplying wooden pegs for alignment, 2" to 3" dia. 9" long.	each	12.10	14.2		
23.1.6 Fixing enamelled iron gauges flush with masonry including cost of hooks.	ft (m)	84.7 278	89.7 294		
23.1.7 Placing boundary pillars in position, including digging pits.	each	56.5			
23.1.8 Fixing mainline type distance mark in position including making 1:3:6 cement concrete base block size 14" x 10" x 15".	each	242	426		Composite rate does not include cost of iron distance marks.
23.1.9 Washing Niwar of bed.	per bed	545	568		
23.1.10 Washing Durries.	sft (m ²)	7.26 78.2	7.81 84.1		
23.1.11 Recaning chairs:-					
(a) Office chairs, single caning seat only.	each	484	528		
(b) Office chairs, double caning seat only.	each	639	699		
(c) Office chairs, single caning back only.	each	415	437		

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
(d) Office chairs, double caning back only.	each	605	649		
(e) Easy chairs, single caning seat only.	each	726	787		
(f) Easy chairs, double caning seat only.	each	968	1056		
(g) Easy chairs, single caning only back and seat in one piece.	each	1936	2123		
(h) Easy chairs, double caning back and seat in one piece or couches with caned area about 16 sft.	each	2904	3399		
23.1.12 Making and fixing hat pegs fixed on wooden strip 4" wide 3/4" thick at 9" spacing including polishing complete:-					Rate be reduced/ increased by 17% for each peg if number of pegs are reduced /increased.
(a) 4 No. ordinary shisham wooden pegs.	each	145	449		
(b) 4 No special alloy pegs on deodar wood strip.	each	121.0	552		
23.1.13 Weaving charpy.	each	330			
23.1.14 Sweeping chimneys.	each	182	195		
23.1.15 Cutting fuel wood, from plantation.	100 kg	195			
23.1.16 Splitting fuel wood.	100 kg	389			
23.1.17 Filling cement bags with coal and sewing (including cost of strings).	cft (m ³)	18.6 657	18.7 662		
23.1.18 Supplying manure.	cart load	108.9	219		Capacity of cart 20 cft.
23.1.19 Washing punkha frills.	each	182			
23.1.20 Washing:-					
(a) Table cloth	each	45.4			
(b) Napkins, dusters, etc.	each	27.9			
(c) Bed sheet	each	72.6			
(d) Carpet	sft	7.26			
23.1.21 Hoisting and placing sleepers for centering including carriage within one chain.	each	72.6			

Description	Unit	Rate (PKR)		Railway Specification	Remarks
		Labour	Composite		
1	2	3	4	5	6
23.1.22 Dismantling sleepers from centring including stacking within one chain.	each	87.1			
23.1.23 Dredging Sumps.	shift	2723			Not less than five gangmen to be employed for each shift to ensure effective dredging.
23.1.24 Fixing 'U' bolt in masonry or concrete, including levelling and tying for fixing angle iron post.	each	290			
23.1.25 Drilling holes in R.C. Trough.	each	176			

Bibliography

Government Publications

1. Composite Schedule of Rates, Standing Rates Committee, Finance Department, Government of Punjab.
2. Composite Schedule of Rates, National Highway Authority, Ministry of Communications, Government of Pakistan.
3. Pakistan Railways, Composite Schedule of Rates, 2003
4. Pakistan Western Railway, Analysis of Rates for Revised Schedule of Rates, 1954
5. Monthly Statistical Bulletins, Bureau of Statistics, Government of Pakistan
6. Publications, Pakistan Institute of Cost and Contracts,
7. Monthly Price Index, National Engineering Services Pakistan (Pvt) Ltd.

Reference Books

1. Construction Planning, Equipment and Methods, Peurifoy, 2009
2. Estimating and Costing in Civil Engineering, Theory and Practice, B.N. Dutta, 1996

Company Brochures of Different Manufacturers

1. Beta Plastic Pipes- Company Brochure
2. Dadex Pipes- Company Brochure
3. Envicrete Pavers, Company Brochure
4. IIL Karachi GI Pipes, Company Brochure and Rates
5. Interwood, Company Brochure
6. Izhar Sons, Company Brochure
7. Rack Tiles, Company Brochure and Rates
8. Shalimar RCC Pipes, Company Brochure
9. Market Surveys

